

MAIL TO:

STATE OF UTAH
 DIVISION OF PURCHASING
 3150 STATE OFFICE BUILDING, CAPITOL HILL
 P.O. BOX 141061
 SALT LAKE CITY, UTAH 84114-1061
 TELEPHONE (801) 538-3026
<http://purchasing.utah.gov>

Invitation to BidSolicitation Number: **PM6003**Due Date: **07/20/05 at 2:00 PM**

Date Sent: June 29, 2005

Agency Contract

Goods and services to be purchased:

OPHIR CANYON PROJECT - 143 MINE CLOSURES**Must Complete**

Company Name		Federal Tax Identification Number	
Ordering Address	City	State	Zip Code
Remittance Address (if different from ordering address)	City	State	Zip Code
Type <input type="checkbox"/> Corporation <input type="checkbox"/> Partnership <input type="checkbox"/> Proprietorship <input type="checkbox"/> Government	Company Contact Person		
Telephone Number (include area code)	Fax Number (include area code)		
Company's Internet Web Address	Email Address		
Discount Terms (for bid purposes, bid discounts less than 30 days will not be considered)	Days Required for Delivery After Receipt of Order (see attached for any required minimums)		
<p>The following documents are included in this solicitation: Solicitation forms, instructions and general provisions, Terms and Conditions, and specifications. <u>Please review all documents carefully before completing.</u></p> <p>The undersigned certifies that the goods or services offered are produced, mined, grown, manufactured, or performed in Utah. Yes_____ No_____. If no, enter where produced, etc._____</p>			
Contractor License Number	Contractor License Expiration Date	Contractor Class Title	Contractor Class Number
CONTRACTOR MUST BE A LICENSED CONTRACTOR IN THE STATE OF UTAH TO BID FOR THIS PROJECT. SEE WWW.PURCHASING .UTAH.GOV CURRENT BIDS CONTRACTOR CLASSIFICATION FOR CURRENT CLASSIFICATION CODES.			
Offeror's Authorized Representative's Signature		Date	
Type or Print Name		Position or Title	

STATE OF UTAH
DIVISION OF PURCHASING

Invitation to Bid

Solicitation Number: PM6003

Due Date: 06/29/05

Vendor Name:

Description	Bid Total
Ophir Canyon Mine Project work consists of 143 mine closures per specifications.	\$

THIS IS A FORMAL BID, THEREFORE NO FAXED RESPONSES WILL BE ACCEPTED

REQUIREMENTS:

AN OPTIONAL PRE-BID ONSITE MEETING WILL BE HELD FOR ALL BIDDERS ON WEDNESDAY, JULY 6, 2005. at 10:00 am. Meet at the turnoff to the town of Ophir, the Ophir Town Site Road off Highway 73. The meeting is expected to last most of the day - high clearance four-wheel-drive vehicles are recommended.

Work must be completed 70 days from receipt of notification.

Specifications available from DOGM for a \$20.00 fee. Contact Amber Fortner at 801-538-5437

BONDS:

A 5% bid bond will be required at the time of bid submission and a 100% performance/payment bond will be required of the successful bidder. **A completed bond statement must be submitted with each bid.**

CHANGES OR MODIFICATIONS TO PROCUREMENT:

Any modification to this procurement effort shall be made in writing by addendum issued by the state division of purchasing. Only authorized and properly issued addenda shall constitute the official position of the state and shall be binding. Anyone submitting a response to this solicitation, with basis in or on other communication or information received from sources other than through official addendum, assumes full risk including the possibility of a determination of non-responsiveness and may be rejected at the sole discretion of the state.

QUESTIONS:

For questions regarding the specifications, please contact Amber Fortner at 801-538-5437

For bid processing questions, please contact Paul Mash at 801-538-3138

Reference: RX 560 52000000008

Commodity Code: 96273

INVITATION TO BID - INSTRUCTION AND GENERAL PROVISIONS

1. BID PREPARATION: (a) All prices and notations must be in ink or typewritten. (b) Price each item separately. Unit price shall be shown and a total price shall be entered for each item bid. Errors may be crossed out and corrections printed in ink or typewritten adjacent and must be initialed in ink by person signing quotation. (c) Unit price will govern, if there is an error in the extension. (d) Delivery time is critical and must be adhered to as specified. (e) Wherever in this document an item is defined by using a trade name of a manufacturer and/or model number, it is intended that the words, "or equivalent" apply. "Or equivalent" means any other brand that is equal in use, quality, economy and performance to the brand listed as determined by the Division of Purchasing & General Services (DIVISION). If the vendor lists a trade name and/or catalog number in the bid, the DIVISION will assume the item meets the specifications unless the bid clearly states it is an alternate, and describes specifically how it differs from the item specified. All bids must include complete manufacturer's descriptive literature if quoting an equivalent product. All products are to be of new, unused condition, unless otherwise requested in this solicitation. (f) By signing the bid the vendor certifies that all of the information provided is accurate, that they are willing and able to furnish the item(s) specified, and that prices quoted are correct. (g) This bid may not be withdrawn for a period of 60 days from bid due date.

2. SUBMITTING THE BID: (a) The bid must be signed in ink, sealed in a properly addressed envelope, and delivered to the DIVISION OF PURCHASING (DIVISION), 3150 State Office Building, Capitol Hill, Salt Lake City, UT 84114-1061 by the "Due Date and Time." **The "Bid Number" and "Due Date" must appear on the outside of the envelope.** (b) Bids, modifications, or corrections received after the closing time on the "Due Date" will be considered late and handled in accordance with the Utah Procurement Rules, section R33-3-109. (c) **Your bid will be considered only if it is submitted on the forms provided by the state. Facsimile transmission of bids to DIVISION will not be considered.** (d) All prices quoted must be both F.O.B. Origin per paragraph 1.(c) and F.O.B. Destination. Additional charges including but not limited to delivery, drayage, express, parcel post, packing, cartage, insurance, license fees, permits, costs of bonds, or for any other purpose must be included in the bid for consideration and approval by the DIVISION. Upon award of the contract, the shipping terms will be F.O.B. Destination with all transportation and handling charges paid by the Contractor, unless otherwise specified by the DIVISION.

3. SOLICITATION AMENDMENTS: All changes to this solicitation will be made through written addendum only. Bidders are cautioned not to consider verbal modifications.

4. PROPRIETARY INFORMATION: Suppliers are required to mark any specific information contained in their bid which is not to be disclosed to the public or used for purposes other than the evaluation of the bid. Each request for nondisclosure must be accompanied by a specific justification explaining why the information is to be protected. Pricing and service elements of any bid will not to be considered proprietary. Bids submitted may to be reviewed and evaluated by any persons at the discretion of the state.

5. SAMPLES: Samples of item(s) specified in this bid, when required by DIVISION, must to be furnished free of charge to DIVISION. Any item not destroyed by tests may, upon request made at the time the sample is furnished, to be returned at the bidder's expense.

6. WARRANTY: The contractor agrees to warrant and assume responsibility for all products (including hardware, firmware, and/or software products) that it licenses, contracts, or sells to the State of Utah under this contract for a period of one year, unless otherwise specified and mutually agreed upon elsewhere in this contract. The contractor (seller) acknowledges that all warranties granted to the buyer by the Uniform Commercial Code of the State of Utah applies to this contract. Product liability disclaimers and/or warranty disclaimers from the seller are not applicable to this contract unless otherwise specified and mutually agreed upon elsewhere in this contract. In general, the contractor warrants that: (1) the product will do what the salesperson said it would do, (2) the product will live up to all specific claims that the manufacturer makes in their advertisements, (3) the product will be suitable for the ordinary purposes for which such product is used, (4) the product will be suitable for any special purposes that the State has relied on the contractor's skill or judgement to consider when it advised the State about the product, (5) the product has been properly designed and manufactured, and (6) the product is free of significant defects or unusual problems about which the State has not been warned. Remedies available to the State include the following: The contractor will repair or replace (at no charge to the State) the product whose nonconformance is discovered and made known to the contractor in writing. If the repaired and/or replaced product proves to be inadequate, or fails of its essential purpose, the contractor will refund the full amount of any payments that have been made. Nothing in this warranty will be construed to limit any rights or remedies the State of Utah may otherwise have under this contract.

7. DIVISION APPROVAL: Purchase orders placed, or contracts written, with the state of Utah, as a result of this bid, will not to be legally binding without the written approval of the director of the DIVISION.

8. AWARD OF CONTRACT: (a) the contract will to be awarded with reasonable promptness, by written notice, to the lowest responsible bidder that meets the specifications. Consideration will to be given to the quality of the product(s) to be supplied, conformity to the specifications, the purpose for which required, delivery time required, discount terms and other criteria set forth in this invitation to bid. (b) The bids are opened publicly in the presence of one or more witnesses. the name of each bidder, and the amount of the bid is recorded. Each bid, and the record, is open to public inspection. (c) The DIVISION may accept any item or group of items, or overall low bid. the DIVISION has the right to cancel this invitation to bid at any time prior to the award of contract. (d) The DIVISION can reject any and all bids. And it can waive any informality, or technicality in any bid received, if the DIVISION believes it would serve the best interest of the State. (e) Before, or after, the award of a contract the DIVISION has the right to inspect the bidder's premises and all business records to determine the holder's ability to meet contract requirements. (f) DIVISION does not guarantee to make any purchase under awarded contract(s). Estimated quantities are for bidding purposes only, and not to be interpreted as a guarantee to purchase any amount. (g) Utah has a reciprocal preference law which will to be applied against bidders bidding products or services produced in states which discriminate against Utah products. For details see Section 63-56 20.5 -20.6, Utah Code Annotated.

9. ANTI-DISCRIMINATION ACT: The bidder agrees to abide by the provisions of the Utah Anti-discrimination Act, Title 34 Chapter 35, U.C.A. 1953, as amended, and Title VI and Title VII of the Civil Rights Act of 1964 (42 USC 2000e), which prohibit discrimination against any employee or applicant for employment, or any applicant or recipient of services, on the basis of race, religion, color, or national origin; and further agrees to abide by Executive Order No. 11246, as amended, which prohibits discrimination on the basis of sex; 45 CFR 90 which prohibits discrimination on the basis of age, and Section 504 of the Rehabilitation Act of 1973 or the Americans with Disabilities Act of 1990, which prohibits discrimination on the basis of disabilities. Also bidder agrees to abide by Utah's Executive Order, dated March 17, 1993, which prohibits sexual harassment in the workplace. Vendor must include this provision in every subcontract or purchase order relating to purchases by the State of Utah to insure that the subcontractors and vendors are bound by this provision.

10. DEBARMENT: The CONTRACTOR certifies that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction (contract) by any governmental department or agency. If the CONTRACTOR cannot certify this statement, attach a written explanation for review by the STATE.

11. ENERGY CONSERVATION AND RECYCLED PRODUCTS: The contractor is encouraged to offer Energy Star certified products or products that meet FEMP (Federal Energy Management Program) standards for energy consumption. The State of Utah also encourages contractors to offer products that are produced with recycled materials, where appropriate, unless otherwise requested in this solicitation.

12. GOVERNING LAWS AND REGULATIONS: All state purchases are subject to the Utah Procurement Code, Title 63 Chapter 56 U.C.A. 1953, as amended, and the Procurement Regulations as adopted by the Utah State Procurement Policy Board. These are available on the Internet at www.purchasing.utah.gov.

ATTACHMENT A: STANDARD TERMS AND CONDITIONS

1. **AUTHORITY:** Provisions of this contract are pursuant to the authority set forth in 63-56, Utah Code Annotated, 1953, as amended, Utah State Procurement Rules (Utah Administrative Code Section R33), and related statutes which permit the State to purchase certain specified services, and other approved purchases for the State.
2. **CONTRACT JURISDICTION, CHOICE OF LAW, AND VENUE:** The provisions of this contract shall be governed by the laws of the State of Utah. The parties will submit to the jurisdiction of the courts of the State of Utah for any dispute arising out of this Contract or the breach thereof. Venue shall be in Salt Lake City, in the Third Judicial District Court for Salt Lake County.
3. **LAWS AND REGULATIONS:** Any and all supplies, services and equipment furnished will comply fully with all applicable Federal and State laws and regulations.
4. **RECORDS ADMINISTRATION:** The Contractor shall maintain, or supervise the maintenance of all records necessary to properly account for the payments made to the Contractor for costs authorized by this contract. These records shall be retained by the Contractor for at least four years after the contract terminates, or until all audits initiated within the four years, have been completed, whichever is later. The Contractor agrees to allow State and Federal auditors, and State Agency Staff, access to all the records to this contract, for audit and inspection, and monitoring of services. Such access will be during normal business hours, or by appointment.
5. **CONFLICT OF INTEREST:** Contractor represents that none of its officers or employees are officers or employees of the State of Utah, unless disclosure has been made in accordance with 67-16-8, Utah Code Annotated, 1953, as amended.
6. **CONTRACTOR, AN INDEPENDENT CONTRACTOR:** The Contractor shall be an independent contractor, and as such, shall have no authorization, express or implied, to bind the State to any agreements, settlements, liability, or understanding whatsoever, and agrees not to perform any acts as agent for the State, except as herein expressly set forth. Compensation stated herein shall be the total amount payable to the Contractor by the State. The Contractor shall be responsible for the payment of all income tax and social security amounts due as a result of payments received from the State for these contract services. Persons employed by the State and acting under the direction of the State shall not be deemed to be employees or agents of the Contractor.
7. **INDEMNITY CLAUSE:** The Contractor agrees to indemnify, save harmless, and release the State OF UTAH, and all its officers, agents, volunteers, and employees from and against any and all loss, damages, injury, liability, suits, and proceedings arising out of the performance of this contract which are caused in whole or in part by the negligence of the Contractor's officers, agents, volunteers, or employees, but not for claims arising from the State's sole negligence.
8. **EQUAL OPPORTUNITY CLAUSE:** The Contractor agrees to abide by the provisions of Title VI and VII of the Civil Rights Act of 1964 (42USC 2000e) which prohibits discrimination against any employee or applicant for employment or any applicant or recipient of services, on the basis of race, religion, color, or national origin; and further agrees to abide by Executive Order No. 11246, as amended, which prohibits discrimination on the basis of sex; 45 CFR 90 which prohibits discrimination on the basis of age; and Section 504 of the Rehabilitation Act of 1973, or the Americans with Disabilities Act of 1990 which prohibits discrimination on the basis of disabilities. Also, the Contractor agrees to abide by Utah's Executive Order, dated March 17, 1993, which prohibits sexual harassment in the work place.
9. **SEPARABILITY CLAUSE:** A declaration by any court, or any other binding legal source, that any provision of this contract is illegal and void shall not affect the legality and enforceability of any other provision of this contract, unless the provisions are mutually dependent.
10. **RENEGOTIATION OR MODIFICATIONS:** This contract may be amended, modified, or supplemented only by written amendment to the contract, executed by the same persons or by persons holding the same position as persons who signed the original agreement on behalf of the parties hereto, and attached to the original signed copy of the contract.
11. **DEBARMENT:** The Contractor certifies that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction (contract), by any governmental department or agency. If the Contractor cannot certify this statement, attach a written explanation for review by the State. The Contractor must notify the State Director of Purchasing within 30 days if debarred by any governmental entity during the Contract period.
12. **TERMINATION:** Unless otherwise stated in the Special Terms and Conditions, this contract may be terminated, with cause by either party, in advance of the specified termination date, upon written notice being given by the other party. The party in violation will be given ten (10) working days after notification to correct and cease the violations, after which the contract may be terminated for cause. This contract may be terminated without cause, in advance of the specified expiration date, by either party, upon 90 days prior written notice being given the other party. On termination of this contract, all accounts and payments will be processed according to the financial arrangements set forth herein for approved services rendered to date of termination.
13. **NONAPPROPRIATION OF FUNDS:** The Contractor acknowledges that the State cannot contract for the payment of funds not yet appropriated by the Utah State Legislature. If funding to the State is reduced due to an order by the Legislature or the Governor, or is required by State law, or if federal funding (when applicable) is not provided, the State may terminate this contract or proportionately reduce the services and purchase obligations and the amount due from the State upon 30 days written notice. In the case that funds are not appropriated or are reduced, the State will reimburse Contractor for products delivered or services performed through the date of cancellation or reduction, and the State will not be liable for any future commitments, penalties, or liquidated damages.
14. **SALES TAX EXEMPTION:** The State of Utah's sales and use tax exemption number is E33399. The tangible personal property or services being purchased are being paid from State funds and used in the exercise of that entity's essential functions. If the items being purchased are construction materials, they will be converted into real property by employees of this government entity, unless otherwise stated in the contract.
15. **WARRANTY:** The contractor agrees to warrant and assume responsibility for all products (including hardware, firmware, and/or software products) that it licenses, contracts, or sells to the State of Utah under this contract for a period of one year, unless otherwise specified and mutually agreed upon elsewhere in this contract. The contractor (seller) acknowledges that all warranties granted to the buyer by the Uniform Commercial Code of the State of Utah apply to this contract. Product liability disclaimers and/or warranty disclaimers from the seller are not applicable to this contract unless otherwise specified and mutually agreed upon elsewhere in this contract. In general, the contractor warrants that: (1) the product will do what the salesperson said it would do, (2) the product will live up to all specific claims that the manufacturer makes in their advertisements, (3) the product will be suitable for the ordinary purposes for which such product is used, (4) the product will be suitable

for any special purposes that the State has relied on the contractor's skill or judgment to consider when it advised the State about the product, (5) the product has been properly designed and manufactured, and (6) the product is free of significant defects or unusual problems about which the State has not been warned. Remedies available to the State include the following: The contractor will repair or replace (at no charge to the State) the product whose nonconformance is discovered and made known to the contractor in writing. If the repaired and/or replaced product proves to be inadequate, or fails of its essential purpose, the contractor will refund the full amount of any payments that have been made. Nothing in this warranty will be construed to limit any rights or remedies the State of Utah may otherwise have under this contract.

16. **PUBLIC INFORMATION:** Contractor agrees that the contract will be a public document, and may be available for distribution, and Contractor gives the State express permission to make copies of the contract and/or of the response to the solicitation in accordance with the State of Utah Government Records Access and Management Act. The permission to make copies as noted will take precedence over any statements of confidentiality, proprietary information, copyright information, or similar notation.
17. **DELIVERY:** Unless otherwise specified in this contract, all deliveries will be F.O.B. destination with all transportation and handling charges paid by the Contractor. Responsibility and liability for loss or damage will remain with Contractor until final inspection and acceptance when responsibility will pass to the State except as to latent defects, fraud and Contractor's warranty obligations.
18. **ORDERING AND INVOICING:** All orders will be shipped promptly in accordance with the delivery schedule. The Contractor will promptly submit invoices (within 30 days of shipment or delivery of services) to the State. The State contract number and/or the agency purchase order number shall be listed on all invoices, freight tickets, and correspondence relating to the contract order. The prices paid by the State will be those prices listed in the contract. The State has the right to adjust or return any invoice reflecting incorrect pricing.
19. **PAYMENT:** Payments are normally made within 30 days following the date the order is delivered or the date a correct invoice is received, whichever is later. All payments to the Contractor will be remitted by mail unless paid by the State of Utah's Purchasing Card.
20. **PATENTS, COPYRIGHTS, ETC.:** The Contractor will release, indemnify and hold the State, its officers, agents and employees harmless from liability of any kind or nature, including the Contractor's use of any copyrighted or un-copyrighted composition, secret process, patented or un-patented invention, article or appliance furnished or used in the performance of this contract.
21. **ASSIGNMENT/SUBCONTRACT:** Contractor will not assign, sell, transfer, subcontract or sublet rights, or delegate responsibilities under this contract, in whole or in part, without the prior written approval of the State.
22. **DEFAULT AND REMEDIES:** Any of the following events will constitute cause for the State to declare Contractor in default of the contract:
 1. Nonperformance of contractual requirements;
 2. A material breach of any term or condition of this contract. The State will issue a written notice of default providing a ten (10) day period in which Contractor will have an opportunity to cure. Time allowed for cure will not diminish or eliminate Contractor's liability for damages. If the default remains, after Contractor has been provided the opportunity to cure, the State may do one or more of the following:
 1. Exercise any remedy provided by law;
 2. Terminate this contract and any related contracts or portions thereof;
 3. Impose liquidated damages, if liquidated damages are listed in the contract;
 4. Suspend Contractor from receiving future solicitations.
23. **FORCE MAJEURE:** Neither party to this contract will be held responsible for delay or default caused by fire, riot, acts of God and/or war which is beyond that party's reasonable control. The State may terminate this contract after determining such delay or default will reasonably prevent successful performance of the contract.
24. **PROCUREMENT ETHICS:** The Contractor understands that a person who is interested in any way in the sale of any supplies, services, construction, or insurance to the State of Utah is violating the law if the person gives or offers to give any compensation, gratuity, contribution, loan or reward, or any promise thereof to any person acting as a procurement officer on behalf of the State, or who in any official capacity participates in the procurement of such supplies, services, construction, or insurance, whether it is given for their own use or for the use or benefit of any other person or organization (63-56-73, Utah Code Annotated, 1953, as amended).
25. **CONFLICT OF TERMS:** Contractor Terms and Conditions that apply must be in writing and attached to the contract. No other Terms and Conditions will apply to this contract including terms listed or referenced on a Contractor's website, terms listed in a Contractor quotation/sales order, etc. In the event of any conflict in the contract terms and conditions, the order of precedence shall be:
 1. State Standard Terms and Conditions;
 2. State Special Terms and Conditions;
 3. Contractor Terms and Conditions.

(Revision date: Nov 21, 2003)

OPHIR CANYON PROJECT

CONSTRUCTION SPECIFICATIONS

AMR/045/907

Summer, 2005

Requisition Number 560 52000000008


=====

Tooele County, Utah

=====



UTAH NATURAL RESOURCES
Abandoned Mine Reclamation Program
Salt Lake City, Utah



Utah Oil Gas and Mining

Copy 30 of 30

***** This is NOT a standard DFCM Specification Package *****

**STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS & MINING
ABANDONED MINE RECLAMATION PROGRAM**

The Utah Department of Natural Resources receives federal aid and prohibits discrimination on the basis of race, color, sex, age, national origin, or handicap. For information or complaints regarding discrimination, contact Executive Director, Utah Department of Natural Resources, P.O. Box 145610, Salt Lake City, Utah 84114-5610 or Office of Equal Opportunity, U.S. Department of the Interior, Washington, D.C. 20240

Completed Date: 6/20/05
Document Filename: O:\Projects\045Tooele\Oquirrh_Mts_Projts\Construction
Revised: 06/07/05

CONSTRUCTION SPECIFICATIONS FOR

OPHIR CANYON PROJECT

RECLAMATION CONSTRUCTION

Tooele County, Utah

Requisition Number RX 560 52000000008

State of Utah

Department of Natural Resources
Division of Oil, Gas and Mining
Abandoned Mine Reclamation Program
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801
(801) 538-5340
<http://www.ogm.utah.gov/amr/contract.htm>

***** This is NOT a standard DFCM Specification Package *****

Table Of Contents

Project Summary And Bidding Check List	i
Instructions To Bidders	ii
PROPOSAL AND BID SCHEDULES (Yellow Pages)	
Proposal	1
Agency Contract Bond Statement	3
Bid Bond	4
Bidder's Proposed Subcontractors, Suppliers & Vendors List	5
Minority And Woman Business Enterprise Representation	7
Applicant/Violator System Eligibility Check	8
Bid Schedule	11
CONTRACT (Orange Pages)	
Contract Form	21
Performance Bond	29
Payment Bond	30
Certificate Of Substantial Completion	32
Certificate Of Final Acceptance	33
GENERAL CONDITIONS (White Pages)	
General Conditions	35
Supplemental General Conditions	53
TECHNICAL SPECIFICATIONS (Blue Pages)	
0200 General Site Information	57
0220 Mobilization/Demobilization	63
0230 Access Improvements	65
0240 Demolition And Clean-Up	67
0250 Mine Closures	71
0251 Cast-In-Place Concrete	79
0252 Concrete Reinforcement	83
0253 Bat Gate & Shaft Grate Installation	85
0254 Polyurethane Foam Mine Closures	93
0290 Revegetation	105
0300 Specific Site Requirements (Gray Pages)	113
APPENDICES	
Appendix A: Site Descriptions and Mine Closure Schedule	
Appendix B: Sites Listed by Closure Type and Estimated Quantity	
Appendix C: Revegetation Seed Mixture	
Appendix D: Contractor Report Forms	
Appendix E: Standard Mine Closure Design Drawings	
Appendix F: Project Location Maps	

Project Summary And Bidding Check List

Sealed bids will be received by the Division of Purchasing, 3150 State Office Building, Salt Lake City, for the OPHIR CANYON PROJECT RECLAMATION CONSTRUCTION in Tooele County, Utah. Bids will be received until 2:00 p.m., on Wednesday, July 20, 2005, at which time they will be opened and read aloud in the Division of Purchasing offices.

The WORK consists of reclamation construction at 143 abandoned hardrock metal mines located in Tooele County, Utah. The work includes installing mine closures and includes incidental tasks such as access improvement and revegetation of disturbed areas. Details of the WORK are contained in the Specifications.

Specifications may be obtained from the Division of Oil, Gas, and Mining, 1594 West North Temple, Suite 1210, Salt Lake City, for a nonrefundable fee of twenty dollars (\$20.00). Checks should be made payable to the Division of Oil, Gas and Mining.

AN OPTIONAL PRE-BID MEETING WILL BE HELD FOR ALL BIDDERS ON Wednesday, July 6, 2005 at 10:00 am. Meet at the turnoff to the town of Ophir, the Ophir Town Site Road off highway 73. The meeting is expected to last most of the day and will involve driving and hiking over rugged terrain. High clearance four-wheel-drive vehicles are recommended. This meeting is optional. *Because of the special nature of abandoned mine closure work, bidders are strongly encouraged to attend the pre-bid meeting.*

Questions about bidding procedures should be directed to the Division of Purchasing. Contact person is Paul Mash, Purchasing Agent. Bids should be delivered to:

Division of Purchasing
3150 State Office Building
Salt Lake City, Utah 84114
(801) 538-3026 FAX: (801) 538-3882

Technical questions about the project should be directed to the project manager at the Division of Oil, Gas and Mining. Contact person is:

Amber Fortner, Project Manager
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801
(801) 538-5437 Fax: (801) 359-3940
E-mail: amberfortner@utah.gov

The following is a check list of items that **must** be provided with the bid documents:

- ☐ Division of Purchasing bid documents
- ☐ Proposal
- ☐ Agency Contract Bond Statement
- ☐ Bid Security (Bid Bond or Cashier's Check)
- ☐ Minority and Woman Business Enterprise Representation
- ☐ Bid Schedule
- ☐ Photocopy of current Utah Contractor's License

Required Submittal:

- | | |
|--|--|
| <input type="checkbox"/> Section 0230, Part 1, 1.02 | <input type="checkbox"/> Section 0251, Part 1, 1.02, A.1 |
| <input type="checkbox"/> Section 0240, Part 1, 1.02, A | <input type="checkbox"/> Section 0254, Part 1, 1.02 |
| <input type="checkbox"/> Section 0250, Part 1, 1.02, A-B | <input type="checkbox"/> Section 0290, Part 1, 1.02, A-B |

The following items are required within 24 hours after bid opening from the apparent two low bidders only. They may be submitted with the bid at the bidder's option or convenience.

- ☐ Bidder's Proposed Subcontractors, Suppliers & Vendors List
- ☐ AVS Eligibility Check information: AML Contractor Ownership & Control Information Package

Bids must be delivered to the Division of Purchasing only. Do NOT deliver bids to DOGM.

Instructions To Bidders

1. Request for Bids

The Utah Division of Purchasing is accepting bids for the Ophir Canyon Project. The WORK consists of installing mine closures at 143 abandoned hardrock metal mines in Tooele County, Utah. Details of the WORK are contained in these Specifications. **Sealed bids are due on Wednesday, July 20, 2005, no later than 2:00 P.M., at which time they will be opened and read aloud at the Division of Purchasing's office.**

2. Qualifications of Bidders

All CONTRACTORS must be currently licensed in Utah for the type of work to be done. Bidders shall submit a photocopy of their current Utah license covering the type of work to be done with their bid.

All CONTRACTORS who have previously performed WORK on a Utah Abandoned Mine Reclamation Program (UAMRP) project have been evaluated based on the Contractor Performance Rating Form (Appendix D). A rating of ten points or more is required to bid on this project.

3. Drawings and Specifications

Drawings and Specifications may be obtained from the Division of Oil, Gas and Mining for the amount stated in the Project Summary and Checklist. Checks should be made payable to the Utah Division of Oil, Gas and Mining. The payment is nonrefundable.

4. Pre-bid Meeting

An optional pre-bid site meeting will be held for all interested bidders on Wednesday, July 6, 2005 at 10:00 am. Meet at the turnoff to the town of Ophir, the Ophir Town Site Road off highway 73. The meeting is expected to last most of the day and will involve driving and hiking over rugged terrain. High-clearance four-wheel-drive vehicles are recommended.

This meeting is optional. Attendance is not required to bid, but attendance should result in a more responsible bid. Abandoned mine closure work is different from standard residential or commercial construction. It requires specialized work in unusual conditions and unique circumstances. *Because of the special nature of abandoned mine closure work, bidders are strongly encouraged to attend the pre-bid meeting.* If attendance at the meeting is not possible, bidders should make every effort to examine the project on their own time. Abandoned mines are hazardous. Do not enter the mines.

5. Proposals

Before submitting a proposal, each bidder shall carefully examine the drawings, specifications and other contract documents and shall visit the site of the WORK; shall fully inform himself or herself as to all existing conditions and limitations; and shall include in the proposal the cost of all items included in the CONTRACT. CONTRACTOR shall fill out all blanks and include all forms and submittals, or be subject to having the bid disqualified. (See the check list of bid items on page i).

The pages required for bidding are included in these specifications. For convenience, additional unbound copies of these pages will be distributed at the pre-bid site meeting. The bidder must submit the Proposal, Agency Contract Bond Statement, Bid Bond, Minority and Woman Business Enterprise Representation, Bid Schedule, photocopy of Utah contractor's license, and required submittals in the sealed bid, along with the required Division of Purchasing bid documents.

Deliver proposals to the Division of Purchasing only. Do not deliver proposals to DOGM.

6. Contract and Bond

The contract agreement will be on a form similar to that which is bound in the specifications. The completion date of construction will be as indicated in the proposal. The successful bidder, within 14 days after the bid opening, will be required to furnish a performance bond and a payment bond in an amount equal to one hundred percent (100%) of the contract price, said bonds shall be secured from a company satisfactory to OWNER. **The surety company must be a U.S. Department of Treasury (Circular 570) listed company.**

7. Listing of Subcontractors

The experience and responsibility of Subcontractors may have bearing on the selection of a CONTRACTOR by the OWNER.

The apparent two low bidders shall deliver to OWNER within 24 hours (Excluding Saturday, Sunday, and State holidays) for OWNER's approval, a list of the names of Subcontractors to be furnished for each of the principal parts of the work and the corresponding dollar amounts. Each principal part shall mean a subcontract dollar value in excess of \$5,000. A form for this submission is included in these Specifications. Such list shall be binding upon the CONTRACTOR; however, OWNER has a right to reject any or all Subcontractors listed or unlisted which OWNER feels are unqualified to do the work.

OWNER may withhold award of CONTRACT to any particular bidder if one or more of his or her proposed Subcontractors are considered by the OWNER to be unqualified.

8. Interpretation of Plans and Specifications

If any person contemplating submitting a bid for the proposed CONTRACT is in doubt as to the true meaning of any part of the drawings, specifications or other proposed CONTRACT documents, he or she may submit to the Division of Oil, Gas & Mining a written request for an interpretation thereof. The person submitting the request will be responsible for its prompt delivery.

Any interpretation of the proposed documents will be made only by addendum duly issued. A copy of such addendum will be mailed or delivered to each person receiving a set of documents, and posted on the UAMRP website and the Division of Purchasing website. CONTRACTORS who have downloaded specifications will need to check for addendums on website. The OWNER will not be responsible for any other explanations or interpretations of the proposed documents.

9. Addenda or Bulletins

Any addenda or bulletins issued during the time of bidding shall become part of the documents issued to the bidders for the preparation of the bid, shall be covered in the bid, and shall be made a part of the CONTRACT.

10. Bid Schedule

Bidding CONTRACTORS shall examine the specifications and the Bid Schedule and *fill in all blanks* of the CONTRACTOR's Proposal and Bid Schedule and submit all required information contained in the Specifications Schedule, including required submittals, or have the bid subject to disqualification.

11. Award of CONTRACT

The CONTRACT will be awarded as soon as possible to the lowest responsible bidder, provided the bid is reasonable and is in the interests of the OWNER to accept. Responsible bidders will be considered to be those bidders who have fully evaluated the work to be performed, as detailed in their bids. For bidders who have previously performed WORK on a UAMRP project, evaluation of the responsibility of the bidder will also include consideration of past performance on AMR contracts for OWNER. Both the Lump Sum Amount and the Variation in Quantities Unit Price for all work items will be considered in awarding the CONTRACT. Lump Sum Amounts do not have to equal the product of the estimated quantity times the Variation in Quantity Unit Price, but OWNER may reject a bid if unit prices are substantially out of line with

the Lump Sum Amount. The OWNER reserves the right to waive any technicalities or formalities in any bid or in the bidding.

12. Qualifications

The CONTRACTOR's and Subcontractor's past performance, organization, equipment, and ability to perform and complete their contracts in the manner and within the time limit specified will be elements along with the cash amount of the bid, which will be considered by the OWNER in the letting of the CONTRACT. A rating of ten points or more on the Contractor Performance Rating Form (Appendix D) is required for any CONTRACTOR who has previously performed WORK on a Utah AMR project. The CONTRACTOR shall comply with and require all of his or her Subcontractors to comply with the license laws as required by the State of Utah.

13. Cost Breakdown

The CONTRACTOR shall, before starting WORK, submit to OWNER a cost breakdown showing the cost of various segments of the WORK according to a specification heading, the total amount equaling the CONTRACT price. This breakdown shall be used as the basis for the payment of estimates as stated in the contract documents.

14. Right to Reject Proposals

The OWNER reserves the right to reject any or all proposals.

15. Time is Essence and Award of CONTRACT

Time is of the essence in award of the CONTRACT.

16. Withdrawal of Bids

Bids may be withdrawn upon written or electronic request received from bidders prior to the time fixed for opening. Electronic request via FAX or E-mail must be received by OWNER in written form before bid opening. Negligence on the part of the bidder in preparing the bid confers no right for the withdrawal of the bid after it has been opened.

17. Bid Security

Bid Security in the amount of five percent (5%) of the bid, made payable to the Division of Oil, Gas & Mining, shall accompany bid. If a certified or cashier's check is used in lieu of bid bond, a current certificate from an approved surety company guaranteeing execution of a 100% Performance Bond and 100% Payment Bond must be on file with the OWNER.

18. Applicant Violator System (AVS) Eligibility Check

Federal regulations (30 CFR 874.16) effective July 1, 1994, require all successful bidders on contracts funded through Title IV of the Surface Mining Control and Reclamation Act (SMCRA) of 1977 to be eligible under 30 CFR 773.15(b)(1) to receive a permit to conduct surface coal mining operations. In general, this means that the Utah Abandoned Mine Reclamation Program may not hire a contractor who is or whose company is associated with a coal mine operator with outstanding unabated violations under SMCRA. The regulations further require that contractor eligibility be confirmed by the Applicant/Violator System (AVS) at the U.S. Office of Surface Mining (OSM). Compliance checks are also required for all subcontractors receiving 10% or more of the total contract amount.

19. Buy American Act

Compliance with the Buy American Act is required for this project. The Buy American Act requires the use of domestically produced materials.

20. Electronic Specs Available

OWNER has electronic versions of the Contract Specifications available on DOGM's website at <http://www.ogm.utah.gov/amr/contract.htm>. Files include the text of the Contract Specifications (as an Adobe Acrobat.pdf file), the maps (in .pdf format, readable with Adobe Acrobat Reader software available free online), and a spreadsheet with the Appendix A mine descriptions and closure specifications (as an Excel *.xls file). The spreadsheet file may be especially useful in preparing a bid because it can automate the arithmetic. Files can be downloaded from the website. Any questions regarding digital data should be directed to Connie Jo Garcia, 801-538-5305, e-mail: conniegarcia@utah.gov

Proposal

NAME OF BIDDER _____ DATE _____

**TO THE DIVISION OF PURCHASING
3150 STATE OFFICE BUILDING
SALT LAKE CITY, UTAH 84114**

Re: RX No: 560 52000000008

Gentlemen:

The undersigned, in compliance with your invitation for bids for the

OPHIR CANYON PROJECT RECLAMATION CONSTRUCTION

having examined the Drawings and Specifications, related documents, and the site of the proposed work and being familiar with all of the conditions surrounding the construction of the proposed project, including the availability of labor, hereby propose to furnish all labor, materials, and supplies as required for the WORK in accordance with the CONTRACT documents as specified and within the time set forth and at the price stated below. This price is to cover all expenses incurred in performing the WORK required under the CONTRACT Documents of which this Proposal is a part. Negotiation of BID PRICE shall be completed with the OWNER prior to final execution of the CONTRACT.

I/We acknowledge receipt of the following addenda:

For all WORK shown on the Drawings and described in the Specifications, I/we agree to perform for the sum of:

_____ DOLLARS (\$ _____)
(In case of discrepancy, written amount shall govern)

For your consideration, we further propose the following ALTERNATIVES for the following total amounts to be added/deducted to/from the above bid amount:

_____ Add \$ _____ Deduct \$ _____

I/We guarantee to complete the WORK within 70 calendar days after receipt of Notice to Proceed, should I/we be the successful bidder.

For your consideration I/we propose an alternative amount of time to complete the WORK after Notice to Proceed, should I/we be the successful bidder. Such an extension allows the following total amount to be deducted from the bid amount:

Alternative: _____ Total Calendar Days _____ Deduct \$ _____

This bid shall be good for 45 days after bid opening.

Enclosed is _____, as required, in the sum of \$ _____
(Bond or Check)

PROPOSAL

Page 2

If applicable, the CONTRACTOR shall certify that all reclamation fees or civil penalty assessments required by the provision of the Surface Mining Control and Reclamation Act of 1977, P.L. 95-87, 30 U.S.C. Sec 1201 et seq., have been paid. Provided further, this certification requirement shall also apply to all Subcontractors utilized by the successful bidders.

Upon receipt of notice of acceptance of this bid, the undersigned agrees to execute the CONTRACT within five (5) days and deliver OWNER's protective bond (performance and bid) in the prescribed form in the amount of 100% of the general construction contract price for faithful performance of the CONTRACT. The certified check, cashier's check or Bid Bond attached, in the amount not less than five percent (5%) of the above BID PRICE, shall become the property of the Division of Oil, Gas & Mining in the event that the CONTRACT is not negotiated and/or the OWNER's Protective Bond delivered within the time set forth, as liquidated damages for the delay and additional expense caused thereby.

SUBSTITUTIONS AND ALTERNATIVES:

The following substitutions and/or alternatives of materials and/or equipment are proposed for your consideration:

Item	Manufacturer and Description	Addition	Deduction
_____	_____	\$ _____	\$ _____
_____	_____	\$ _____	\$ _____
_____	_____	\$ _____	\$ _____

CONTRACTOR shall furnish and attach to this proposal all submittals as required in the specifications:

Section 0230, Part 1, 1.02

Section 0240, Part 1, 1.02, A

Section 0250, Part 1, 1.02, A-B

Section 0251, Part 1, 1.02, A.1

Section 0254, Part 1, 1.02

Section 0290, Part 1, 1.02, A-B

The undersigned CONTRACTOR's License Number for Utah is _____

Type of Organization:

(Corporation, Co-Partnership, Individual, etc.)

SEAL
(If a Corporation)

(Tax ID No.)

Respectfully submitted,

Name of Bidder

Address

Authorized Signature

STATE OF UTAH
Division of Purchasing
Agency Contract Bond Statement

BIDDING REQUIREMENTS

A 5% bid bond or cashier's check is required by all vendors bidding on this project. The bid bond must be attached to bid **or it will be disqualified**. Checks submitted will be returned certified mail after an official award has been made.

AWARD REQUIREMENTS

A 100% performance/payment bond will be required from the award vendor within 14 days after notification of award. Bonds must be in the form of a cashiers check (no personal or business checks) or a surety bond from a licensed surety company doing business in the State of Utah.

Performance/payment bonds (or checks) will be **held as security for a period of 12 months after completion of project**, per state law. Checks submitted will be returned certified mail only after this specified time. Bidder's name must be the same on both the bid forms and all bonds submitted.

Please indicate which method of bonding will be used if awarded this job:

_____ 100% CASHIERS CHECK

_____ 100% PERFORMANCE/PAYMENT BOND

Bond/Ins Company _____

Agent name _____

Fax # _____ Phone # _____

Upon awarding, the requesting agency will fax a verification to the bonding company listed above to start the bonding process. It is then the responsibility of the vendor to follow through with their bonding agent to assure the bond is processed. After the bonding company sends the bond to vendor for signatures, it is the responsibility of the vendor to mail or hand carry the original bond (no copies or faxes accepted) to the requesting agency, to the attention of the contract person listed on the bid. **No work can commence until the requesting agency has receipt of this performance/payment bond.** After this time the contract will be officially released to the award vendor.

Bid Bond

Date Bond Executed

Principal

Surety

Sum of Bond

KNOW ALL MEN OF THESE PRESENTS, that we, the PRINCIPAL AND SURETY above named, are held and firmly bound unto the STATE OF UTAH, ACTING BY AND THROUGH THE DIVISION OF OIL, GAS AND MINING OF UTAH, IN THE SUM OF THE AMOUNT STATED ABOVE, FOR THE PAYMENT OF WHICH SUM WELL AND TRULY TO BE MADE, we bind ourselves, our heirs, executors, administrators, and successors, jointly and severally, firmly by these presents. THE CONDITION OF THIS OBLIGATION IS SUCH that whereas the principal has submitted the accompanying bid, dated as shown above, for

\$ _____

NOW THEREFORE, THE CONDITION OF THE ABOVE OBLIGATION IS SUCH, that if the said principal shall execute a CONTRACT and give bond to be approved by the Oblige for the faithful performance thereof within ten (10) days after being notified in writing of such CONTRACT to the principal, this obligation shall then be null and void; otherwise it shall remain in full force and effect.

IN WITNESS WHEREOF, the above bounden parties have executed this instrument under their several seals on the date indicated above, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

Individual or Partnership Principal

Corporate Principal

Business Address

Business Address

By: _____ Affix
Corporate Seal
Title _____

Corporate Surety:

Business Address

NOTE: If certified or cashier's check is used in lieu of Bid Bond, a certificate from an approved surety company guaranteeing execution of a full performance bond must accompany bid.

By: _____ Affix
Corporate Seal
Attorney-in-Fact _____

STATE OF UTAH)
COUNTY OF SALT LAKE)

_____, being first duly sworn on oath, deposes and says that he/she is the Attorney-in-Fact of the above-named Surety Company, and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations.

Subscribed and sworn to before me this _____ day of _____, 20_____.

My commission expires _____.

Attorney-in-Fact

Bidder's Proposed Subcontractors, Suppliers & Vendors List

OPHIR CANYON PROJECT RECLAMATION CONSTRUCTION AMR/045/907

Utah Division of Oil, Gas & Mining

We submit the following list of first-tier subcontractors, suppliers and vendors for OWNER approval. We recognize this list as binding on us, and acknowledge OWNER'S right to reject any or all subcontractors, suppliers or vendors listed or unlisted which the OWNER feels are unqualified to do the work.

SUBCONTRACTOR	CONTRACT AMOUNT	STATE CONTRACTOR'S LICENSE NO.	LICENSE LIMIT
Excavation:			
Concrete Fabrication:			
Masonry:			
Demolition:			
Steel Fabrication:			
Revegetation:			
Trucking/Transport:			
Polyurethane Foam:			
Other:			
Other:			
Other:			

BIDDER'S PROPOSED SUBCONTRACTORS, SUPPLIERS & VENDORS LIST

Page 2

SUPPLIER/VENDOR	AMOUNT	PRODUCT
Ready-Mix:		
Cement/Block:		
Steel:		
Polyurethane Foam:		
Other:		
Other:		
Other:		

We certify that:

1. This list includes all subcontractors, suppliers and vendors whose bids exceed \$5,000 (for prime contractor bids less than \$250,000) or \$25,000 (for prime contractor bids of \$250,000 or more).
2. Where we have listed "Self" it is our intent to perform said work and that we generally and regularly perform that type of work, and are appropriately licensed.
3. Any approved change in sub-bidders, suppliers or vendors which results in a lower contract price for sub-bid work shall accordingly reduce the total sum of the prime contract.

Signed by: _____

Firm: _____

Date: _____

Note: Failure to submit this form properly completed and signed within 24 hours (not including Saturday, Sunday, or State holidays) of the bid opening may be grounds for OWNER'S refusal to enter into a written CONTRACT with BIDDER. Action will be taken against BIDDER'S bid bond or cashier's check as deemed appropriate by OWNER. Timely notice of unacceptable subcontractors, suppliers or vendors will be given to the BIDDER. Reporting of subcontractors may be required for conformance with 63A-5-208 UCA.

Minority And Woman Business Enterprise Representation

The offeror represents that it ☐ is ☐ is not a minority business enterprise.

A minority business enterprise is defined as a concern that:

- 1) is at least 51 percent owned by one or more individuals who are socially and economically disadvantaged, or a publicly owned business having at least 51 percent of its stock owned by one or more individuals who are socially and economically disadvantaged individuals; and
- 2) has its management and daily business controlled by one or more such individuals.

Qualified groups. The offeror shall presume that socially and economically disadvantaged individuals include Black Americans, Hispanic American, Native Americans, Asian-Pacific American, Asian-Indian Americans, and other individuals found to be qualified by the Small Business Administration under 13 CFR 124.I.

The offeror represents that it ☐ is ☐ is not a woman business enterprise.

A woman business enterprise is defined as a concern that:

- 1) is at least 51 percent owned by one or more women, or a publicly owned business having at least 51 percent of its stock owned by one or more women; and
- 2) has its management and daily business controlled by one or more of the women owners.

Business firms which are 51 percent owned by minorities or women, but are in fact managed and operated by non-minority individuals do not qualify as minority or woman business enterprises.

The offeror represents that the following proposed subcontractor(s) is (are) a minority or woman business enterprise:

Signature of Offeror

Title

Date

This information is requested for Federal reporting purposes only. Minority/woman status has no bearing on the selection of a contractor.

Applicant/Violator System Eligibility Check

Federal regulations (30 CFR 874.16) effective July 1, 1994, require all successful bidders on contracts funded through Title IV of the Surface Mining Control and Reclamation Act (SMCRA) of 1977 to be eligible under 30 CFR 773.15(b)(1) to receive a permit to conduct surface coal mining operations. In general, this means that the Utah Abandoned Mine Reclamation Program may not hire a contractor who is or whose company is associated with a coal mine operator with outstanding unabated violations under SMCRA. The regulations further require that contractor eligibility be confirmed by the Applicant/Violator System (AVS) at the U.S. Office of Surface Mining (OSM). Compliance checks are also required for all subcontractors receiving 10% or more of the total contract amount.

To comply with these rules, prospective bidders must provide the Division of Oil, Gas and Mining with information on the ownership and control of the firm for AVS review. A bidder must receive a recommendation of "Issue" or "Conditional Issue" from the OSM AVS office to be awarded the contract.

The two apparent low bidders shall submit to DOGM within 24 hours (Excluding weekends and holidays) of the bid opening either a notarized copy of the "AML Contractor Ownership and Control Information Package" or else a copy of the "AML Contractor Ownership and Control Data Certification" updating and certifying previously submitted information. DOGM will provide forms for these submissions or you may download from the Internet at <http://www.avs.osmre.gov>. DOGM will submit the ownership and control information to OSM for AVS review. OSM's review will be completed within 72 hours if the ownership and control data entry is complete.

Bidders may choose to submit the required information prior to submitting the bid proposal in order to facilitate data entry by OSM and expedite the AVS review and contract award process. Forms may be obtained from DOGM.

The following information is required for the "AML Contractor Ownership and Control Information Package":

- Contractor's identity (name, address, telephone, Social Security number, Employee ID number).
- Contractor's legal structure (sole proprietorship, partnership, corporation).
- Identities (name, address, telephone, SSN, EIN, % ownership) of every officer, general partner, shareholder (10% voting stock), director, or other controlling entity.
- Identities of parties with the authority to commit the assets of the firm.
- Identities of other relationships that give direct or indirect authority over the execution of the work.
- List (name, address, permit number, MSHA number) of all permits issued in the last five years to or pending permit applications for coal mining operations by any parties identified above.
- All of the above information for any subcontractor with 10% of the contract amount.

Ophir Canyon Project Summary Bid Schedule

<u>Mine Group</u>	<u>Lump Sum Amount</u>
Foothills Area	\$ _____
Dry Canyon Area	\$ _____
Ophir Canyon Area	\$ _____
South Fork Ophir Canyon/Meadow Canyon Area	\$ _____
Lion Hill Area	\$ _____
Silveropolis Area	\$ _____
Rover Hill Area	\$ _____
MOBILIZATION/DEMOBILIZATION/CLEAN-UP FOR ALL MINE SITES	\$ _____
BONDS & INSURANCE FOR ALL MINE SITES	\$ _____
TOTAL CONTRACT BID PRICE	\$ _____

TOTAL CONTRACT BID PRICE WRITTEN:

DATE: _____ BY: _____

FIRM: _____

By the above signature I/we acknowledge that I/we have examined the site conditions and have made the measurements and evaluations necessary to plan and bid the WORK.

Note: The "Variation in Quantity Unit Price" on the Mine Closure Bid Schedule will be used for adjustments to the CONTRACT amount where the actual WORK quantity varies by more than 15% from the estimated quantity listed in the bid schedule (see Supplementary Condition No. 6: Variation in Estimated Quantity). The "Variation in Quantity Unit Price" will also be used as the basis for determining costs for closures not currently specified in the WORK that may be added in the future by change order. Award of CONTRACT will be based on consideration of both the base "Bid Price" and the "Variation in Quantity Unit Price" for additional/reduced WORK.

**Ophir Canyon Project
Bid Schedule**

FOOTHILLS AREA					
Item Of Work	Description of Work and Tag Number	Spec Section	Estimated Quantity	Bid Price Amount (\$)	Variation Quantity Unit Price (\$/Unit)
		0230			
1)	Access Improvement		n/a	<u>N/A</u>	n/a
2)	Mine Closure	0250			
	a) Equipment Backfill				
	3050405VO001		20 cyd	\$ _____	\$ _____/cyd
	b)Grate				
	3050408VO001		280 ft ²	\$ _____	\$ _____/ft ²
Foothill Area: Mine Closure SUBTOTAL (Carry over to Summary Bid Schedule)				\$ _____	

DRY CANYON AREA					
Item Of Work	Description of Work and Tag Number	Spec Section	Estimated Quantity	Bid Price Amount (\$)	Variation Quantity Unit Price (\$/Unit)
1)	Access Improvement	0230	lump sum	\$ _____	n/a
2)	Mine Closure	0250			
	a) Hand Backfill				
	3050421HO001		2 cyd	\$ _____	\$ _____/cyd
	3050421HO002		1 cyd	\$ _____	\$ _____/cyd
	3050421HO004		4 cyd	\$ _____	\$ _____/cyd
	3050421HO007		4 cyd	\$ _____	\$ _____/cyd
	3050421VO002		40 cyd	\$ _____	\$ _____/cyd
	3050421VO003		9 cyd	\$ _____	\$ _____/cyd

Ophir Canyon Project
 Bid Schedule

DRY CANYON AREA					
	3050422HO002		4 cyd	\$	\$ /cyd
	b) Equipment Backfill				
	3050421HO006		3 cyd	\$	\$ /cyd
	3050421IO002		60 cyd	\$	\$ /cyd
	3050421VO001		320 cyd	\$	\$ /cyd
	3050421VO005		10 cyd	\$	\$ /cyd
	3050421VO006		36 cyd	\$	\$ /cyd
	c) Bat Gate				
	3050421HO003		30 ft ²	\$	\$ /ft ²
	3050421HO005		20 ft ²	\$	\$ /ft ²
	3050421IO001		48 ft ²	\$	\$ /ft ²
	3050422HO001		52 ft ²	\$	\$ /ft ²
	3050422HO003		36 ft ²	\$	\$ /ft ²
	3050422HO004		24 ft ²	\$	\$ /ft ²
	d)Grate				
	3050421VO004		40 ft ²	\$	\$ /ft ²
	3050421VO007		99 ft ²	\$	\$ /ft ²
	e) Block Wall				
	3050422HO005		15 ft ²	\$	\$ /ft ²
Dry Canyon Area: Mine Closure SUBTOTAL				\$	
(Carry over to Summary Bid Schedule)					

OPHIR CANYON AREA					
Item Of Work	Description of Work and Tag Number	Spec Section	Estimated Quantity	Bid Price Amount (\$)	Variation Quantity Unit Price (\$/Unit)
1)	Access Improvement	0230	Lump sum	\$	n/a
2)	Mine Closure	0250			
	a) Hand Backfill				
	3050426VO018		14 cyd	\$	\$/cyd
	3050426VO019		62 cyd	\$	\$/cyd
	3050426IO001		4 cyd	\$	\$/cyd
	3050427HO008		8 cyd	\$	\$/cyd
	b) Equipment Backfill				
	3050428HO001		32 cyd	\$	\$/cyd
	3050428HO002		40 cyd	\$	\$/cyd
	3050428HO003		6 cyd	\$	\$/cyd
Ophir Canyon Area: Mine Closure SUBTOTAL (Carry over to Summary Bid Schedule)				\$	

SOUTH FORK OPHIR CANYON/MEADOW CANYON AREA					
Item Of Work	Description of Work and Tag Number	Spec Section	Estimated Quantity	Bid Price Amount (\$)	Variation Quantity Unit Price (\$/Unit)
1)	Access Improvement	0230	Lump sum	\$	n/a
2)	Mine Closure	0250			

Ophir Canyon Project
Bid Schedule

SOUTH FORK OPHIR CANYON/MEADOW CANYON AREA					
	a) Equipment Backfill				
	3050332VO001		130 cyd	\$	\$ /cyd
	b) Bat Gate				
	3050330HO001		3 ft ²	\$	\$ / ft ²
	3050330HO002		8 ft ²	\$	\$ /ft ²
South Fork Ophir Canyon/Meadow Canyon Area: Mine Closure					
SUBTOTAL					
(Carry over to Summary Bid Schedule)				\$	

LION HILL AREA					
Item Of Work	Description of Work and Tag Number	Spec Section	Estimated Quantity	Bid Price Amount (\$)	Variation Quantity Unit Price (\$/Unit)
1)	Access Improvement	0230	Lump sum	\$	n/a
2)	Mine Closure	0250			
	a) Hand Backfill				
	3050425HO003		11 cyd	\$	\$ /cyd
	3050426HO002		10 cyd	\$	\$ /cyd
	3050426HO003		6 cyd	\$	\$ /cyd
	3050426HO004		19 cyd	\$	\$ /cyd
	3050426HO008		8 cyd	\$	\$ /cyd
	3050426HO009		11 cyd	\$	\$ /cyd
	3050426HO011		12 cyd	\$	\$ /cyd
	3050426HO013		11 cyd	\$	\$ /cyd
	3050426HO014		10 cyd	\$	\$ /cyd
	3050426HO015		4 cyd	\$	\$ /cyd
	3050426HO016		8 cyd	\$	\$ /cyd
	3050426HO018		19 cyd	\$	\$ /cyd

LION HILL AREA					
	a) hand backfill (Cont.)				
	3050426VO001		108 cyd	\$	\$ /cyd
	3050426VO002		46 cyd	\$	\$ /cyd
	3050426VO003		100 cyd	\$	\$ /cyd
	3050426VO004		190 cyd	\$	\$ /cyd
	3050426VO005		98 cyd	\$	\$ /cyd
	3050426VO006		75 cyd	\$	\$ /cyd
	3050426VO007		30 cyd	\$	\$ /cyd
	b) Equipment Backfill				
	3050425HO001		13 cyd	\$	\$ /cyd
	3050425HO002		7 cyd	\$	\$ /cyd
	3050425HO004		10 cyd	\$	\$ /cyd
	3050425HO006		7 cyd	\$	\$ /cyd
	3050425HO007		7 cyd	\$	\$ /cyd
	3050425HO008		20 cyd	\$	\$ /cyd
	3050425HO009		8 cyd	\$	\$ /cyd
	3050425HO010		19 cyd	\$	\$ /cyd
	3050425HO011		17 cyd	\$	\$ /cyd
	3050425HO012		4 cyd	\$	\$ /cyd
	3050425HO013		10 cyd	\$	\$ /cyd
	3050425HO014		10 cyd	\$	\$ /cyd
	3050425HO015		10 cyd	\$	\$ /cyd
	3050425HO018		51 cyd	\$	\$ /cyd
	3050425HO019		51 cyd	\$	\$ /cyd
	3050425HO020		19 cyd	\$	\$ /cyd
	3050425HO021		10 cyd	\$	\$ /cyd
	3050425HO022		10 cyd	\$	\$ /cyd
	3050425HO023		10 cyd	\$	\$ /cyd
	3050425HO024		10 cyd	\$	\$ /cyd
	3050425VO001		104 cyd	\$	\$ /cyd
	3050425VO002		26 cyd	\$	\$ /cyd
	3050425VO003		50 cyd	\$	\$ /cyd
	3050425VO004		55 cyd	\$	\$ /cyd
	3050425VO005		80 cyd	\$	\$ /cyd

Ophir Canyon Project
 Bid Schedule

LION HILL AREA					
b) Equipment Backfill (Cont.)					
3050425VO006		60 cyd	\$	\$	/cyd
3050425VO007		16 cyd	\$	\$	/cyd
3050426HO001		11 cyd	\$	\$	/cyd
3050426HO005		10 cyd	\$	\$	/cyd
3050426HO006		7 cyd	\$	\$	/cyd
3050426HO019		27 cyd	\$	\$	/cyd
3050426HO020		22 cyd	\$	\$	/cyd
3050426HO021		33 cyd	\$	\$	/cyd
3050426VO008		27 cyd	\$	\$	/cyd
3050426VO009		51 cyd	\$	\$	/cyd
3050426VO010		22 cyd	\$	\$	/cyd
3050426VO011		238 cyd	\$	\$	/cyd
3050426VO012		95 cyd	\$	\$	/cyd
3050426VO013		41 cyd	\$	\$	/cyd
3050426VO014		149 cyd	\$	\$	/cyd
3050426VO015		54 cyd	\$	\$	/cyd
3050426VO016		4 cyd	\$	\$	/cyd
3050426VO017		2000 cyd	\$	\$	/cyd
3050426VO017B		500 cyd	\$	\$	/cyd
c) Bat Gate					
3050425HO005		30 ft ²	\$	\$	/ft ²
3050425HO016		33 ft ²	\$	\$	/ft ²
3050425HO017		4 ft ²	\$	\$	/ft ²
d) Native Stone Wall					
3050426HO007		42 ft ²	\$	\$	/ft ²
3050426HO010		30 ft ²	\$	\$	/ft ²
3050426HO012		6 ft ²	\$	\$	/ft ²
3050426HO017		21 ft ²	\$	\$	/ft ²
Lion Hill Area: Mine Closure SUBTOTAL					
(Carry over to Summary Bid Schedule)			\$		

SILVEROPOLIS HILL AREA					
Item Of Work	Description of Work and Tag Number	Spec Section	Estimated Quantity	Bid Price Amount (\$)	Variation Quantity Unit Price (\$/Unit)
1)	Access Improvement	0230	lump sum	\$	n/a
2)	Mine Closure	0250			
	a) Hand Backfill				
	3050424HO001		4 cyd	\$	\$ /cyd
	3050425HO025		6 cyd	\$	\$ /cyd
	3050425HO029		6 cyd	\$	\$ /cyd
	3050425HO032		9 cyd	\$	\$ /cyd
	3050425HO033		3 cyd	\$	\$ /cyd
	3050425HO036		6 cyd	\$	\$ /cyd
	3050425HO037		5 cyd	\$	\$ /cyd
	3050425HO038		6 cyd	\$	\$ /cyd
	3050425HO042		6 cyd	\$	\$ /cyd
	3050425HO043		6 cyd	\$	\$ /cyd
	3050425HO044		8 cyd	\$	\$ /cyd
	3050425HO045		8 cyd	\$	\$ /cyd
	3050425HO046		16 cyd	\$	\$ /cyd
	3050425VO008		11 cyd	\$	\$ /cyd
	3050425VO009		21 cyd	\$	\$ /cyd
	b) Equipment Backfill				
	3050425HO040		23 cyd	\$	\$ /cyd
	c) Bat Gate				
	3050425HO026		20 ft ²	\$	\$ /ft ²
	3050425HO027		42 ft ²	\$	\$ /ft ²
	3050425HO028		90 ft ²	\$	\$ /ft ²
	3050425HO034		63 ft ²	\$	\$ /ft ²

Ophir Canyon Project
Bid Schedule

SILVEROPOLIS HILL AREA					
	c) Bat Gate (Cont.)				
	3050425HO041		36 ft ²	\$	\$ /ft ²
	d) Grate				
	3050425VO010		35 ft ²	\$	\$ /cyd
	3050425VO011		18 ft ²	\$	\$ /cyd
	e) Block Wall				
	3050425HO030		32 ft ²	\$	\$ /ft ²
	3050425HO031		25 ft ²	\$	\$ /ft ²
	3050425HO035		25 ft ²	\$	\$ /ft ²
	3050425HO039		15 ft ²	\$	\$ /ft ²
Silveropolis Area: Mine Closure SUBTOTAL (Carry over to Summary Bid Schedule)				\$	

ROVER HILL AREA					
Item Of Work	Description of Work and Tag Number	Spec Section	Estimated Quantity	Bid Price Amount (\$)	Variation Quantity Unit Price (\$/Unit)
1)	Access Improvement	0230	lump sum	\$	n/a
2)	Mine Closure	0250			
	a) Hand Backfill				
	3050436HO001		8 cyd	\$	\$ /cyd
	3050436HO004		3 cyd	\$	\$ /cyd
	b) Equipment Backfill				
	3050331IO001		10 cyd	\$	\$ /cyd
	3050331VO001		190 cyd	\$	\$ /cyd

ROVER HILL AREA					
	3050331VO002		120 cyd	\$	\$ /cyd
	3050433HO004		4 cyd	\$	\$ /cyd
	3050433VO007		150 cyd	\$	\$ /cyd
	3050436HO002		45 cyd	\$	\$ /cyd
	3050436HO003		60 cyd	\$	\$ /cyd
	3050436VO001		120 cyd	\$	\$ / cyd
	3050436VO002		47 cyd	\$	\$ /cyd
	3050436VO003		105 cyd	\$	\$ /cyd
	3050436VO004		16 cyd	\$	\$ /cyd
Rover Hill Area: Mine Closure SUBTOTAL				\$	
(Carry over to Summary Bid Schedule)					

Contract Form

Contract # _____

1. CONTRACTING PARTIES: This contract is between the following agency of the State of Utah:

Department of Natural Resources 560 Division of Oil, Gas and Mining, referred to as OWNER,
Agency Name Agency Code Division

and the following CONTRACTOR:

Name _____

Address _____

City _____ State _____ Zip _____

Contact Person _____

Phone _____ E-mail Address _____

LEGAL STATUS OF CONTRACTOR

- ☐ Sole Proprietor
☐ Non-Profit Corporation
☐ For-Profit Corporation
☐ Partnership
☐ Government Agency

Federal Tax ID# _____

Vendor # _____

Commodity Code # 96273

FI-NET Accounting Codes: Ophir Canyon Project

Fund	Agency	Org	Approp. Unit	Activity (Mine)	Grant Category	Project or Job
100	560	2881	REG		GSP4	NA 148 01 G

2. GENERAL PURPOSE OF CONTRACT: The general purpose of this contract is for reclamation construction of abandoned mine sites in Tooele County, Utah, referred to as the Ophir Canyon Project.
3. PROCUREMENT: This contract is entered into as a result of the procurement process on Bid # ***PM, Requisition # RX 560 52000000008, FY05, or the attached pre-approved sole source.
4. CONTRACT PERIOD: Effective date ***MONTH DAY, 2005. Termination date ***MONTH DAY, 2005 unless terminated early or extended in accordance with the terms and conditions of this contract. Renewal options (if any) None.
5. CONTRACT COSTS: CONTRACTOR will be paid a maximum of \$ *** for costs authorized by this contract.
6. ATTACHMENT A: Division of Purchasing's Standard Terms and Conditions.

ATTACHMENT B: SCOPE OF WORK, hereinafter the WORK, to be performed is that contained in the Drawings and Technical Specifications prepared by: the Division of Oil, Gas & Mining and entitled *TECHNICAL SPECIFICATIONS: Ophir Canyon Project Reclamation Construction*; the General Specifications prepared by the Division of Oil, Gas and Mining entitled *GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS*, dated June, 1988; and the Supplementary Conditions listed in the Technical Specifications cited above.

ATTACHMENT C: Division of Oil, Gas and Mining Construction Terms and Conditions.

ATTACHMENT D: Cost Schedule

Contract
Ophir Canyon Project

Any conflicts between Attachment A and other Attachments will be resolved in favor of Attachment A.

7. DOCUMENTS INCORPORATED INTO THIS CONTRACT BY REFERENCE BUT NOT ATTACHED:

- a. All other governmental laws, regulations, or actions applicable to the goods and/or services authorized by this contract.
- b. Utah State Procurement Code, Procurement Rules, and CONTRACTOR'S response to Bid #_ PM***, dated ***MONTH DAY, YEAR.

IN WITNESS WHEREOF, the parties sign and cause this contract to be executed.

FOR THE CONTRACTOR:

ATTEST:

Secretary of Corporation or Witness

CONTRACTOR:

BY: _____

NAME: _____

TITLE: _____

TAXPAYER ID #: _____

FOR THE STATE OF UTAH:

APPROVED FOR AVAILABILITY OF FUNDS:
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS & MINING

Mark Mesch, AMR Administrator

John Baza, Director

Paula Dupin-Zahn, Acting Budget/Accounting

APPROVED FOR EXPENDITURE:
DIVISION OF PURCHASING

DIVISION OF FINANCE

Douglas G. Richins, Director of Purchasing

(for) Kim S. Thorne, Director of Finance

Agency Contact	Phone Number	Fax Number	E-mail Address
Amber Fortner	(801) 538-5437	(801) 359-3940	amberfortner@utah.gov

APPROVED AS TO FORM BY
ATTORNEY GENERAL'S OFFICE
DOGM Construction Contract (revised 06/17/04)
Reference: Division of Finance Form FI 84 (revised 08/26/03)

ATTACHMENT A
STANDARD TERMS AND CONDITIONS

1. AUTHORITY: Provisions of this contract are pursuant to the authority set forth in 63-56, Utah Code Annotated, 1953, as amended, Utah State Procurement Rules (Utah Administrative Code Section R33), and related statutes which permit the State to purchase certain specified services, and other approved purchases for the State.

2. CONTRACT JURISDICTION, CHOICE OF LAW, AND VENUE: The provisions of this contract shall be governed by the laws of the State of Utah. The parties will submit to the jurisdiction of the courts of the State of Utah for any dispute arising out of this Contract or the breach thereof. Venue shall be in Salt Lake City, in the Third Judicial District Court for Salt Lake County.

3. LAWS AND REGULATIONS: Any and all supplies, services and equipment furnished will comply fully with all applicable Federal and State laws and regulations.

4. RECORDS ADMINISTRATION: The CONTRACTOR shall maintain, or supervise the maintenance of all records necessary to properly account for the payments made to the CONTRACTOR for costs authorized by this contract. These records shall be retained by the CONTRACTOR for at least four years after the contract terminates, or until all audits initiated within the four years, have been completed, whichever is later. The CONTRACTOR agrees to allow State and Federal auditors, and State Agency Staff, access to all the records to this contract, for audit and inspection, and monitoring of services. Such access will be during normal business hours, or by appointment.

5. CONFLICT OF INTEREST: CONTRACTOR represents that none of its officers or employees are officers or employees of the State of Utah, unless disclosure has been made in accordance with 67-16-8, Utah Code Annotated, 1953, as amended.

6. CONTRACTOR, AN INDEPENDENT CONTRACTOR: The CONTRACTOR shall be an independent contractor, and as such, shall have no authorization, express or implied, to bind the State to any agreements, settlements, liability, or understanding whatsoever, and agrees not to perform any acts as agent for the State, except as herein expressly set forth. Compensation stated herein shall be the total amount payable to the CONTRACTOR by the State. The CONTRACTOR shall be responsible for the payment of all income tax and social security amounts due as a result of payments received from the State for these contract services. Persons employed by the State and acting under the direction of the State shall not be deemed to be employees or agents of the CONTRACTOR.

7. INDEMNITY CLAUSE: The CONTRACTOR agrees to indemnify, save harmless, and release the State of Utah, and all its officers, agents, volunteers, and employees from and against any and all loss, damages, injury, liability, suits, and proceedings arising out of the performance of this contract which are caused in whole or in part by the negligence of the CONTRACTOR's officers, agents, volunteers, or employees, but not for claims arising from the State's sole negligence.

8. EQUAL OPPORTUNITY CLAUSE: The CONTRACTOR agrees to abide by the provisions of Title VI and VII of the Civil Rights Act of 1964 (42USC 2000e) which prohibits discrimination against any employee or applicant for employment or any applicant or recipient of services, on the basis of race, religion, color, or national origin; and further agrees to abide by Executive Order No. 11246, as amended, which prohibits discrimination on the basis of sex; 45 CFR 90 which prohibits discrimination on the basis of age; and Section 504 of the Rehabilitation Act of 1973, or the Americans with Disabilities Act of 1990 which prohibits discrimination on the basis of disabilities. Also, the CONTRACTOR agrees to abide by Utah's Executive Order, dated March 17, 1993, which prohibits sexual harassment in the work place.

9. SEPARABILITY CLAUSE: A declaration by any court, or any other binding legal source, that any provision of this contract is illegal and void shall not affect the legality and enforceability of any other provision of this contract, unless the provisions are mutually dependent.

10. RENEGOTIATION OR MODIFICATIONS: This contract may be amended, modified, or supplemented only by written amendment to the contract, executed by the same persons or by persons holding the same position as persons who signed the original agreement on behalf of the parties hereto, and attached to the original signed copy of the contract.

Contract
Ophir Canyon Project

11. DEBARMENT: The CONTRACTOR certifies that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily Excluded from participation in this transaction (contract), by any governmental department or agency. If the CONTRACTOR cannot certify this statement, attach a written explanation for review by the State. The CONTRACTOR must notify the State Director of Purchasing within 30 days if debarred by any governmental entity during the Contract period.

12. TERMINATION: Unless otherwise stated in the Special Terms and Conditions, this contract may be terminated, with cause by either party, in advance of the specified termination date, upon written notice being given by the other party. The party in violation will be given ten (10) working days after notification to correct and cease the violations, after which the contract may be terminated for cause. This contract may be terminated without cause, in advance of the specified expiration date, by either party, upon 90 days prior written notice being given the other party. On termination of this contract, all accounts and payments will be processed according to the financial arrangements set forth herein for approved services rendered to date of termination.

13. NONAPPROPRIATION OF FUNDS: The CONTRACTOR acknowledges that the State cannot contract for the payment of funds not yet appropriated by the Utah State Legislature. If funding to the State is reduced due to an order by the Legislature or the Governor, or is required by State law, or if federal funding (when applicable) is not provided, the State may terminate this contract or proportionately reduce the services and purchase obligations and the amount due from the State upon 30 days written notice. In the case that funds are not appropriated or are reduced, the State will reimburse CONTRACTOR for products delivered or services performed through the date of cancellation or reduction, and the State will not be liable for any future commitments, penalties, or liquidated damages.

14. SALES TAX EXEMPTION: The State of Utah's sales and use tax exemption number is E33399. The tangible personal property or services being purchased are being paid from State funds and used in the exercise of that entity's essential functions. If the items being purchased are construction materials, they will be converted into real property by employees of this government entity, unless otherwise stated in the contract.

15. WARRANTY: The CONTRACTOR agrees to warrant and assume responsibility for all products (including hardware, firmware, and/or software products) that it licenses, contracts, or sells to the State of Utah under this contract for a period of one year, unless otherwise specified and mutually agreed upon elsewhere in this contract. The CONTRACTOR (seller) acknowledges that all warranties granted to the buyer by the Uniform Commercial Code of the State of Utah apply to this contract. Product liability disclaimers and/or warranty disclaimers from the seller are not applicable to this contract unless otherwise specified and mutually agreed upon elsewhere in this contract. In general, the CONTRACTOR warrants that: (1) the product will do what the salesperson said it would do, (2) the product will live up to all specific claims that the manufacturer makes in their advertisements, (3) the product will be suitable for the ordinary purposes for which such product is used, (4) the product will be suitable for any special purposes that the State has relied on the CONTRACTOR's skill or judgment to consider when it advised the State about the product, (5) the product has been properly designed and manufactured, and (6) the product is free of significant defects or unusual problems about which the State has not been warned. Remedies available to the State include the following: The CONTRACTOR will repair or replace (at no charge to the State) the product whose nonconformance is discovered and made known to the CONTRACTOR in writing. If the repaired and/or replaced product proves to be inadequate, or fails of its essential purpose, the CONTRACTOR will refund the full amount of any payments that have been made. Nothing in this warranty will be construed to limit any rights or remedies the State of Utah may otherwise have under this contract.

16. PUBLIC INFORMATION: CONTRACTOR agrees that the contract will be a public document, and may be available for distribution. And CONTRACTOR gives the State express permission to make copies of the contract and/or of the response to the solicitation in accordance with the State of Utah Government Records Access and Management Act. The permission to make copies as noted will take precedence over any statements of confidentiality, proprietary information, copyright information, or similar notation.

17. DELIVERY: Unless otherwise specified in this contract, all deliveries will be F.O.B. destination with all transportation and handling charges paid by the CONTRACTOR. Responsibility and liability for loss or damage will remain with CONTRACTOR until final inspection and acceptance when responsibility will pass to the State except as to latent defects, fraud and CONTRACTOR's warranty obligations.

18. ORDERING AND INVOICING: All orders will be shipped promptly in accordance with the delivery schedule. The CONTRACTOR will promptly submit invoices (within 30 days of shipment or delivery of services) to the State.

The State contract number and/or the agency purchase order number shall be listed on all invoices, freight tickets, and correspondence relating to the contract order. The prices paid by the State will be those prices listed in the contract. The State has the right to adjust or return any invoice reflecting incorrect pricing.

19. PAYMENT: Payments are normally made within 30 days following the date the order is delivered or the date a correct invoice is received, whichever is later. All payments to the CONTRACTOR will be remitted by mail unless paid by the State of Utah's Purchasing Card.

20. PATENTS, COPYRIGHTS, ETC.: The CONTRACTOR will release, indemnify and hold the State, its officers, agents and employees harmless from liability of any kind or nature, including the CONTRACTOR's use of any copyrighted or un-copyrighted composition, secret process, patented or un-patented invention, article or appliance furnished or used in the performance of this contract.

21. ASSIGNMENT/SUBCONTRACT: CONTRACTOR will not assign, sell, transfer, subcontract or sublet rights, or delegate responsibilities under this contract, in whole or in part, without the prior written approval of the State.

22. DEFAULT AND REMEDIES: Any of the following events will constitute cause for the State to declare CONTRACTOR in default of the contract: 1. Nonperformance of contractual requirements; 2. A material breach of any term or condition of this contract. The State will issue a written notice of default providing a ten (10) day period in which CONTRACTOR will have an opportunity to cure. Time allowed for cure will not diminish or eliminate CONTRACTOR's liability for damages. If the default remains, after CONTRACTOR has been provided the opportunity to cure, the State may do one or more of the following: 1. Exercise any remedy provided by law; 2. Terminate this contract and any related contracts or portions thereof; 3. Impose liquidated damages, if liquidated damages are listed in the contract; 4. Suspend CONTRACTOR from receiving future solicitations.

23. FORCE MAJEURE: Neither party to this contract will be held responsible for delay or default caused by fire, riot, acts of God and/or war which is beyond that party's reasonable control. The State may terminate this contract after determining such delay or default will reasonably prevent successful performance of the contract.

24. PROCUREMENT ETHICS: The CONTRACTOR understands that a person who is interested in any way in the sale of any supplies, services, construction, or insurance to the State of Utah is violating the law if the person gives or offers to give any compensation, gratuity, contribution, loan or reward, or any promise thereof to any person acting as a procurement officer on behalf of the State, or who in any official capacity participates in the procurement of such supplies, services, construction, or insurance, whether it is given for their own use or for the use or benefit of any other person or organization (63-56-73, Utah Code Annotated, 1953, as amended).

25. CONFLICT OF TERMS: CONTRACTOR Terms and Conditions that apply must be in writing and attached to the contract. No other Terms and Conditions will apply to this contract including terms listed or referenced on a CONTRACTOR's website, terms listed in a CONTRACTOR quotation/sales order, etc. In the event of any conflict in the contract terms and conditions, the order of precedence shall be: 1. State Standard Terms and Conditions; 2. State Special Terms and Conditions; 3. CONTRACTOR Terms and Conditions.

DOGM Standard Terms and Conditions (revised 06/11/04)

Reference: Division of Purchasing Standard Terms and Conditions (revised 11/21/03)

End Attachment A

Contract
Ophir Canyon Project

ATTACHMENT B
SCOPE OF WORK

SCOPE OF WORK, hereinafter the WORK, to be performed is that contained in the Drawings and Technical Specifications prepared by: the Division of Oil, Gas & Mining and entitled *TECHNICAL SPECIFICATIONS: Ophir Canyon Project Reclamation Construction*; the General Specifications prepared by the Division of Oil, Gas and Mining entitled *GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS*, dated June 1988; and the Supplementary Conditions listed in the Technical Specifications cited above.

The CONTRACTOR agrees to furnish all labor, materials and equipment to complete the WORK as described the Drawings, Specifications, and addenda to the specifications which are hereby made a part of this CONTRACT by reference. It is understood and agreed by the parties hereto that all WORK will be performed as required in the Drawings and Specifications and will be subject to inspection and approval prior to final acceptance by the OWNER. The relationship of the CONTRACTOR to the OWNER hereunder is that of an independent CONTRACTOR.

End Attachment B

ATTACHMENT C
DIVISION OF OIL, GAS AND MINING
CONSTRUCTION TERMS AND CONDITIONS

ARTICLE 1. TIME OF COMPLETION. The WORK under this CONTRACT shall be commenced upon notice to proceed and shall be completed within 60 calendar days after date marked on registered receipt of said Notice to Proceed and no later than ***MONTH DAY, YEAR. WORK delays caused by weather may, at the discretion of the OWNER, extend the completion date. CONTRACTOR also agrees to the liquidated damages provisions of Article 12.

ARTICLE 2. PAYMENT. OWNER will promptly pay for services performed by the CONTRACTOR. Vouchers for reimbursement of expenditures under this Agreement must be filed promptly with OWNER's Representative by the tenth day of the month following the month in which WORK has been performed. OWNER will withhold from payment an amount not to exceed 10% of the total CONTRACT cost, except for Mobilization, which will have 40% withheld, until all WORK has been performed by the CONTRACTOR and is approved and accepted by OWNER.

ARTICLE 3. INDEBTEDNESS. Before final payment is made, the CONTRACTOR must submit evidence including lien waivers, satisfactory to the OWNER that all payrolls, materials bills, subcontracts and outstanding indebtedness in connection with the WORK have been paid or that arrangements have been made for their payment. Payment will be made without unnecessary delay after receipt of such evidence as mentioned above and Final Acceptance of the WORK by the OWNER.

ARTICLE 4. ADDITIONAL WORK. It is understood and agreed by the parties hereto that no money will be paid to the CONTRACTOR for any additional WORK, labor or materials furnished unless a new CONTRACT in the form of a Change Order or a modification hereof for such additional materials or labor has been executed by OWNER and CONTRACTOR. The OWNER specifically reserves the right to modify or amend this CONTRACT and the total sum due hereunder either by enlarging or restricting the WORK through a change order.

ARTICLE 5. ACCEPTANCE. The WORK will be inspected for acceptance by the OWNER promptly upon receipt of notice from the CONTRACTOR that the WORK is complete and ready for inspection.

ARTICLE 6. DISPUTES PERTAINING TO PAYMENT FOR WORK. Any disputes which may arise respecting the value of any WORK done, or any WORK omitted, or of any ADDITIONAL WORK which CONTRACTOR may be required to perform, or respecting any other elements involved in this CONTRACT, will be decided by the Director of the Division of Oil, Gas & Mining, acting as the OWNER.

ARTICLE 7. TERMINATION OF CONTRACT

- a. If the CONTRACTOR is adjudged bankrupt or if the CONTRACTOR makes a general assignment for the benefit of CONTRACTOR'S creditors or if a receiver is appointed on account of CONTRACTOR'S insolvency, or if CONTRACTOR or any of his/her Subcontractors violates any of the provisions of this CONTRACT, or if the

CONTRACTOR does not perform the WORK according to the Specifications, the OWNER may serve written notice upon CONTRACTOR of its intention to terminate the CONTRACT; and unless within ten (10) days after the serving of the notice, the violation ceases, the OWNER then may take over the WORK and at the expense of the CONTRACTOR, complete it by contract or by any other method it may deem advisable. The CONTRACTOR will be liable to the OWNER for any excess cost incurred by the OWNER and the OWNER may, without liability for so doing, take possession of and utilize in completing the WORK, such materials, appliances, paint, and any other property belonging to the CONTRACTOR as may be on the site of the WORK.

- b. OWNER may terminate this Agreement upon thirty days written notice to CONTRACTOR in the event the U.S. Department of the Interior fails to grant to OWNER sufficient funds to meet its obligations under this Agreement. In such event, CONTRACTOR will be entitled to receive just and equitable compensation for any satisfactory WORK completed up to the time of termination.

ARTICLE 8. OWNER'S RIGHT TO WITHHOLD CERTAIN AMOUNT AND MAKE APPLICATION THEREOF. The OWNER may withhold from payment to the CONTRACTOR an amount or amounts as, in the OWNER'S judgment, may be necessary to pay just claims against the CONTRACTOR or any Subcontractor for labor and services rendered and materials furnished in and about the WORK. The OWNER in its discretion may apply the withheld amounts on the payment of such claims. In so doing the OWNER will be deemed the agent of the CONTRACTOR and payments so made by the OWNER will be considered as a payment made under the CONTRACT by the OWNER to the CONTRACTOR and the OWNER will not be liable to the CONTRACTOR for any such payments made in good faith. Such payments may be made without prior determination of the claim or claims.

ARTICLE 9. INDEPENDENT CONTRACTOR. The CONTRACTOR will be considered an independent contractor, and, as such, has no authorization, expressed or implied, to bind the State of Utah or the OWNER to any agreement, settlement, liability or understanding whatsoever, nor to perform any acts as agent for the State of Utah, except as herein expressly set forth. The compensation provided for herein will be the total compensation payable hereunder by the State of Utah or the OWNER.

ARTICLE 10. LIABILITY AND INDEMNIFICATION. It is agreed that the CONTRACTOR will at all times protect and indemnify and save harmless, the State of Utah and all institutions, agencies, departments, authorities and instrumentalities of the State of Utah and any member of their governing bodies or of their boards or commissions or any of their elected or appointed officers or any of their employees or authorized volunteers, or the private landowners who have consented to reclamation construction and/or have consented to allow ingress or egress to a reclamation site, as described in the general conditions of the project specifications which are included herein by reference, from any and all claims, damages of every kind and nature made, rendered or incurred by or in behalf of any person or corporation whatsoever, including the parties hereto and their employees that may arise, occur or grow out of any acts, actions, work or other activity done by the CONTRACTOR in the performance and execution of this CONTRACT.

ARTICLE 11. SUBCONTRACTOR. No part of this CONTRACT may be sublet by the CONTRACTOR without the prior written approval of the OWNER. The CONTRACTOR and the OWNER for themselves, their heirs, successors, executors, and administrators, hereby agree to the full performance of the covenants herein contained.

ARTICLE 12. LIQUIDATED DAMAGES. In the event the CONTRACTOR fails to complete the WORK within the time agreed upon in CONTRACTOR's schedule as set forth in Article 2, or within such additional time as may have been allowed by the OWNER, there will be deducted from any moneys due or that may become due the CONTRACTOR the sum of \$781.00 per day for each and every calendar day beyond the agreed or extended completion day that the WORK remains uncompleted. Such sum is fixed and agreed upon by the OWNER and the CONTRACTOR as liquidated damages due the OWNER by reason of the inconvenience and added costs of administration, engineering and supervision resulting from the CONTRACTOR's default, and not as a penalty.

Permitting the CONTRACTOR to continue and finish the WORK or any part of it after the time fixed for its completion, or after the date to which the time for completion may have been extended, in no way operates as a waiver on the part of the OWNER of any of OWNER'S rights under the CONTRACT.

ARTICLE 13. DEFAULT: In the event of default by the CONTRACTOR, termination may be executed as described by the Termination for Default Clause of the DIVISION OF OIL, GAS AND MINING GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS.

Contract
Ophir Canyon Project

ARTICLE 14. NONAPPROPRIATION OF FUNDS: Financial obligations of the OWNER payable after the current fiscal year are contingent upon funds for the purpose being appropriated, budgeted or otherwise made available. If funds are not appropriated or otherwise available to continue the payment, this contract may be terminated without penalty by giving thirty (30) days written notice.

| ARTICLE 15. CERTIFICATIONS: PART A: Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – Lower Tier Covered Transactions. 1) The CONTRACTOR certifies that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily Excluded from participation in this transaction (contract), by any Federal department or agency. 2) Where the CONTRACTOR is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal. PART B: Certification Regarding Lobbying. The undersigned certifies, to the best of his or her knowledge and belief, that: 1) No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of an agency, a Member of Congress and officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement. 2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by Section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

The CONTRACTOR was selected for this contract in accordance with the State of Utah, Division of Purchasing's Regulations for the Procurement of Construction and Professional Services.

DOGM Construction Terms and Conditions (revised 09/24/03)

End Attachment C

ATTACHMENT D
COST SCHEDULE

The Cost Schedule will be generated from the Bid Schedule following the award of the CONTRACT.

Performance Bond

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL MEN BY THESE PRESENTS:

That _____, hereinafter referred to as the "Principal," and _____, a corporation organized and existing under the laws of the State of _____, with its principal office in the City of _____, hereinafter referred to as the "Surety," are held and firmly bound unto _____, hereinafter referred to as the "Obligee," in the amount of _____ DOLLARS (\$_____) for the payment whereof, the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain written Contract with the Obligee, dated the _____ day of _____, 20____, which Contract is hereby referred to and made a part hereof as fully and to the same extent as if copied at length herein.

NOW, THEREFORE, the condition of this obligation is such that if the said Principal shall faithfully perform the Contract in accordance with the Plans, Specifications and conditions thereof, then this obligation shall be void; otherwise it shall remain in full force and effect.

PROVIDED, HOWEVER, that this Bond is executed pursuant to the provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as Amended, and all liabilities on this Bond shall be determined in accordance with said provisions to the same extent as if it were copied at length herein.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument this _____ day of _____, 20____.

Principal (Seal)

WITNESS OR ATTESTATION:

By

Surety (Seal)

WITNESS:

By

STATE OF UTAH)
COUNTY OF SALT LAKE) ss
)

_____, being first duly sworn on oath, deposes and says that he/she is the Attorney-in-fact of the _____ and that he/she is duly authorized to execute and deliver the foregoing obligation that said company is authorized to execute the same, and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations.

Subscribed and sworn to before me this _____ day of _____, 20____.

NOTARY PUBLIC
My commission expires: _____

APPROVED AS TO FORM: ATTORNEY GENERAL'S OFFICE

Payment Bond

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL MEN BY THESE PRESENTS:

That _____, hereinafter referred to as the "Principal," and _____, a corporation organized and existing under the laws of the State of _____, with its principal office in the City of _____, hereinafter referred to as the "Surety," are held and firmly bound unto _____, hereinafter referred to as the "Obligee," in the amount of _____ DOLLARS (\$_____) for the payment whereof, the said Principal and surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain written Contract with the Obligee, dated the _____ day of _____, 20_____, which Contract is hereby referred to and made a part hereof as fully and to the same extent as if copied at length herein.

NOW, THEREFORE, the condition of this obligation is such that if the said Principal shall pay all claimants supplying labor or materials to him/her or his/her subcontractors in the prosecution of the work provided for in said Contract, then, this obligation shall be void; otherwise it shall remain in full force and effect.

PROVIDED, HOWEVER, that this bond is executed pursuant to the provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended and all liabilities on this bond to all such claimants shall be determined in accordance with said provisions to the same extent as if it were copies at length herein.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument this _____ day of _____, 20_____.

(Seal)

WITNESS OR ATTESTATION:

(Seal)

WITNESS:

Principal

By

Surety

By

STATE OF UTAH)
) ss
COUNTY OF SALT LAKE)

_____, being first duly sworn on oath, deposes and says that he/she is the Attorney-in-fact of the _____ and that he/she is duly authorized to execute and deliver the foregoing obligation that said company is authorized to execute the same, and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations.

Subscribed and sworn to before me this _____ day of _____, 20_____.

NOTARY PUBLIC

My commission expires: _____

APPROVED AS TO FORM: ATTORNEY GENERAL'S OFFICE

STATE OF UTAH CONTRACT AMENDMENT

AMENDMENT # _____ **to CONTRACT #** _____

TO BE ATTACHED TO AND MADE A PART OF the above numbered contract by and between the State of Utah, Division Of Oil, Gas And Mining, referred to as STATE and, ***, referred to as CONTRACTOR.

Project Name: Ophir Canyon

Project Number : AMR/045/907

THE PARTIES AGREE TO AMEND THE CONTRACT AS FOLLOWS:

- | | |
|---|--|
| <p>1. Contract period:
(original starting date) _____

(current ending date) _____

new ending date _____</p> | <p>2. Contract amount:
(current contract amount) _____

(amendment amount) _____

new contract amount
(add current amount to amendment amount) _____</p> |
|---|--|

3. Change Details:

Fund	Agency	Org	Approp. Unit	Activity (Mine)	Grant Category	Project or Job
100	560	2881	REG		GSP4	NA 148 01 G

ITEM NO.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE, ETC.	INCREASE (DECREASE)
1.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE.	\$0
2.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE.	\$0
3.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE	\$0
4.	SUBTOTAL	\$0
5.	BONDS & INSURANCE (6% of Change Order Amount)	\$0
6.	TOTAL AMOUNT OF CHANGE ORDER	\$0

4. Effective Date of Amendment:

All other conditions and terms in the original contract remain the same.
IN WITNESS WHEREOF, the parties sign and cause the amendment to be executed.

Approved by _____	Date: _____
Contract Rep: _____	
Approved by _____	Date: _____
AMR Admin: _____	
Accepted by _____	Date: _____
Contractor: _____	
Approved by _____	Date: _____
DOGM Budget Off: _____	
Approved by _____	Date: _____
DOGM Director _____	
Approved by _____	Date: _____
Div'n Purchasing: _____	
Approved by _____	Date: _____
Div'n of Finance: _____	

Certificate Of Substantial Completion

UTAH DIVISION OF OIL, GAS AND MINING

PROJECT OPHIR CANYON PROJECT

PROJECT NO. AMR/045/907

CONTRACT NO. 05-####

The WORK performed under the subject CONTRACT has been reviewed on this date and found to be substantially completed.

DEFINITION OF SUBSTANTIAL COMPLETION

The date of substantial completion of a project or specified area of a project is the date when the construction is sufficiently completed in accordance with the Contract Documents, as modified by any change orders agreed to by the parties, so that the OWNER can occupy the project or specified area of the project for the use for which it was intended.

A list of items to be completed or corrected, prepared by the Division of Oil, Gas & Mining and verified by the OWNER, is appended hereto. This list may not be exhaustive, and the failure to include an item on it does not alter the responsibility of the CONTRACTOR to complete all the WORK in accordance with the Contract Documents, including authorized changes thereof.

Division of Oil, Gas & Mining

CONTRACT REPRESENTATIVE DATE

The CONTRACTOR will complete or correct the work on the list of items appended hereto within ____ days from the above date of issuance of this Certificate.

CONTRACTOR

AUTHORIZED REPRESENTATIVE DATE

The OWNER accepts the project or specified area of the project as substantially complete and will assume full possession of the project or specified area of the project at _____ (time) on _____ (date).

Division of Oil, Gas & Mining

OWNER

CONTRACT REPRESENTATIVE DATE

ADMINISTRATOR, AMR DATE

RESPONSIBILITIES AND/OR EXCEPTIONS:

Certificate Of Final Acceptance

UTAH DIVISION OF OIL, GAS AND MINING

PROJECT OPHIR CANYON PROJECT

PROJECT NO. AMR/045/907

CONTRACT NO. 05-####

The WORK performed under the subject CONTRACT has been reviewed on this date and found to be completed.

DEFINITION OF FINAL ACCEPTANCE

The date of final acceptance of a project is the date when the construction is completed in accordance with the Contract Documents, as modified by any change orders agreed to by the parties, so that the OWNER can occupy the project for the use for which it was intended.

Items listed on the Certificate of Substantial Completion, as prepared by the Division of Oil, Gas & Mining, have been completed or corrected and verified by the OWNER as having been completed or corrected.

Division of Oil, Gas & Mining
OWNER

PROJECT MANAGER DATE

CONTRACT REPRESENTATIVE DATE

CONTRACTOR

AUTHORIZED REPRESENTATIVE DATE

The OWNER accepts the project as complete and will assume full possession of the project or specified area of the project at _____pm (time) on _____, 2005 (date).

Division of Oil, Gas & Mining
OWNER

ADMINISTRATOR, AMRP DATE

General Conditions For Abandoned Mine Reclamation Projects

CONTENTS

1. Definitions
2. Correlation and Intent of Documents
3. Copies Furnished
4. Dimensions
5. Detail Drawings and Instructions
6. Drawings and Specifications on the Work
7. Ownership of Drawings
8. Shop Drawings
9. Samples
10. Materials, Appliances, Employees
11. Royalties and Patents
12. Surveys, Permits and Regulations
13. Protection of WORK and Property
14. Inspection of WORK
15. Superintendence and Supervision
16. Changes
17. Claims Based on OWNER's Actions or Omissions
18. Deductions for Uncorrected Work
19. Delays and Extension of Time
20. Correction of WORK Before Final Payment
21. Correction of WORK After Final Payment
22. Termination for Default Clause
23. Application for Payments
25. Liability Insurance
26. Property Insurance
27. Indemnification
28. Guarantee Bonds
29. Liens
30. Assignment
31. Mutual Responsibility of CONTRACTORS
32. Separate Contracts
33. Subcontractors
34. Relations of CONTRACTOR and Subcontractor
35. State's Inspection
36. Contract Representative's Status
37. Contract Representative's Decisions
38. Cash Allowances
39. Use of Premises
40. Cutting, Patching and Digging
41. Cleaning Up
42. Substitutions
43. Laying Out WORK
44. Emergencies
45. Testing of Materials
46. Temporary Enclosing, Drying Out, Etc.
47. Examination of Site
48. Storage and Care of Materials
49. Construction Risks
50. Temporary Appurtenances and Conveniences
51. Scaffolding, Tools, Etc.
52. Sanitary Provisions
53. Refuse
54. Removing Water
55. Taxes
56. Citizens Preferred
57. Code Requirements
58. Nondiscrimination and Affirmative Action
59. Affirmative Action
60. Safety
61. Rubbish Disposal
62. Subcontractors Financial Bid Limits and License Classification
63. Balancing and Testing
64. Substantial Completion
65. Other Prohibited Interests
66. Conflicting Conditions
67. Monthly Progress Meetings
68. Suspension of WORK
69. Differing Site Conditions
70. Price Adjustment
71. Termination for Convenience of the OWNER
72. Liquidated Damages
73. Termination for Breach, Etc.
74. Normal Daylight Hours
75. Normal Working Days
76. Use of Explosives
77. Compliance with Copeland Regulations
78. Overtime Compensation
79. Clean Air and Water

General Conditions

DIVISION OF OIL, GAS AND MINING GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS

1. Definitions:

- A. The CONTRACT documents consist of the agreement, the general conditions of the CONTRACT, the drawings and specifications, including all modifications thereof incorporated in the documents before their execution. These form the CONTRACT.
- B. The OWNER and the CONTRACTOR or pronouns used in place thereof, are those mentioned as such in the agreement. They are treated throughout the CONTRACT documents as if each were in the singular number.
- C. The term "Subcontractor," as employed herein, includes anyone having a direct CONTRACT with anyone except the OWNER to provide material and/or labor under this CONTRACT, and it includes one who furnishes material worked to a special design according to the plans and/or specifications of this WORK, but does not include one who merely furnishes material not so worked.
- D. The word "state," or pronoun used in place thereof, is to designate the State of Utah, as represented by the Division of Oil, Gas & Mining.
- E. The word "OWNER," or pronoun used in place thereof, is to designate the State of Utah, as represented by the Division of Oil, Gas & Mining.
- F. The term "WORK" of the CONTRACTOR or subcontractor includes labor or materials or both, and the SCOPE OF WORK.
- G. The term "site" shall be used to refer to all areas where the WORK is to be performed.
- H. The term "engineer" shall be used to refer to a consultant representing the OWNER or a designated representative of the OWNER.
- I. The applicable laws and regulations of the State of Utah shall govern the execution of the WORK embodied in the contract documents.

2. Correlation and Intent of Documents:

The CONTRACT documents are complementary, and what is called for by any one shall be as binding as if called for by all. The intention of the documents is to include all labor and materials, equipment, and transportation necessary for the proper and complete execution of the WORK, and equal in quality and workmanship to the highest standards. The CONTRACTOR is to abide by and comply with the true intent and meaning of all drawings and specifications taken as a whole and is not to avail himself to the detriment of the WORK, of any manifestly unintentional error or omission, should any exist. All minor details of WORK which are not shown on the plans, as well as such items as are not specifically mentioned in the specifications but are obviously necessary for the proper

completion of the WORK, shall be considered as incidental and as being part of the WORK.

3. Copies Furnished:

Unless otherwise provided in the CONTRACT documents, the OWNER will furnish the CONTRACTOR, free of charge to the CONTRACTOR, copies of drawings and specifications, reasonably necessary for the execution of the WORK.

4. Dimensions:

Where no figures or memoranda are given, the drawings shall be accurately followed according to their scale, but figures or memoranda are to be preferred to the scale, in all cases of difference, and the larger scale details shall take preference over those of smaller scale.

5. Detail Drawings and Instructions:

The OWNER shall furnish, with reasonable promptness, additional instructions, by means of drawings or otherwise, necessary for the proper execution of the WORK. All such drawings and instructions shall be consistent with the CONTRACT documents, true developments thereof, and reasonably inferable therefrom. The WORK shall be executed in conformity with the drawings and instructions. Any WORK performed by the CONTRACTOR in advance of these drawings and instructions shall be entirely at the CONTRACTOR's risk.

6. Drawings and Specifications on the Work:

The CONTRACTOR shall keep at the jobsite one copy of all drawings and specifications on the WORK in good order, available to the OWNER and their representatives.

7. Ownership of Drawings:

All copies of drawings and specifications furnished the CONTRACTOR by the OWNER are the property of the OWNER. They are not to be used by the CONTRACTOR on other work, and are to be returned to the OWNER, upon request, at the completion of the WORK.

8. Shop Drawings/As Built Drawings:

The CONTRACTOR shall submit to the OWNER, with such promptness as to cause no delay in his/her WORK or in that of any other CONTRACTOR, six copies of all shop/as built drawings or setting drawings and schedules required for the WORK of the various trades and the OWNER shall pass upon them with reasonable promptness. The CONTRACTOR shall submit to the OWNER, with such promptness, making desired corrections. Said corrections shall pertain to conformance with the basic design concepts embodied in the CONTRACT documents. The CONTRACTOR shall make any corrections required by the OWNER. The OWNER shall distribute the corrected drawings as follows: Two drawings to the OWNER; three drawings back to the general CONTRACTOR; and one drawing to the project inspector (if one is assigned to the job). The OWNER's approval of such drawings or schedules shall not relieve

the CONTRACTOR from responsibility for deviations from drawings or specifications, unless he/she has in writing called the OWNER's attention to such deviations at the time of submission, and has received the OWNER's written approval of such deviation; nor shall it relieve him/her from responsibility for errors of any sort in shop/as built drawings or schedules.

9. Samples:

The CONTRACTOR shall furnish to the OWNER for approval, all samples as directed. The WORK shall be in accordance with approved samples.

10. Materials, Appliances, Employees:

Unless otherwise stipulated, the CONTRACTOR shall provide and pay for all materials, labor, water, tools, equipment, light, power, transportation, and other facilities and services necessary for the execution and completion of the WORK.

Unless otherwise specified, all materials shall be new, and both workmanship and materials shall be of high quality. The CONTRACTOR shall, if required, furnish satisfactory evidence as to the kind and quality of materials.

The CONTRACTOR shall at all times enforce strict discipline and order among his/her employees, and shall not employ on the WORK any unfit person or anyone not skilled in the work assigned to him/her.

11. Royalties and Patents:

The CONTRACTOR shall pay all royalties and license fees. He/she shall defend all suits or claims for infringement of any patent rights and shall save the OWNER harmless from loss on account thereof.

12. Surveys, Permits and Regulations:

The OWNER shall furnish surveys necessary to establish site boundaries and existing topography. The OWNER shall provide those surveys necessary for laying out the WORK.

The CONTRACTOR shall give all notices and comply with all applicable laws, ordinances, rules and regulations bearing on the conduct of the WORK as drawn and specified. If the CONTRACTOR observes that the drawings and specifications are at variance therewith, he/she shall promptly notify the OWNER in writing, and any necessary changes shall be adjusted as provided in the contract for changes in the WORK. If the CONTRACTOR performs any work knowing it to be contrary to such laws, ordinances, rules and regulations and without such notice to the OWNER, he/she shall bear all costs arising therefrom.

Inasmuch as the WORK under this contract will be performed for the State of Utah, it will not be necessary to take out local building permits, electrical permits and plumbing permits, nor will it be necessary to pay fees for inspections pertaining thereto; however, it will be necessary to obtain a permit from the city, county, and or Department of Transportation having jurisdiction

whenever the WORK involves their property. The CONTRACTOR shall cooperate as necessary with these jurisdictions to comply with all their requirements, which may include a bond and permit fee.

Fees for connection to utilities such as water and power must be borne by the CONTRACTOR.

13. Protection of Work and Property:

The CONTRACTOR shall continuously maintain adequate protection of all his/her WORK from damage and shall protect the OWNER's property from injury or loss arising in connection with this CONTRACT. CONTRACTOR shall make good any such damage, injury, or loss, except such as may be directly due to errors in the CONTRACT documents or caused by agents or employees of the OWNER. CONTRACTOR shall adequately protect adjacent property as provided by law and the CONTRACT documents.

The CONTRACTOR shall take all necessary precautions for the safety of employees on the WORK and shall comply with all applicable provisions of federal, state and municipal safety laws and building codes to prevent accidents or injury to persons on, about, or adjacent to the premises where the WORK is being performed. CONTRACTOR shall erect and properly maintain at all times, as required by the conditions and progress of the WORK, all necessary safeguards for the protection of workers and the public and shall post danger signs warning against hazardous conditions.

14. Inspection of Work:

The OWNER and the representatives thereof and authorized federal government inspectors shall at all times have access to the WORK, and the CONTRACTOR shall provide proper facilities for such access and for inspection.

If the specifications or the OWNER requires any work to be specially tested or approved, the CONTRACTOR shall give the OWNER timely notice of its readiness for inspection. Inspections shall be promptly made and, where practicable, at the source of supply. If any WORK should be covered up without approval or consent of the OWNER, it must, if required by the OWNER, be uncovered for examination at the CONTRACTOR's expense.

15. Superintendence and Supervision:

The CONTRACTOR shall keep on the WORK, during its progress, a competent superintendent and any necessary assistants, all satisfactory to the OWNER. The superintendent shall represent the CONTRACTOR in his/her absence, and all directions given to superintendent shall be as binding as if given to the CONTRACTOR.

The CONTRACTOR shall give efficient supervision to the WORK, using his/her best skill and attention. CONTRACTOR shall carefully study and compare all drawings, specifications and other instructions, and shall at once report to the OWNER any error, inconsistency,

General Conditions

or omission which CONTRACTOR may discover, but shall not be held responsible for their existence or discovery.

16. Changes:

- A. Change Order. The OWNER, at any time, unilaterally and without notice to sureties, in writing designated or indicated to be a change order, may order:
- (1) Changes in the WORK within the scope of this CONTRACT;
 - (2) Changes in the time for performance of this CONTRACT that do not alter the scope of WORK of this CONTRACT; and/or
 - (3) Changes necessary to continue the WORK or to accommodate the OWNER with essential services required to complete the WORK as normally intended in accordance with specifications.
- B. Adjustments of Price or Time for Performance. If any change order increases or decreases the CONTRACTOR's cost of, or the time required for, performance of any part of the WORK under this CONTRACT, whether changed or not changed by any such change order, an equitable adjustment shall be made in the contract price or completion date, or both, and this contract shall be modified in writing accordingly. Any adjustment in contract price made pursuant to this clause shall be determined in accordance with the Price Adjustment Clause of this contract.

Failure of the parties to agree to an adjustment shall not excuse the CONTRACTOR from proceeding with this contract as changed, provided that the OWNER promptly and duly makes such provisional adjustments in payments or time for performance as the OWNER deems to be reasonable.

- C. Written Certification. No change order shall be authorized without a written certification, signed by an official of the OWNER responsible for monitoring and reporting the status of the costs of the total project or the contract budget, stating that funds are available therefor.

Where the OWNER has assigned an engineer to the project, the CONTRACTOR shall submit such proposals to the engineer in sufficient number that one copy may be transmitted to the OWNER, one to the project inspector, and one retained by the engineer. Upon acceptance of the proposal by all parties, a written change order will be issued.

Whenever a request for a change order proposal is received by the CONTRACTOR, he/she shall indicate thereon his/her proposed price to be added or deducted from the CONTRACT sum due to the change, together with his/her request for any adjustment in time of final completion of the entire CONTRACT.

It is further agreed that all time extensions to the

completion date of the CONTRACT and any costs or changes in the CONTRACT price from any cause whatsoever that may be incurred as a result of the change order(s) are included in the change order as authorized.

17. Claims Based on OWNER's Actions or Omissions:

Notice of Claim. If any action or omission on the part of the OWNER, requiring performance changes within the scope of the CONTRACT and which are not covered by other clauses of this CONTRACT, constitutes the basis for a claim by the CONTRACTOR for additional compensation, damages, or an extension of time for completion, the CONTRACTOR shall continue the performance of the CONTRACT in compliance with the directions or orders of the OWNER, but by so doing, the CONTRACTOR shall not be deemed to have prejudiced any claim for additional compensation, damages, or an extension of time for completion; provided:

- (1) The CONTRACTOR shall have given written notice to the OWNER:
 - (a) Prior to the commencement of the WORK involved, if at that time the CONTRACTOR knows of the occurrence of such action or omission; or
 - (b) Within thirty (30) days after the CONTRACTOR knows of the occurrence of such action or omission, if the CONTRACTOR did not have such knowledge prior to the commencement of the WORK; or
 - (c) Such further time as may be allowed by the OWNER in writing.

This notice shall state that the CONTRACTOR regards the act or omission as a reason which may entitle the CONTRACTOR to additional compensation, damages, or an extension of time. The OWNER, upon receipt of such notice, may rescind such action, remedy such omission, or take such other steps as may be deemed advisable in the discretion of the OWNER.

- (2) The notice required by Subparagraph (A)(1) of this paragraph describes as clearly as practicable at the time the reasons why the CONTRACTOR believes that additional compensation, damages, or an extension of time may be remedies to which the CONTRACTOR is entitled; and
- (3) The CONTRACTOR maintains and, upon request, makes available to the OWNER within a reasonable time, detailed records to the extent practicable, of the claimed additional costs or basis for an extension of time in connection with such changes.

18. Deductions for Uncorrected Work:

If the OWNER deems it inexpedient to correct WORK damaged or done not in accordance with the CONTRACT, an equitable deduction from the CONTRACT price shall be made therefor.

19. Delays and Extension of Time:

If the CONTRACTOR is significantly delayed at any time in the progress of the WORK by any act or neglect of the OWNER, or of any employee of either, or by any separate CONTRACTOR employed by the OWNER, or by significant changes ordered in the WORK or by strikes, lockouts, fire, unavoidable casualties or any causes beyond the CONTRACTOR's control, or by any cause which the OWNER shall decide justifies the delay, then the time of completion shall be extended for such reasonable time as the OWNER may decide. No action shall lie against the OWNER for damages or other claims due to losses attributable to hindrances or delays from any cause whatsoever, including acts and omissions of the OWNER or its agents; however, the CONTRACTOR may receive an extension of time in which to complete the WORK under this CONTRACT as provided above. The right to apply for such an extension of time shall be the Exclusive remedy available to the CONTRACTOR or any Subcontractor as against the OWNER for such loss.

Any request for extension of time shall be made to the OWNER in writing within seven (7) days from the time of occurrence of cause for delay. In case of a continuing cause of delay, only one claim is necessary.

20. Correction of WORK Before Final Payment:

The CONTRACTOR shall promptly remove from the premises all WORK condemned by the OWNER as failing to conform to the CONTRACT, whether incorporated or not, and the CONTRACTOR shall promptly replace and reexecute his/her own WORK in accordance with the CONTRACT and without expense to the State of Utah and shall bear the expense of making good all WORK of other CONTRACTORS destroyed or damaged by such removal or replacement.

If the CONTRACTOR does not remove such condemned WORK within a reasonable time, fixed by written notice, the OWNER may have the materials removed and stored at the expense of the CONTRACTOR.

21. Correction of WORK After Final Payment:

Neither the final certificate of payment nor any provision in the CONTRACT documents nor partial or entire occupancy of the premises by the OWNER shall constitute an acceptance of WORK not done in accordance with the CONTRACT documents or relieve the CONTRACTOR of liability in respect to any express warranties or responsibility for faulty materials or workmanship. The CONTRACTOR shall remedy any defects in the WORK and pay for any damage to other WORK resulting therefrom which shall appear within a period of one year from the date of substantial completion of the WORK, unless a longer period is specified. The OWNER will give notice of observed defects with reasonable promptness.

22. Termination for Default Clause:

- A. The OWNER may, subject to the provisions of Paragraph (C) below, by written notice of default to the CONTRACTOR, terminate the whole or any part

of this CONTRACT in any one of the following circumstances:

- (1) If the CONTRACTOR fails to perform this CONTRACT within the time specified herein or any extension thereof; or
- (2) If the CONTRACTOR fails to perform any of the other provisions of this CONTRACT, or so fails to make progress as to endanger performance of this CONTRACT in accordance with its terms, and in either of these two circumstances does not cure such failure within a period of five (5) days (or such longer period as the OWNER may authorize in writing) after receipt of notice from the OWNER specifying such failure.

- B. In the event the OWNER terminates this CONTRACT in whole or in part as provided in Paragraph (A) of this clause, the OWNER may procure, upon such terms and in such manner as the OWNER may deem appropriate, supplies or services similar to those so terminated, and the CONTRACTOR shall be liable to the OWNER for any excess costs for such similar supplies or services; provided that the CONTRACTOR shall continue the performance of this CONTRACT to the extent not terminated under the provisions of this clause.

- C. Except with respect to defaults of Subcontractors, the CONTRACTOR shall not be liable for any excess costs if the failure to perform the CONTRACT arises out of causes beyond the control and without the fault or negligence of the CONTRACTOR. Such causes may include, but are not restricted to, acts of God or of the public enemy, acts of the state or federal government in either their sovereign or contractual capacity, fires, floods, epidemics, quarantine restrictions, strikes, freight embargoes, and unusually severe weather; but in every case the failure to perform must be beyond the control and without the fault or negligence of the CONTRACTOR. If the failure to perform is caused by the default of a Subcontractor, and if such default arises out of causes beyond the control of both the CONTRACTOR and the Subcontractor, and without the fault or negligence of either of them, the CONTRACTOR shall not be liable for any excess costs for failure to perform unless the supplies or services to be furnished by the Subcontractor were obtainable from other sources in sufficient time to permit the CONTRACTOR to meet the required delivery or completion schedule.

If this CONTRACT is terminated as provided in Paragraph (A) of this clause, the OWNER, in addition to any other rights provided in this clause, may take over the WORK and prosecute the same to completion, by contract or otherwise, and may take possession of, and utilize in completing the WORK, such materials, equipment and plants as may be on the site of the WORK and necessary therefor. The OWNER may require the CONTRACTOR to transfer title and deliver to the OWNER, in the manner and to the extent directed by the OWNER:

General Conditions

- (1) Any completed portion of the WORK; and
- (2) Any partially completed portion of the WORK and any parts, tools, dies, jigs, fixtures, plans, drawings, information, and CONTRACT rights (hereinafter called "construction materials") as the CONTRACTOR has specifically produced or specifically acquired for the performance of such part of this CONTRACT as has been terminated; and the CONTRACTOR shall, upon direction of the OWNER, protect and preserve property in the possession of the CONTRACTOR in which the OWNER has an interest.

Payment for completed WORK accepted by the OWNER shall be at the contract price. Payment for construction materials delivered to and accepted by the OWNER and for the protection and preservation of property shall be in an amount agreed upon by the CONTRACTOR and OWNER. The OWNER may withhold from amounts otherwise due the CONTRACTOR for such completed WORK or construction materials such sum as the OWNER determines to be necessary to protect the OWNER against loss because of outstanding liens or claims of former lien holders.

- E. If, after notice of termination of the contract under the provisions of this clause, it is determined for any reason that the CONTRACTOR was not in default under the provisions of this clause, or that the default was excusable under the provisions of this clause, the rights and obligations of the parties shall, if the CONTRACT contains a clause providing for termination for convenience of the OWNER, be the same as if the notice of termination had been issued pursuant to such clause. If, after notice of termination of this CONTRACT under the provisions of this clause, it is determined for any reason that the CONTRACTOR was not in default under the provisions of the clause, and if this CONTRACT does not contain a clause providing for termination for convenience of the OWNER, the CONTRACT shall be equitably adjusted to compensate for such termination and the contract modified accordingly.
- F. The rights and remedies of the OWNER provided in this clause shall not be Exclusive and are in addition to any other rights and remedies provided by law or under this CONTRACT.

23. Application for Payments:

The CONTRACTOR shall submit an application monthly for progress payments to the OWNER for approval. The CONTRACT REPRESENTATIVE shall approve the payment, and obtain the signature of the inspector for payment. Receipts or other vouchers showing payments for the materials and labor, including payments to Subcontractors, for the preceding month shall be submitted with the application if required.

If payments are made on valuation of WORK done, such application shall be submitted at least ten days before each payment falls due. The CONTRACTOR shall, before the first application, submit to the OWNER, a

schedule of values for the various parts of the WORK, including quantities, aggregating the total sum of the CONTRACT, divided so as to facilitate payments as outlined above and made out in such form as the OWNER and the CONTRACTOR may agree upon, and supported by such evidence as to its correctness as the OWNER may direct. This schedule, when approved by the OWNER, shall be used as a basis for payment, unless it be found to be in error. In applying for payments, the CONTRACTOR shall submit in duplicate a statement based upon this schedule and itemized in such form and supported by such evidence as the OWNER may direct, showing CONTRACTOR's right to the payment claimed.

In making payments to the CONTRACTOR for completed WORK or for materials stored on site, it is understood between the OWNER and the CONTRACTOR that proportionate parts of such payments as are made to the CONTRACTOR for completed WORK of Subcontractors and/or suppliers will be transmitted to such Subcontractors and/or suppliers in the form of payments for completed WORK within ten (10) days after receipt of such payments by the CONTRACTOR. The submittal of an application by a CONTRACTOR for a progress payment shall constitute prima facie representation by that CONTRACTOR that all previous proportionate payments made by the OWNER to the CONTRACTOR for completed WORK of Subcontractors and/or suppliers have been transmitted to all appropriate Subcontractors and/or suppliers for their completed WORK within ten (10) days after receipt of respective payments.

For projects in excess of \$100,000, the CONTRACTOR may request retainage to be paid to an escrow agent for interest to accrue to the CONTRACTOR's benefit. See OWNER for forms and more information.

24. OWNER's Right to Withhold Certain Amounts and Make Application Thereof:

The OWNER may withhold from payment to the CONTRACTOR such an amount or amounts as, in its judgment, may be necessary to pay just claims against the CONTRACTOR or any Subcontractor for labor and services rendered and materials furnished in and about the WORK. The OWNER may apply such withheld amounts on the payment of such claims in its discretion. In so doing, the OWNER shall be deemed the agent of the CONTRACTOR and payments so made by the OWNER shall be considered as a payment made under the CONTRACT by the OWNER to the CONTRACTOR and the OWNER shall not be liable to the CONTRACTOR for any such payments in good faith made. Such payments may be made without prior determination of the claim or claims.

Neither the final certificate of payment nor any provision in the CONTRACT documents, nor partial or entire occupancy of the premises by the OWNER shall constitute an acceptance of WORK not done in accordance with the contract documents or relieve the CONTRACTOR of liability in respect to any express warranties or responsibility for faulty materials or workmanship. The CONTRACTOR shall remedy any defects in the WORK and pay for any damage to other WORK resulting therefrom, which shall appear within a

period of one year from the date of the certificate of substantial completion of the WORK, unless a longer period is specified. The OWNER will give notice of observed defects with reasonable promptness.

25. Liability Insurance:

To protect against liability, loss, or expense arising from damage to property or injury or death of any person or persons incurred in any way out of, in connection with or resulting from the WORK provided hereunder, CONTRACTOR shall obtain at its own expense from reliable insurance companies acceptable to OWNER's Risk Manager and authorized to do business in the state in which the work is to be performed, and shall maintain in full force during the entire period of this contract the following or equivalent insurance:

- (a) Workers' Compensation Insurance and Employers' Liability Insurance providing statutory benefits.
- (b) Comprehensive General Liability Insurance, including premises-operations; explosion; collapse and underground hazards; products and completed operation hazards; blanket contractual; broad form property damage; independent CONTRACTORS; and personal injury including employees with limits not less than \$1,000,000 combined single limit per occurrence.
- (c) Comprehensive Automobile Liability Insurance including owned, hired and non-owned automobiles with limits not less than \$1,000,000 combined single limit per occurrence.
- (d) CONTRACTOR using its own aircraft, or employing aircraft in connection with the WORK performed under this contract shall maintain Bodily Injury and Property Damage Liability coverage with a combined single limit of not less than \$1,000,000 per occurrence.

Any policy required by this section may be arranged under a single policy for the full limit required, or by a combination of underlying policies with the balance provided by an Excess or Umbrella Liability policy.

OWNER may accept equivalent self-insured programs in lieu of insurance upon specific approval of OWNER's Risk Manager.

Irrespective of the requirements as to insurance to be carried by CONTRACTOR as provided herein, insolvency, bankruptcy or failure of any insurance company to pay all claims accruing, shall not be held to relieve CONTRACTOR of any obligations hereunder.

The State of Utah and all Institutions, Agencies, Departments, Authorities and Instrumentalities of the State of Utah, and while acting within the scope of their duties as such: any member of their governing bodies, or of their boards, commissions, or advisory committees, or any of their elected or appointed officials, or any of their employees or authorized volunteers shall be listed as additional insureds under each of the policies required to be purchased and maintained by CONTRACTOR, with the exception of Workers'

Compensation. Each policy so required shall be primary to the aforesaid additional insureds listed above, and shall apply to the full policy limits prior to any other insurance coverage which the aforesaid additional insureds may have in the event of claim under any of said policies, but, only with respect to WORK being performed by CONTRACTOR on behalf of the aforesaid additional insureds.

Before the WORK is commenced, certificates evidencing that satisfactory coverage of the type and limits set forth above are in effect, shall be furnished to the OWNER. Such insurance policies shall contain provisions that no alteration, cancellation or material change therein shall become effective except upon thirty (30) days prior written notice to OWNER's Risk Manager as evidenced by return of registered or certified letter sent to OWNER's Risk Manager.

Any and all deductibles in the above described policies shall be assumed by, for the account of, and at sole risk of CONTRACTOR.

26. Property Insurance:

OWNER shall provide "all risk" property insurance to protect OWNER, as well as all CONTRACTORS, Subcontractors and sub-subcontractors with respect to WORK performed hereunder at OWNER's own cost and expense, according to the policy forms currently in force with insurance carriers selected by OWNER's Risk Manager. OWNER's Risk Manager will furnish, upon request, all parties in interest with copies of said policies authenticated by authorized agents of the insurers or the State Risk Management Fund.

The above described policies shall be subject to a total deductible of \$500.00 per loss occurrence, which shall be assumed by all insureds in proportion to their share of the total amount of an insured loss occurrence.

Any insured property loss is to be adjusted with the OWNER's Risk Manager, and made payable to the OWNER's Risk Manager as trustee for the insureds, as their interests may appear, subject to the requirements of any applicable loss payable clause.

CONTRACTOR and OWNER hereby waive all rights against each other for damages caused by perils insured against under the property insurance provided by OWNER, except such rights as CONTRACTOR may have to the proceeds of such insurance held by the OWNER's Risk Manager as trustee.

If the CONTRACTOR requests in writing that insurance for special hazards be included in the property insurance policy, the OWNER's Risk Manager shall, if possible, include such insurance, and the cost thereof shall be charged to the CONTRACTOR by appropriate change order.

27. Indemnification:

"Indemnities" shall be defined for the purposes of this section: the State of Utah and all institutions, agencies, departments, authorities, and instrumentalities of the State of Utah, and any member of their governing

General Conditions

bodies, or of their boards or commissions, or any of their elected or appointed officers, or any of their employees or authorized volunteers.

The CONTRACTOR will protect, indemnify and hold harmless indemnities from every kind and character of damages, losses, expenses, demands, claims and causes of action arising against indemnities and their Subcontractors, their officers, agents, employees or any other person, firm or corporation whatsoever from, against, or on account of any and all claims damages, losses, demands causes of action and expenses (including attorney's fees) arising out of or resulting from any violation or alleged violation by CONTRACTOR, his officers, agents and employees, or his Subcontractors or their officers, agents and employees of any federal, state or local law, statute or ordinance, relating to the WORK to be performed by the CONTRACTOR on the project growing out of or incident to the WORK to be performed and operations to be conducted by CONTRACTOR, or his Subcontractors, under this agreement, whether such claims, death or damages, result from or are claimed to have resulted from the negligence of CONTRACTOR, his officers, agents or employees, or his Subcontractors, their officers, agents, employees, or whether resulting from or alleged to have resulted from the concurrent negligence of indemnities and/or CONTRACTORS, their officers, agents or employees. The CONTRACTOR, at his own expense, shall defend any suit or action brought against OWNER based on any such alleged injury, death or damage, and shall pay all damages, costs and expenses, including attorney's fees in connection therewith or in any manner resulting therefrom. Such damages will include all the injuries or damages occasioned by the failure of, use of, or misuse of any and all kinds of equipment, whether owned or rented by CONTRACTOR or furnished by a Subcontractor.

The OWNER shall be fully informed by the CONTRACTOR of settlement negotiations regarding any matter referred to in the preceding paragraph and shall first approve any settlement to be made by CONTRACTOR. Any such settlement shall include a release of all claims relating to OWNER. The form copy of all releases obtained shall be furnished by OWNER. If CONTRACTOR is unable to make settlement of any such claims within fifteen (15) days after the final completion date, the OWNER reserves the right, at his/her option, to either make settlement of the claim and charge the amount to CONTRACTOR or to withhold the dollar amount, in whole or in part, of the claim or claims in question from payment to CONTRACTOR until OWNER receives a release for such claim or claims.

In any and all claims against indemnities by any employee or CONTRACTOR, any Subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, the indemnification obligation under this article shall not be limited in any way by any limitation on the amount or type of damages, compensation or benefits payable by or for CONTRACTOR or any Subcontractor under workers' compensation acts, disability benefit acts or other employee benefit acts.

The CONTRACTOR shall indemnify and hold harmless

indemnities from all claims, demands, causes of action or suits of whatever nature arising out of services, equipment, supplies, materials and/or labor furnished by CONTRACTOR or its Subcontractors under this agreement; from all labor and/or mechanic or materialmen liens upon the real property upon which the work is located arising in favor of laborers and/or materialmen, Subcontractors and suppliers, out of services, equipment, supplies, materials and/or labor furnished by CONTRACTOR or any of his/her Subcontractors from all liens, claims and encumbrances arising from the performance of CONTRACTOR or his/her Subcontractors.

28. Guarantee Bonds:

The CONTRACTOR shall include in his/her bid, as part of the quoted total, all costs involved in securing and furnishing the following bonds based on the completed cost of the CONTRACT:

- (a) A full 100% performance bond covering the faithful execution of the CONTRACT; and
- (b) A full 100% payment bond of all obligations arising thereunder.

29. Liens:

Neither the final payment nor any part of the retained percentage shall become due until the CONTRACTOR, if required, shall deliver to the OWNER a complete release of all liens arising out of this CONTRACT, or receipts in full in lieu thereof, and, if required in either case, an affidavit that so far as CONTRACTOR has knowledge or information the releases and receipts include all the labor and materials for which a lien could be filed, but the CONTRACTOR may, if any Subcontractor refuses to furnish a release or receipt in full, furnish a bond satisfactory to the OWNER to indemnify him/her against any lien. If any lien remain unsatisfied after all payments are made, the CONTRACTOR shall refund to the OWNER all moneys that the latter may be compelled to pay in discharging such a lien, including all costs and a reasonable attorney's fee.

30. Assignment:

The CONTRACTOR shall not assign the CONTRACT or sublet it as a whole without the written consent of the OWNER, nor shall the CONTRACTOR assign any moneys due or to become due to CONTRACTOR hereunder, without the previous written consent of the OWNER.

31. Mutual Responsibility of Contractors:

Should the CONTRACTOR cause damage to any separate CONTRACTOR on the WORK, the CONTRACTOR agrees, upon due notice, to settle with such CONTRACTOR by agreement or arbitration, if he/she will so settle. If such separate CONTRACTOR sues the OWNER on account of any damage alleged to have been so sustained, the OWNER shall notify the CONTRACTOR, who shall defend such proceedings at his/her own expense, and if any judgment against the OWNER arises therefrom, the CONTRACTOR shall pay

or satisfy it in its entirety.

32. Separate Contracts:

The OWNER reserves the right to let other CONTRACTS in connection with this WORK. The CONTRACTOR shall afford other CONTRACTORS reasonable opportunity for the introduction and storage of their materials and the execution of their work and shall properly connect and coordinate his/her WORK with theirs.

If any part of the CONTRACTOR's WORK depends for proper execution or results upon the WORK of any other CONTRACTOR, the CONTRACTOR shall inspect and promptly report to the OWNER any defects in such WORK that render it unsuitable for such proper execution and results. His/her failure so to inspect and report shall constitute an acceptance of the other CONTRACTOR's work as fit and proper for the reception of his/her work, except as to defects which may develop in the other CONTRACTOR's WORK after the execution of his/her WORK. To insure the proper execution of his/her subsequent WORK, the CONTRACTOR shall measure WORK already in place and shall at once report to the OWNER any discrepancy between the executed WORK and the drawings.

33. Subcontractors:

The two apparent low bidders shall furnish to the OWNER, within twenty-four (24) hours after the opening of bids, a list of the Subcontractors by name and amounts where Subcontractors' bids are in excess of \$5,000 and shall not employ any that the OWNER may, within a reasonable time, object to as incompetent or unfit. Bidders shall not list themselves or "self" under any category as Subcontractor unless the bidder intends to perform as the Subcontractor for which he/she lists "self," and unless he/she generally and regularly performs that type of subcontract WORK. The OWNER shall, on request, furnish to any Subcontractor, wherever practicable, evidence of the amounts certified on this account.

The CONTRACTOR agrees that CONTRACTOR is as fully responsible to the OWNER for the acts and omissions of his Subcontractors and of persons either directly or indirectly employed by them, as he/she is for the acts and omissions of persons directly employed by CONTRACTOR.

Nothing contained in the CONTRACT documents shall create any contractual relation between any Subcontractor or supplier and the OWNER.

34. Relations of CONTRACTOR and Subcontractor:

The CONTRACTOR agrees to bind every Subcontractor and every Subcontractor agrees to be bound by the terms of the agreement, the general conditions, and the drawings and specifications as far as applicable to his/her WORK. Nothing in this article shall create any obligation on the part of the OWNER to pay or to see to the payment of any sums to any Subcontractor.

35. State's Inspection:

The OWNER, at his/her option, may assign an inspector to the project. Such staff inspector will cooperate with the CONTRACT REPRESENTATIVE and design engineer in noting deviations from, or necessary adjustments to, the CONTRACT documents or of deficiencies or defects in the construction. The staff inspector's presence on the project, however, shall in no way relieve the CONTRACT REPRESENTATIVE of the prime responsibilities as set forth herein.

36. CONTRACT REPRESENTATIVE Status:

The OWNER shall appoint a CONTRACT REPRESENTATIVE who shall have general supervision of the work and he/she is the agent of the OWNER to the extent provided in the CONTRACT documents and when in special instances he/she is authorized by the OWNER to so act.

As the CONTRACT REPRESENTATIVE is, in the first instance, an interpreter of the conditions of the CONTRACT and a judge of its performance, he/she shall side neither with the OWNER nor with the CONTRACTOR, but shall use his/her powers under the CONTRACT to enforce its faithful performance by both.

37. CONTRACT REPRESENTATIVE's Decisions:

The CONTRACT REPRESENTATIVE shall, within a reasonable time, make decisions on all claims of the OWNER or CONTRACTOR and on all other matters relating to the execution and progress of the WORK or the interpretation of the CONTRACT documents.

38. Cash Allowances:

The CONTRACTOR shall include in the BID PRICE all allowances named in the CONTRACT documents and shall cause the WORK so covered to be done by such CONTRACTORS and for such sums as the CONTRACT REPRESENTATIVE may specify and certify, the BID PRICE being adjusted in conformity therewith, upon approval of the OWNER.

39. Use of Premises:

The CONTRACTOR shall confine apparatus, the storage of materials and the operations of his/her workers to limits indicated by law, ordinances, permit or directions of the CONTRACT REPRESENTATIVE and shall not unreasonably encumber the premises with his/her materials. The CONTRACTOR shall not load or permit any part of the equipment or structure to be loaded with a weight that will endanger its safety or the safety of any person on the premises.

40. Cutting, Patching and Digging:

The CONTRACTOR shall do all cutting, patching or fitting of his/her WORK that may be required to make its several parts come together properly and fit it to receive or be received by WORK of other CONTRACTORS shown upon, or reasonably implied by, the drawings and specifications for the completed structure, and he shall make good after them as the CONTRACT REPRESENTATIVE may direct.

General Conditions

Any cost caused by defective or ill-timed work shall be borne by the party responsible therefor. The CONTRACTOR shall not endanger any WORK by cutting, digging or otherwise, and shall not cut or alter the WORK of any other CONTRACTOR save with the consent of the CONTRACT REPRESENTATIVE.

41. Cleaning Up:

The CONTRACTOR shall at all times keep the premises free from accumulations of waste material or rubbish caused by his/her employees or WORK. At the completion of the WORK, CONTRACTOR shall remove all rubbish from and about the building and all tools, scaffolding and surplus materials and shall leave his/her WORK "broom-clean" or its equivalent, unless more exactly specified. In case of dispute, the OWNER may remove the rubbish and charge the cost to the several CONTRACTORS as the CONTRACT REPRESENTATIVE may determine to be just.

42. Substitutions:

Where reference is made to one or more propriety products but restrictive descriptive material of one or more manufacturer(s) is used, it is understood that the products of other manufacturers will be accepted, provided they equal or exceed the standards set forth in the plans and specifications and are compatible with the intent and purpose of the design, subject to the written approval of the OWNER and the CONTRACT REPRESENTATIVE prior to the opening of bids. Requests for and information pertaining to said approval must be submitted to the OWNER no later than four (4) working days (not including Saturday, Sunday or state holidays) prior to bid opening. If the descriptive material is not restrictive, the products of other manufacturers specified will be accepted without prior approval provided they are compatible with the intent and purpose of the design.

The CONTRACTOR may propose the substitution of any material as a supplement to his/her bid with the monetary amount, additive or deductive as may be the case, clearly stated and shall include the manufacturer's complete descriptive information with the proposed substitution. This shall be completely apart and separate from the BID PRICE quotation and shall be solely for the information of the OWNER and the use of such proposed substitutions shall be strictly at the decision of the OWNER. If substitution is accepted by the OWNER, the CONTRACT sum shall be adjusted from the BID PRICE either up or down as indicated on the supplementary list by change order after award.

43. Laying Out WORK:

The CONTRACTOR shall be held strictly responsible for the accuracy of the laying out of his/her WORK and for its strict conformity with the existing conditions of the building and shall determine all changes and chases and openings before WORK is commenced.

44. Emergencies:

In an emergency affecting the safety of life, or of the structure or of adjoining property, then the

CONTRACTOR, without special instruction or authorization from the OWNER, shall act at his/her discretion to prevent such threatened loss or injury. Any compensation claimed to be due him/her therefrom shall be determined as provided for under Article 17, "Changes."

45. Testing of Materials:

In case the CONTRACT REPRESENTATIVE direct that any materials be tested or analyzed, then the CONTRACTOR shall furnish a sample for the test, such sample being selected according to the directions of the CONTRACT REPRESENTATIVE. The cost of testing or analysis of such sample or samples shall be borne by the manufacturer or supplier of the product. This provision shall not apply to the testing of concrete. The cost of testing shall be borne by the OWNER.

46. Temporary Enclosing, Drying Out, Etc.:

If applicable when openings are made in exterior walls, the CONTRACTOR shall, if required by the OWNER on account of weather or security conditions, close up all exterior openings (except one or more which are to be provided with battened doors, padlocks, etc.) with temporary frames covered with approved material.

The CONTRACTOR must, at all times, protect the building from damage from weather, surface water or subsoil drainage. He/she must keep the excavations dry, if necessary, by pumping, while concrete or masonry is being laid.

47. Examination of Site:

The CONTRACTOR shall visit the site and examine for himself/herself the site conditions. He/she shall furnish all labor and materials necessary for preparation of the site for the execution of this CONTRACT.

48. Storage and Care of Materials:

The CONTRACTOR shall provide, maintain and remove when directed, suitable, substantial, watertight storage sheds upon the premises where directed, in which he/her shall store his/her materials. All cement, lime and other materials affected by moisture shall be covered and protected to keep from damage while it is being transported to the site.

49. Construction Risks:

The construction and all materials and WORK connected therewith shall be at the CONTRACTOR's risk until they are accepted, and he/she will be held responsible for and liable for their safety in the amount paid to him/her by the OWNER on account thereof.

50. Temporary Appurtenances and Conveniences:

The CONTRACTOR shall provide well-fastened ladders and other means to facilitate inspection of the work.

51. Scaffolding, Tools, Etc.:

The CONTRACTOR shall provide and erect all the necessary platforms, scaffolds and supports of ample

strength required for the handling of the materials and other loading to be imposed. The same shall apply to all derricks and hoisting machinery, all appliances and materials, ladders, horses, poles, plants, ropes, wedges, centers, moulds, and other tools and materials, and the cartage thereof to and from the site as may become necessary for the performance of his/her contract.

52. Sanitary Provisions:

The CONTRACTOR shall provide a chemical toilet for his workers' use. The CONTRACTOR shall keep the toilet clean, neat and in first-class condition at all times.

53. Refuse:

Refuse barrels are to be provided by the CONTRACTOR for the workers' lunch boxes and papers.

54. Removing Water:

The CONTRACTOR shall remove, at his/her expense from all excavations and/or from the site, all unwanted water appearing from any cause during any stage of the WORK until the site is accepted by the OWNER. All excavations shall be free from water before any concreting or other WORK is done in them.

55. Taxes:

The CONTRACTOR shall include in his/her BID PRICE the cost of social security, unemployment compensation, and sales and use taxes as required by federal and state laws.

56. Citizens Preferred:

Preference shall be given in hiring citizens of the United States or those having declared their intention of becoming citizens; failure to comply may result in the OWNER declaring the contract void.

57. Code Requirements:

The provisions of the 1979 Uniform Building Code, and the 1980 Supplement to Uniform Building Code and Uniform Building Code Standards, the 1981 National Electrical Code, except as specific variances therewith may be authorized by the OWNER, and the 1979 Utah Plumbing Code as amended, shall apply.

If the drawings and specifications fail to meet the minimum standards of the above-mentioned codes, it shall be the responsibility of the CONTRACTOR to bring such information to the attention of the OWNER having jurisdiction. Subcontractors shall also inform the CONTRACTOR of any infractions of the above-mentioned codes regarding their own particular trades.

In the event that workmanship or incidental materials are not specified or indicated, they shall at least conform to the above-mentioned codes and shall be incorporated into the work without any additional cost to the OWNER.

If the plans and specifications call for items or workmanship which exceed the codes, the plans and specifications hold precedence over any code requirements.

58. Nondiscrimination - Equal Employment Opportunity:

In order to comply with the provisions of the Utah Anti-Discrimination Act of 1965, relating to unfair employment practices, the CONTRACTOR agrees as follows:

- A. The CONTRACTOR will not discriminate against any employee or applicant for employment because of race, color, sex, religion ancestry or natural origin.
- B. In all solicitations or advertisements for employees, the CONTRACTOR will state that all qualified applicants will receive consideration without regard to race, color, sex, religion, ancestry or national origin.
- C. The CONTRACTOR will send to each labor union or workers' representative notices to be provided, stating the CONTRACTOR's responsibilities under the statute.
- D. The CONTRACTOR will furnish such information and reports as requested by the division for the purpose of determining compliance with the statute.
- E. Failure of the CONTRACTOR to comply with the statute, the rules and regulations promulgated thereunder and this nondiscrimination clause shall be deemed a breach of contract and it may be canceled, terminated or suspended in whole or in part.
- F. The CONTRACTOR shall include the provisions of the above Paragraphs A through E in all subcontracts for this project.

59. Affirmative Action:

The CONTRACTOR will take affirmative action to ensure that applicants are employed and that employees are treated during employment without regard to their race, color, religion, sex or national origin. Such action shall include, but not be limited to the following: employment; upgrading; demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship.

At its discretion, the OWNER may perform a compliance review at the office and project of the CONTRACTOR to check on compliance in hiring practices, record-keeping, contracting of agencies and unions, advertising, informing of personnel of the requirements under this provision, etc. If the visit to the project site or other information received indicates need to perform a compliance review more frequently on a project, this will be done. The size of the project, complaint situation, and past record of CONTRACTOR will determine the frequency of on-the-job compliance reviews.

General Conditions

60. Safety:

The CONTRACTOR shall institute a safety program at the start of construction to minimize accidents; such program to continue to the end of the job and conform to the latest general safety orders of the State Industrial Commission. The CONTRACTOR shall post signs, erect barriers, etc., as necessary to implement this program. The CONTRACTOR shall have all workers and all visitors on site wear safety hard hats and obey all safety rules and regulations and statutes as soon as the CONTRACTOR proceeds. The CONTRACTOR shall post a sign regarding hats in a conspicuous location and furnish extra hats at his/her expense for visitors.

61. Rubbish Disposal:

Rubbish, trash, etc., shall not be burned on premises unless approved by the local fire authority, but rather, hauled from the site and legally disposed of or other methods as specified by OWNER.

62. Subcontractors Financial Bid Limits and License Classification:

The CONTRACTOR shall verify the license classification and bid limit of each of his/her Subcontractors. Regulations prohibit work of the above Subcontractors exceeding their respective bid limit and working outside of license classification as determined by the Department of Business Regulation, Department of Contractors.

In the event the bid limit or classification is not complied with, the respective Subcontractor(s) mentioned above will be disqualified by the OWNER, and the CONTRACTOR shall be responsible to provide a suitable and properly qualified Subcontractor as approved by the OWNER without a change in the contract price.

63. Balancing and Testing:

It is the intent of this specification that the site, when presented to the OWNER for final acceptance, be complete and operable in all respects, including, but not limited to, mechanical, utilities, and other systems which are tuned, tested, and balanced to the satisfaction of the OWNER, or his/her appropriate engineers and consultants. Any and all testing and balancing necessary shall be done as part of the CONTRACT with the state.

During, or in connection with the inspection of the WORK, the CONTRACTOR or his/her appropriate Subcontractor(s) shall perform such tests and/or demonstrations of the operation of the systems, or its components, as may be requested by the OWNER, or his/her appropriate engineers and consultants, as necessary to adequately determine the acceptability of the installation.

64. Substantial Completion:

The OWNER will conduct inspections to determine the dates of substantial completion and final payment, will

receive written guarantees and related documents required by the CONTRACT and assembled by the CONTRACTOR and submit these to the OWNER, and will issue a final certificate for payment.

The date of substantial completion of the WORK or designated portion thereof is the date certified by the OWNER when construction is sufficiently complete in accordance with the CONTRACT documents so the OWNER may occupy the site or designated portion thereof for the use for which it is intended. When the CONTRACTOR determines that the WORK, or a designated portion thereof acceptable to the OWNER, is substantially complete, the OWNER shall prepare a list of items to be completed or corrected. The failure to include any item on such list does not alter the responsibility of the CONTRACTOR to complete all WORK in accordance with the contract documents. When the OWNER, on the basis of an inspection, determines that this WORK is substantially complete, the CONTRACT REPRESENTATIVE then will prepare a Certificate of Substantial Completion which shall establish the date of substantial completion; shall state the responsibilities of the OWNER and the CONTRACTOR for maintenance, heat, utilities and insurance; and shall fix the time within which the CONTRACTOR shall complete the items listed therein, said time to be within the CONTRACT time unless extended pursuant to Article, "Delays and Extension of Time." The certificate of substantial completion shall be submitted to the OWNER and the CONTRACTOR for their written acceptance of the responsibilities assigned to them in such certificate. A sample form of the certificate of substantial completion is included in the specifications.

If within one year after the date of substantial completion or within such longer period of time as may be prescribed by law or by the terms of any applicable special guarantee required by the CONTRACT documents, any of the WORK is found to be defective or not in accordance with the CONTRACT documents, the CONTRACTOR shall correct it promptly after receipt of written notice from the OWNER to do so unless the OWNER has previously given the CONTRACTOR a written acceptance of such condition. The OWNER shall give such notice promptly after discovery of the condition.

65. Other Prohibited Interests:

No official of the OWNER who is authorized in such capacity and on behalf of the OWNER to negotiate, make, accept or approve, or to take part in negotiating, making, accepting, or approving any architectural engineering, inspection, construction or material supply contract or any subcontract in connection with the construction of the project, shall become directly interested personally in the contract or in any part hereof.

No officer, employee, attorney, engineer or inspector of or for the OWNER who is authorized in such capacity and on behalf of the OWNER to exercise any legislative, executive, supervisory or other similar functions in connection with the construction of the project shall become directly or indirectly interested personally in this contract or in any part thereof, any material supply

contract, subcontract, insurance contract, or any other contract pertaining to the project.

66. Conflicting Conditions:

Any provision in any of the CONTRACT documents which may be in conflict or inconsistent with any of the paragraphs in these general conditions shall be void to the extent of such conflict or inconsistency. In the event of conflicts of plans and specifications, the CONTRACTOR shall follow the most stringent requirements as approved by the OWNER.

67. Monthly Progress Meetings:

Monthly progress meetings may be held at the discretion of the OWNER or the general CONTRACTOR, at which time the Subcontractors and/or suppliers will be required to be present.

68. Suspension of WORK:

A. Suspension of WORK for the Convenience of the Owner. The OWNER may order the CONTRACTOR in writing to suspend, delay or interrupt all or any part of the WORK for such period of time as the OWNER may determine to be appropriate for the convenience of the OWNER.

B. Adjustment of Cost. If the performance of all or any part of the work is suspended, delayed or interrupted by an act or failure to act of the OWNER for an unreasonable period of time, an equitable adjustment in the CONTRACT price shall be made for any increase in the cost of performance of this CONTRACT necessarily caused by such unreasonable suspension, delay or interruption and an equitable adjustment of time for completion of the WORK will be allowed the CONTRACTOR and the CONTRACT shall be modified in writing accordingly. However, no adjustment shall be made under this clause for any suspension, delay or interruption to the extent:

(1) That performance would have been so suspended, delayed or interrupted by any other cause, including the fault or negligence of the CONTRACTOR; or

(2) For which an adjustment is provided or Excluded under any other provision of this CONTRACT.

C. Time Period for Claims. Any claim by the CONTRACTOR for adjustment under this clause must be asserted by the CONTRACTOR, in writing, within thirty (30) days from the date of termination of such suspension, delay or interruption; provided that the OWNER may, in his/her sole discretion, receive and act upon any such claim asserted at any time prior to final payment under this CONTRACT.

D. Adjustments of Price. Any adjustment in contract price made pursuant to this clause shall be determined in accordance with the price adjustment clause of this CONTRACT.

69. Differing Site Conditions:

A. Notice. The CONTRACTOR shall promptly, and before such conditions are disturbed, notify the OWNER, in writing, concerning any:

(1) Subsurface or latent physical conditions at the site differing materially from those indicated in this CONTRACT; or

(2) Unknown physical conditions at the site of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in WORK of the character provided for in this CONTRACT.

B. Adjustments of Price or Time for Performance. After receipt of such notice, the OWNER shall promptly investigate the site, and if it is found that such conditions do materially so differ and cause an increase in the CONTRACTOR's cost of, or the time required for, performance of any part of the WORK under this contract, whether or not changed as a result of such conditions, an equitable adjustment shall be made and the CONTRACT modified in writing accordingly. Any adjustment in CONTRACT price made pursuant to this clause shall be determined in accordance with the Price Adjustment Clause of this CONTRACT.

C. Time Period for Notice of Claims. Any claim by the CONTRACTOR for an adjustment under this clause must be asserted by the CONTRACTOR, in writing, within thirty (30) days from the date of the CONTRACTOR's notice to the OWNER concerning the differing site conditions; provided that the OWNER may, in his/her sole discretion, receive and act upon any such claim asserted at any time prior to issuance of notice of substantial completion.

D. No claim shall be allowed unless the CONTRACTOR has given the notice required in Subparagraph (A) of this clause; provided that the time prescribed therefor may be extended by the OWNER.

E. Knowledge. Nothing contained in this clause shall be grounds for an adjustment in compensation if the CONTRACTOR had actual knowledge of the existence of such conditions prior to the submission of bids.

70. Price Adjustment:

A. Price Adjustment Methods. Any adjustment in BID PRICE pursuant to any clause in this CONTRACT shall be made in one or more of the following ways:

(1) By agreement on a fixed-price adjustment before commencement of the pertinent performance;

(2) By unit prices specified in this CONTRACT;

(3) By the costs attributable to the applicable events or situations, plus appropriate profit or fee, in the following manner:

General Conditions

- (a) The CONTRACTOR shall furnish to the OWNER a detailed estimate of the actual cost of labor, materials, taxes and equipment required for the performance of such WORK. Equipment rental rates shall not exceed those of comparable rates charged by rental companies or as agreed to by the OWNER and CONTRACTOR prior to start of the project.
 - (b) For added or omitted work by a Subcontractor (not including unit price) the CONTRACTOR shall furnish to the OWNER a detailed estimate of the actual cost of the Subcontractors for labor, materials, taxes and equipment to be used for such WORK. Each such estimate shall be signed by the Subcontractor as his/her estimate of the costs thereto.
 - (c) The CONTRACTOR and Subcontractor agree that a fixed fee not exceeding 15% of the increased costs shall be full compensation to cover all costs of supervision, overhead, bond, and any other direct or indirect overhead expenses and profit.
 - (4) In such manner as the parties may mutually agree; or
 - (5) In the absence of agreement between the parties, by a unilateral determination by the OWNER of the costs attributable to the applicable event or situation, plus appropriate profit or fee, all as computed by the OWNER, subject to the CONTRACTOR's legal and contractual remedies.
- B. Submission of Cost or Pricing Data.** The CONTRACTOR shall submit certified cost or pricing data for any price adjustments, except where they are based upon established catalog prices or market prices, or upon adequate price competition or are set by law or regulation. Any price adjustments allowable hereunder shall Exclude sums found by the OWNER to have resulted from any cost or pricing data furnished by the CONTRACTOR which were inaccurate, incomplete or not current as of the date of their submission to the OWNER.
- 71. Termination for Convenience of the Owner:**
- A.** The performance of WORK under this contract may be terminated by the OWNER in accordance with this clause in whole, or from time to time, in part, whenever the OWNER shall determine that such termination is in the best interest of the OWNER or any person for whom the OWNER is acting under this CONTRACT. Any such termination shall be effected by delivery to the CONTRACTOR of a notice of termination specifying the extent to which performance of WORK under the contract is terminated, and the date upon which such termination becomes effective.
- No termination may be effected unless the CONTRACTOR is given (1) not less than ten calendar days written notice (delivered by certified mail, return receipt requested), and (2) an opportunity for consultation with the OWNER prior to termination.
- B.** After receipt of a notice of termination, and except as otherwise directed by the OWNER, the CONTRACTOR shall:
- (1) Stop WORK under the CONTRACT on the date and to the extent specified in the notice of termination;
 - (2) Place no further orders or subcontracts for materials, services or facilities, except as may be necessary for completion of such portion of the WORK under the CONTRACT as is not terminated;
 - (3) Terminate all orders and subcontracts to the extent that they relate to performance of WORK terminated by the notice of termination;
 - (4) Assign to the OWNER in the manner, at the times, and to the extent directed by the OWNER, all of the right, title, and interest of the CONTRACTOR under the orders and subcontracts so terminated, in which case the OWNER shall have the right, in his/her discretion, to settle or pay any or all claims arising out of the termination of such orders and subcontracts;
 - (5) Settle all outstanding liabilities and all claims arising out of such termination of orders and subcontracts, with the approval or ratification of the OWNER, which approval or ratification shall be final for all the purposes of this clause;
 - (6) Transfer title and deliver to the OWNER in the manner, at the times, and to the extent, if any, directed by the OWNER:
 - (a) The fabricated or unfabricated parts, WORK in process, completed WORK, supplies, and other material produced as a part of, or acquired in connection with the performance of the WORK terminated by the notice of termination; and
 - (b) The completed or partially completed plans, drawings, information, and other property which, if the CONTRACT had been completed, would have been required to be furnished to the OWNER;
 - (7) Use his/her best efforts to sell, in the manner, at the times, to the extent, and at the price or prices directed or authorized by the OWNER, any property of the types referred to in (6) above; provided, however, that the CONTRACTOR:
 - (a) Shall not be required to extend credit to any purchaser; and
 - (b) May acquire any such property under the conditions prescribed by and at a price or

- prices approved by the OWNER; and provided further that the proceeds of any such transfer of disposition shall be applied in reduction of any payments to be made by the OWNER to the CONTRACTOR under this CONTRACT or shall otherwise be credited to the price or cost of the work covered by this CONTRACT or paid in such other manner as the OWNER may direct;
- (8) Complete performance of such part of the WORK as shall not have been terminated by the notice of termination; and
- (9) Take such action as may be necessary, or as the OWNER may direct, for the protection and preservation of the property related to this contract which is in the possession of the CONTRACTOR in which the OWNER has or may acquire an interest.
- C. After receipt of a notice of termination, the CONTRACTOR shall submit to the OWNER his/her termination claim, in the form and with certification prescribed by the OWNER. Such claim shall be submitted promptly but in no event not later than sixty (60) days from the effective date of termination, unless one or more extensions in writing are granted by the OWNER, upon request of the CONTRACTOR made in writing within such period or authorized extension thereof. However, if the OWNER determines that the facts justify such action, he/she may receive and act upon any such termination claim at any time after such sixty (60) day period or any extension thereof. Upon failure of the CONTRACTOR to submit his/her termination claim within the time allowed, the OWNER may determine, on the basis of information available to him/her, the amount, if any, due to the CONTRACTOR by reason of the termination and shall thereupon pay to the CONTRACTOR the amount so determined.
- D. Subject to the provisions of Paragraph (C), the CONTRACTOR and the OWNER may agree upon the whole or any part of the amount or amounts to be paid to the CONTRACTOR by reason of the total or partial termination of WORK pursuant to this clause, which amount or amounts may include a reasonable allowance for profit on WORK done; provided that such agreed amount or amounts, Exclusive of settlement costs, shall not exceed the total contract price as reduced by the amount of payments otherwise made and as further reduced by the CONTRACT price of work not terminated. The CONTRACT shall be amended accordingly, and the CONTRACTOR shall be paid the agreed amount. Nothing in Paragraph (E) of this clause, prescribing the amount to be paid to the CONTRACTOR in the event of failure of the CONTRACTOR and the OWNER to agree upon the whole amount to be paid to the CONTRACTOR by reason of the termination of work pursuant to this clause, shall be deemed to limit, restrict, or otherwise determine or affect the amount or amounts which may be agreed upon to be paid to the CONTRACTOR pursuant to this Paragraph (D).
- E. In the event of the failure of the CONTRACTOR and the OWNER to agree, as provided in Paragraph (D), upon the whole amount to be paid to the CONTRACTOR by reason of the termination of WORK pursuant to this clause, the OWNER shall pay to the CONTRACTOR the amounts determined by the OWNER as follows, but without duplication of any amounts agreed upon in accordance with Paragraph (D):
- (1) With respect to all CONTRACT WORK performed prior to effective date of the notice of termination, the total (without duplication of any items) of:
- (a) The cost of such WORK;
- (b) The cost of settling and paying claims arising out of the termination of WORK under subcontracts or orders as provided in Paragraph (B)(5) above, Exclusive of the amounts paid or payable on account of supplies or materials delivered or services furnished by the Subcontractor prior to the effective date of the notice of termination under this CONTRACT, which amounts shall be included in the cost on account of which payment is made under (a) above; and
- (c) A sum, as profit on (a) above, determined by the OWNER to be fair and reasonable; provided, however, that if it appears that the CONTRACTOR would have sustained a loss on the entire CONTRACT had it been completed, no profit shall be included or allowed under this subdivision (c) and an appropriate adjustment shall be made reducing the amount of the settlement to reflect the indicated rate of loss; and
- (2) The reasonable cost of the preservation and protection of property incurred pursuant to Paragraph (B)(9); and any other reasonable cost incidental to termination of WORK under this CONTRACT, including expense incidental to the determination of the amount due to the CONTRACTOR as the result of the termination of WORK under this CONTRACT.
- The total sum to be paid to the CONTRACTOR under (E)(1) above shall not exceed the total CONTRACT price as reduced by the amount of payments otherwise made and as further reduced by the CONTRACT price of WORK not terminated. Except for normal spoilage, and except to the extent that the OWNER shall have otherwise expressly assumed the risk of loss, there shall be Excluded from the amounts payable to the CONTRACTOR under (E)(1) above, the fair value, as determined by the OWNER of property which is destroyed, lost, stolen, or damaged so as to become undeliverable to the OWNER, or to a buyer pursuant to Paragraph (B)(7).

General Conditions

- F. In arriving at the amount due the CONTRACTOR under this clause, there shall be deducted:
- (1) All unliquidated advance or other payments on account theretofore made to the CONTRACTOR, applicable to the terminated portion of this CONTRACT;
 - (2) Any claim which the OWNER may have against the CONTRACTOR in connection with this CONTRACT; and
 - (3) The agreed price for, or the proceeds of sale of, any materials, supplies, or other things acquired by the CONTRACTOR or sold, pursuant to the provisions of this clause, and not otherwise recovered by or credited to the OWNER.
- G. If the termination hereunder be partial, the CONTRACTOR may file with the OWNER a claim for an equitable adjustment of the price or prices specified in the CONTRACT relating to the continued portion of the CONTRACT (the portion not terminated by the notice of termination), and such equitable adjustment as may be agreed upon shall be made in such price or prices. Any claim by the CONTRACTOR for an equitable adjustment under this clause must be asserted within sixty (60) days from the effective date of the notice of termination, unless an extension is granted in writing by the OWNER.
- H. The OWNER may, from time to time, under such terms and conditions as he may prescribe, make partial payments and payments on account against costs incurred by the CONTRACTOR in connection with the terminated portion of this CONTRACT whenever, in the opinion of the OWNER the aggregate of such payments shall be within the amount to which the CONTRACTOR will be entitled hereunder. If the total of such payments is in excess of the amount finally agreed or determined to be due under this clause, such excess shall be payable by the CONTRACTOR to the OWNER upon demand, together with interest at a rate equal to the average rate at the time being received from the investment of state funds, as determined by the State Treasurer, for the period from the date such excess is repaid to the OWNER; provided, however, that no interest shall be charged with respect to any such excess payment attributable to a reduction in the CONTRACTOR's claim by reason of retention or other disposition of termination inventory until ten (10) days after the date of such retention or disposition, or such later date as determined by the OWNER by reason of the circumstances.
- I. Unless otherwise provided for in this contract, or by applicable statute, the CONTRACTOR shall - from the effective date of termination until the expiration of three years after final settlement under this CONTRACT - preserve and make available to the OWNER at all reasonable times at the office of the CONTRACTOR, but without direct charge to the OWNER, all books, records, documents and other evidence bearing on the costs and expenses of the CONTRACTOR under this CONTRACT and relating to the work terminated hereunder, or, to the extent

approved by the contracting officer, photographs, micrographs, or other authentic reproductions thereof.

72. Liquidated Damages:

The CONTRACTOR is referred to Attachment C, Article 12 of the contract for conditions of liquidated damages.

73. Termination for Breach, Etc.:

If the CONTRACTOR shall be adjudged bankrupt, or if CONTRACTOR should make a general assignment for the benefit of his/her creditors, or if a receiver should be appointed on account of CONTRACTOR's insolvency, or if CONTRACTOR or any of his/her Subcontractors should violate any of the provisions of this CONTRACT, the OWNER may serve written notice upon CONTRACTOR of its intention to terminate said CONTRACT; and unless within ten (10) days after the serving of such notice, such violation shall cease, the OWNER then may take over the WORK and prosecute same to completion by CONTRACT or by any other method it may deem advisable for the amount and at the expense of the CONTRACTOR. The CONTRACTOR shall be liable to the OWNER for any excess cost occasioned the OWNER thereby and in such event, the OWNER may, without liability for so doing, take possession of and utilize in completing the WORK, such materials, appliances, paint, and any other property belonging to the CONTRACTOR as may be on the site of the work and necessary therefor.

74. Normal Daylight Hours:

Contractor shall perform WORK on the premises during normal daylight hours and shall not perform WORK on the site when artificial light would be required to safely perform the WORK.

75. Normal Working Days:

CONTRACTOR shall perform the WORK during normal working days and shall not work during Sundays, or recognized national and state holidays. CONTRACTOR may take the option of working on Saturdays if the WORK is scheduled regularly to be performed on Saturdays and is approved by OWNER.

76. Use of Explosives

The storage, possession or use of explosives on the site shall be strictly prohibited unless expressly authorized by the OWNER and approved by the State.

77. Compliance with Copeland Regulations

The CONTRACTOR shall comply with the Copeland Regulations of the Secretary of Labor (29 CFR Part 3) which are incorporated herein by reference.

78. Overtime Compensation

- A. The CONTRACTOR or Subcontractor shall not require or permit any laborer or mechanic in any workweek in which he or she is employed under this CONTRACT to work in excess of forty hours in such workweek unless such laborer or mechanic receives

compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek, whichever is the greater number of overtime hours.

- B. In the event of any violation of the provisions of paragraph (a), the CONTRACTOR or Subcontractor shall be liable to any affected employee for any amounts due, and to the State of Utah for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the provisions of paragraph (a) in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard forty hour workweek without payment of the overtime wages required by paragraph (a).

79. Clean Air and Water

The CONTRACTOR shall use best efforts to comply with all requirements and applicable regulations, standards, and implementation plans under the Clean Air Act (42 USC 7401 et seq.) and the Clean Water Act (33 USC 1251 et seq.). No part of the WORK shall be performed in a facility listed on the U.S. Environmental Protection Agency List of Violating Facilities during the term of the CONTRACT. CONTRACTOR further agrees to insert the substance of this clause in any Subcontract.

Clean air and water standards include any enforceable rules, regulations, guidelines, orders, or other requirements issued under the Clean Air Act, Clean Water Act, or Executive Order 11738; applicable approved implementation plans described in Sections 110(d), 111(c&d), or 112(d) of the Clean Air Act; and requirements contained in permits issued by the U.S. Environmental Protection Agency or state or local governments authorized by Sections 402 or 307 of the Clean Water Act. "Facility," as used here, means any building, plant, structure, mine, location, or site of operations owned, leased, or supervised by the CONTRACTOR or Subcontractor in the performance of the CONTRACT.

[Last Revised November 5, 2002.]

Supplemental General Conditions

1. Statement Clarification of Terms:

The Division of Oil, Gas & Mining will assume responsibility for design and engineering on this project and will provide inspection. See Articles 36, 37, and 38.

2. Plan Checks:

Checks shall be made out to the Utah Division of Oil, Gas & Mining.

3. Equal Opportunity:

The CONTRACTOR agrees to abide by the provisions of Titles VI and VII of the Civil Rights Act of 1964 (42 USC 2000e) which prohibits discrimination against any employee or applicant for employment or any applicant or recipient of services on the basis of race, religion, color, or national origin. CONTRACTOR further agrees to abide by the following directives: Executive Order No. 11246, as amended, which prohibits discrimination on the basis of sex; federal regulation 45 CFR 90, which prohibits discrimination on the basis of age; Section 504 of the Rehabilitation Act of 1973 (29 USC 701 et seq), which prohibits discrimination on the basis of handicap; and Utah's Executive Order, dated June 30, 1989, which prohibits sexual harassment in the workplace.

4. Access to Records:

The CONTRACTOR agrees to provide the OWNER, the U.S. Office of Surface Mining, The Comptroller General of the United States, or any of their duly authorized representatives access to any books, documents, papers, and records which are directly pertinent to this CONTRACT for the purpose of making audit, examination, excerpts, and transcriptions. Such access will be made during normal business hours, or by appointment.

5. Retention of Records:

The CONTRACTOR agrees to retain and preserve any books, documents, papers, and records which are directly pertinent to this CONTRACT for a period of four years from the date of final payment for the WORK or from the date of Final Acceptance, whichever is later.

6. Variation in Estimated Quantities:

Variations Requiring Adjustments. Where the quantity of any item within the scope of this CONTRACT is an estimated quantity and where the actual quantity of such item varies by more than 15% above or below the estimated quantity stated in this CONTRACT, an adjustment in the CONTRACT price shall be made upon demand of either party. The adjustment shall be based upon any increase or decrease in costs due solely to variation above 115% or below 85% of the estimated quantity. If the quantity variation is such as to cause an increase in the time necessary for completion, the OWNER, upon receipt of a written request for an extension of time, prior to the date of final settlement of the CONTRACT, shall ascertain the facts and make adjustment for extending the completion date as in the judgment of the OWNER such facts justify.

7. Authority:

Provisions of this contract are pursuant to the authority set forth in Sections 63-56 UCA 1953 as amended, the Utah State Procurement Rules (*Utah Administrative Code*, Section R33), and related statutes which permit the OWNER to purchase certain specified services and other approved purchases for the State.

8. Conflict of Interest:

CONTRACTOR represents that none of its officers or employees are officers or employees of the State of Utah, unless disclosure has been made in accordance with Section 67-16-8, UCA 1953, as amended.

9. Separability Clause:

The declaration by any court or any other binding legal source that any provision of this contract is illegal and void shall not affect the legality and enforceability of any other provision of this contract unless the provisions are mutually dependent.

10. Debarment:

The CONTRACTOR certifies that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily Excluded from participation in this contract by any governmental department or agency.

[Last Revised April 2, 1993.]

OPHIR CANYON PROJECT

TECHNICAL SPECIFICATIONS

SECTION 0200	GENERAL SITE INFORMATION
SECTION 0220	MOBILIZATION/DEMOBILIZATION
SECTION 0230	ACCESS IMPROVEMENT
SECTION 0240	DEMOLITION AND CLEAN-UP
SECTION 0250	MINE CLOSURES
SECTION 0251	CAST-IN-PLACE CONCRETE
SECTION 0252	CONCRETE REINFORCEMENT
SECTION 0253	BAT GATE & SHAFT GRATE INSTALLATION
SECTION 0254	POLYURETHANE FOAM SHAFT CLOSURES
SECTION 0290	REVEGETATION
SECTION 0300	SPECIFIC SITE REQUIREMENTS

0200 General Site Information

PART 1 - GENERAL

1.01 WORK INCLUDED

The WORK consists of reclamation of abandoned mine features as described in Section 0300. The General Technical Specifications, Sections 0200 through 0290, outline WORK broadly applicable to all abandoned mine reclamation situations and that may not be required at each mine site in this project. Section 0300 provides the site-specific detail. Where there is a conflict between Section 0300 and the General Technical Specifications (0200's), Section 0300 shall govern.

1.02 SUBMITTALS

- A. Submittals requested in the Technical Specifications to be submitted with the Bid Proposal shall be included in and submitted with the sealed bid proposal delivered to the Division of Purchasing.
- B. Submittals requested in the Technical Specifications to be submitted after award of the CONTRACT or during construction shall be delivered to the designated representative for the Division of Oil, Gas and Mining (DOGM), referred to in these Specifications as the OWNER.

CONTRACTOR shall submit within five (5) days after award of the CONTRACT a calendar of WORK for performing the WORK, including routine workdays and hours, anticipated holidays, and days that the project will remain idle. Schedule shall also indicate WORK schedules for subcontractors and their estimated start and completion days. Allowance in the schedule shall be made for routine delays due to weather or other site conditions as they occur. The OWNER shall approve said schedule. Any significant deviation from that schedule shall be submitted in writing to the OWNER in the form of an updated schedule as the WORK progresses.

1.03 RELATED WORK

- A. Section 0220: Mobilization/Demobilization
- B. Section 0230: Access Improvement
- C. Section 0240: Demolition and Clean-up
- D. Section 0250: Mine Closures
- E. Section 0251: Cast-in-Place Concrete
- F. Section 0252: Concrete Reinforcement
- G. Section 0253: Bat Gate & Shaft Grate Installation
- H. Section 0254: Polyurethane Foam Shaft Closures
- I. Section 0290: Revegetation
- J. Section 0300: Specific Site Requirements

1.04 CONDITIONS AND RESTRICTIONS

- A. The project area and vicinity may contain several abandoned mine and/or town sites, but WORK will be limited to items specifically identified in Section 0300: Specific Site Requirements.
- B. *The pre-bid meeting is optional.* However, due to the nature of the WORK at these sites, the CONTRACTOR is strongly encouraged to participate in the entire prebid site tour and meeting in order to submit a responsible bid. The CONTRACTOR shall acknowledge in the bid that the site conditions have been examined and that the measurements and evaluations necessary to plan

Section 0200

and bid the WORK have been made.

- C. Due to the hazards associated with abandoned mines, all WORK on mine portals shall be conducted under the supervision of a qualified person with current certification to do such WORK under the General Safety Orders of Utah Coal Mines (i.e. Mine Foreman and/or Fire Boss). The specified qualification for the Certified Person is someone currently certified under the General Safety Orders of Utah Coal Mines as a Mine Foreman and/or Fire Boss. In special cases, the Abandoned Mine Reclamation Program may approve a Certified Person who does not possess current Mine Foreman or Fire Boss certifications. Among other things, the qualified person must have documented underground mine employment experience with job duties including responsibility for the safety of others. Candidates for the position of the Certified Person will be considered and approved on a case-by-case basis. This person is referred to as the "Certified Person" in these specifications hereafter.
- D. No smoking or open flames shall be permitted within fifty feet of any mine opening. Welding in or near a mine opening is permitted with the approval of the Certified Person. No person shall be permitted to enter a mine opening unless the atmosphere of the opening is tested, the roof is adequately supported and tested, and only at the direction of the Certified Person.
- E. CONTRACTOR shall identify and develop rapid communication procedures with the closest available emergency medical response units and medical centers. All workers, foremen, superintendents, and managers shall be indoctrinated to emergency response procedures.
- F. CONTRACTOR shall be aware that underlying mine workings exist in the areas to be disturbed by the CONTRACTOR. The location, extent, and condition of the underground workings at each mine site are not well known. These workings or voids where workings have caved may be encountered unexpectedly during the course of the WORK and present a hazard to equipment operators and other workers at the site. The CONTRACTOR shall take every precaution to protect the safety of the workers during WORK on the project. Any voids or openings excavated or discovered shall be brought to the immediate attention of the OWNER.
- G. The WORK shall stop and the OWNER shall be notified immediately if an accident occurs or upon discovery of a hazard that threatens the safety of workers or the public. The OWNER shall be notified immediately of any situation that may cause environmental damage.
- H. CONTRACTOR shall provide, erect, and maintain temporary barriers, signs, and security devices as necessary to ensure the safety of the CONTRACTOR's personnel, the OWNER's personnel, and the general public.
- I. WORK shall occur normally during daylight hours and shall not be performed when darkness or other conditions required the use of artificial light to safely perform the WORK, without the prior written approval of the OWNER.
- J. WORK shall be performed during weekdays and shall not be performed during weekends or legal State and Federal holidays without the prior written approval of the OWNER. A schedule of holidays is available from the OWNER.
- K. WORK shall be conducted with minimum interference to public or private thoroughfares. Egress and access shall be maintained at all times.
- L. Roadways shall not be closed or obstructed without permits. The CONTRACTOR will close and lock gates at the landowner's request.
- M. All trucks transporting materials and debris shall be covered with tarps or other suitable

coverings if necessary to eliminate loss of debris during transportation to off-site disposal areas.

- N. CONTRACTOR shall provide water and an adequate water supply system for dust suppression where dust will cause a public nuisance or as directed by OWNER. The CONTRACTOR will pay the cost of water and dust suppression.
- O. No materials shall be placed in or be situated such that they may enter any stream, tributary, or drainage channel.
- P. Relics, antiques, artifacts and similar objects as identified by the OWNER remain the property of the OWNER. CONTRACTOR shall notify the OWNER upon discovery of cultural features and obtain direction from OWNER regarding handling of features that interfere with performing the WORK. Relics and antiques include, but are not limited to:
 - 1. Cornerstone and contents
 - 2. Commemorative plaques
 - 3. Archaeological relics or finds
 - 4. Historical relics
- Q. CONTRACTOR shall remove and promptly dispose of any contaminated, vermin infested, or dangerous materials encountered. Transformers, oil-filled electrical equipment, or other toxic materials shall be called immediately to the attention of the OWNER. Disposal of such items shall be the responsibility of the CONTRACTOR and at the direction of the OWNER in accordance with EPA and State Health requirements.
- R. CONTRACTOR shall remove from site all debris created during construction.
- S. Materials shall not be burned on site without appropriate permits and the approval of the OWNER.
- T. Blasting shall be permitted only with prior written approval of the OWNER and following submission by the CONTRACTOR of a blasting plan.
- U. Existing utilities, benchmarks, trees, vegetation, and landscaping materials which are not to be demolished, relocated, or otherwise disturbed shall be protected.
- V. Wildlife of any kind (except Norway rats) encountered during the WORK shall be left unharmed or, if captured, released unharmed offsite. Snakes, including rattlesnakes, shall not be harmed. Any wildlife inadvertently killed by the CONTRACTOR will be turned over to the OWNER to be disposed of under the Certificate of Registration (COR Number 6COLL5414) issued to the OWNER by the Utah DWR. CONTRACTOR shall immediately notify OWNER of any bats found in mine openings.
- W. CONTRACTOR shall compensate employees at a rate of no less than 1.5 times the base rate of pay for work beyond 40 hours in one week.
- X. CONTRACTOR shall submit to OWNER each week daily logs indicating the following: 1) weather conditions, 2) crew size, 3) hours worked, 4) equipment used, 5) work completed, 6) WORK approved, 7) delays, 8) equipment downtime, 9) injuries, 10) visitors, 11) access problems, etc. OWNER has provided a form for these logs in Appendix D.
- Y. Should onset of adverse winter or extreme summer weather conditions force construction to stop prior to completion of the WORK, the sites shall be left in a condition that minimizes safety hazards and risk of erosion. Temporary erosion control structures may be required.

Section 0200

Revegetation may be postponed to the fall if necessary.

- Z. Depending upon the bid submittals and the overall CONTRACTOR selection process, CONTRACTOR WORK may precede, follow, or occur during work by other CONTRACTORS at the same site and/or other sites in the Project Area.
- AA. CONTRACTOR shall select from a pre-determined number of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.

1.05 QUALITY ASSURANCE

- A. CONTRACTOR shall use only quality materials in performing the WORK.
- B. Quality of the WORK performed by the CONTRACTOR shall be subject to approval by the OWNER. CONTRACTOR shall assure that the WORK has been performed to the specifications and standards as described herein. The OWNER shall inspect and accept or reject the WORK as the WORK progresses. Payment shall be made only for WORK accepted and approved by the OWNER. CONTRACTOR shall warrant the WORK for a period of one year following final acceptance except that such material warranties and guarantees from manufacturers and suppliers that may be longer than one year shall carry for their term.

PART 2 - PRODUCTS

2.01 GENERAL

Products and materials used in the WORK shall be as required in these Specifications.

2.02 DELIVERY, STORAGE AND HANDLING

- A. CONTRACTOR shall be responsible for the delivery, storage and handling of all items and materials used in performing the WORK.
- B. CONTRACTOR shall be responsible for all materials used in conjunction with the WORK until said WORK is accepted and approved by the OWNER and shall warrant all materials as required by Part 1.05, Quality Assurance.

PART 3 - EXECUTION

PREPARATION

- A. Upon receipt of notice to proceed, the CONTRACTOR shall perform the WORK as required by these Specifications and Construction Drawings.
- B. CONTRACTOR shall obtain and provide proof of all licenses, permits, bonds, insurance and other such items as may be required by these Specifications and local, regional, State and Federal jurisdictions prior to execution of the WORK. CONTRACTOR shall select from a pre-determined set of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.
- C. Upon receipt by the CONTRACTOR of the NOTICE TO PROCEED, the CONTRACTOR shall notify the OWNER of the starting date and execution of the WORK shall commence in accordance with the General Specifications as included with the Agreement and the Technical Specifications as presented herein. CONTRACTOR shall provide the OWNER with a schedule

for the proposed WORK in calendar, bar chart, or critical path schedule form.

PART 4 - FORM OF AGREEMENT

4.01 CONTRACT AGREEMENT

The CONTRACT agreement will be in the form of that included in the bid package. This agreement may be administered as a Division of Purchasing Purchase Order. If administered as a purchase order, the purchase order will reference the bid package, and all the terms and conditions of the solicitation, including the contract form, general and supplementary conditions, technical specifications, and addenda will apply to the agreement.

4.02 CHANGES TO THE AGREEMENT

- A. When these services are procured by an agency contract, OWNER shall require amendments to the Agreement to be in the form of a change order, signed by both parties. When these services are procured by a Division of Purchasing Purchase Order, amendments shall be on Form DP-28 "Request for Purchase Order Cancellation or Change."
- B. Change orders or Form DP-28's shall become attached to and part of the Agreement under the terms of the Agreement with changes as stipulated on the change order or Form DP-28. Change orders or Form DP-28's shall not release the CONTRACTOR from any other terms or conditions that apply and are a part of the Agreement.
- C. Any additional WORK must be authorized by the OWNER and must be in the form of a contract change order or Form DP-28 as an amendment to the Agreement. The change order or Form DP-28 must be fully executed prior to the CONTRACTOR undertaking any additional WORK.

PART 5 - MEASUREMENT, PAYMENT, AND WORK INCLUDED

5.01 GENERAL

- A. The WORK included and measurement of and payment for that WORK shall be as described within each Section of the Technical Specifications and Supplementary Condition #6.
- B. Total contract amount, including any change orders, shall constitute full compensation for the WORK.
- C. Payments shall only be made for those items shown on the Bid Schedule. All other costs or incidentals shall be reflected in the Bid Schedule or shall be paid at the CONTRACTOR's expense.

5.02 RETAINAGE

Unless stated otherwise in the specific section of the Specifications, all final bid item payments shall have ten percent withheld as retainage until successful completion of the CONTRACT. The retainage shall be made from each progress payment, and be released upon written Final Acceptance by the OWNER.

5.03 PENALTIES

- A. The OWNER reserves the right to levy a penalty payment for areas unnecessarily disturbed during the WORK. These areas include any archeological sites, paleontological sites, or undisturbed upland vegetation areas.

Section 0200

- B. The penalty for unnecessary disturbance to archeological sites, paleontological, or upland vegetation areas will be based on the per acre disturbance at the CONTRACTOR's bid amount for revegetation of adjacent sites.

END OF SECTION 0200

0220 Mobilization/Demobilization

PART 1 - GENERAL

WORK INCLUDED

The item for payment for mobilization/demobilization is intended to compensate the CONTRACTOR for operations including, but not limited to, those necessary for the movement of personnel, equipment, supplies, and incidentals to and from the project area, movement between the various mine sites included within the project area, and for all other WORK and operations which must be performed or costs incurred prior to the initiation of meaningful work at the site.

PART 2 - PRODUCTS

2.01 DRINKING WATER AND SANITARY FACILITIES

CONTRACTOR shall provide and maintain safe drinking water and sanitary facilities for all employees, all subcontractors' employees, and the OWNER. Drinking water and sanitary facilities shall comply with all regulations of the local and state departments of health and be approved by the OWNER.

2.02 COMMUNICATIONS

CONTRACTOR shall provide OWNER's onsite inspector or representative with an onsite communication system for the OWNER's Exclusive use for the full duration of the project construction. The communication system shall be a cellular telephone and cellular service, or equivalent. Cell phones shall have sufficient power to allow clear transmissions from a majority of the project area. Any necessary accessories, such as antennas, batteries, battery charger, cigarette lighter adapter, and operating manuals, shall be provided. This item is not a separate bid or pay item; all telephone costs are subsidiary to and should be included in the overall cost for Mobilization/Demobilization.

PART 3 - EXECUTION

3.01 PREPARATION

- A. Preparation of the WORK shall include obtaining all permits and other such incidentals as necessary to execute the WORK. CONTRACTOR shall select from a pre-determined set of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.
- B. Permits shall be posted or readily available prior to start of construction activities as required by municipal, State, or Federal regulations.

3.02 EXECUTION

Upon receipt by the CONTRACTOR of due NOTICE TO PROCEED, the CONTRACTOR shall notify the OWNER of the starting date and execution of the WORK shall commence in accordance with the General Specifications as included with the Agreement and the Technical Specifications as presented herein. CONTRACTOR shall provide the OWNER with a schedule for the proposed WORK in calendar, bar chart, or critical path schedule form.

PART 4 - MEASUREMENT AND PAYMENT

4.01 BASIS FOR PAYMENT

No partial payments will be made for multiple equipment moves or for moving between sites. Only the following partial payment shall be made of the total lump sum for mobilization/demobilization. Payment of sixty percent (60%) of total lump sum for mobilization will be made when 10 percent of the overall BID PRICE has been earned from other bid items. Payment of the remaining forty percent (40%) of the total lump sum for demobilization will be made after issuance of the Certificate of Substantial Completion at the completion of CONTRACT. Payments for mobilization/demobilization are not subject to withholding of retainage. The BID PRICE for mobilization/demobilization will also include those incidental costs as required by the CONTRACTOR in order to commence the WORK such as permits, insurance, and other such items as may be required to perform the WORK.

4.02 MEASUREMENT

Measurement will be based on the amount of the WORK performed and accepted and approved by the OWNER. When 10 percent of the WORK has been earned, the CONTRACTOR may submit on the invoice sixty percent (60%) of the BID PRICE for mobilization/demobilization as set forth above. On completion of the CONTRACT and issuance of the Certificate of Substantial Completion, the CONTRACTOR may claim the remaining forty percent (40%) of the BID PRICE for mobilization/demobilization.

4.03 PAYMENT

The BID PRICE for mobilization/demobilization will be paid once only and will include complete mobilization, demobilization, and moves between sites regardless of the number of times equipment is moved or additional equipment is transported to or from the construction site. The BID PRICE will also include those incidental costs as required by the CONTRACTOR in order to commence with the WORK such as permits, insurance, and other such items as may be required to perform the WORK.

END OF SECTION 0220

0230 Access Improvements

PART 1 - GENERAL

1.01 WORK INCLUDED

This item for payment is to develop and maintain site access or improve existing site access. Improvement is limited to the extent required to complete WORK at each mine site. It is not the intent of this WORK to construct roads. The WORK shall include temporary site access to reach sites of construction, and maintenance of existing permanent roads that must be used for movement of equipment, materials and labor. CONTRACTOR shall minimize disturbance resulting from site access improvements. In areas in which a passable road did not previously exist, the CONTRACTOR shall reclaim the access improvement in accordance with this Section upon completion of the WORK. Existing, permanent roads shall be left in a condition at a minimum as good as that prior to the WORK.

1.02 SUBMITTALS

The CONTRACTOR shall submit *with the Bid Proposal* a description of access improvements to be performed at each site and shall not deviate from this plan without the written approval of the OWNER. For sites not easily accessible, the CONTRACTOR may choose to gain equipment access, do hand work, or access with a helicopter.

1.03 RELATED WORK

- A. Section 0240: Demolition and Clean-up
- B. Section 0250: Mine Closures
- C. Section 0253: Bat Gate & Shaft Grate Installation
- D. Section 0254: Polyurethane Foam Shaft Closures
- E. Section 0300: Specific Site Requirements

PART 2 - PRODUCTS

MATERIALS

- 2.01 CONTRACTOR may utilize local resistant materials or import road base materials to maintain access and minimize damage to the environment. If wet weather conditions prevail, OWNER may require CONTRACTOR to stockpile road base material at work sites in order to maintain the schedule.
- 2.02 CONTRACTOR may choose to temporarily place corrugated steel pipe or other conveyance structures in the access improvement. The CONTRACTOR shall comply with Section 0280: Drainage Control and Stream Protection unless otherwise directed by the OWNER.

PART 3 - EXECUTION

GENERAL

- 3.01 The location, alignment and grade of any temporary access improvement shall be in accordance with Section 0300: Specific Site Requirements, subject to Section 0280: Drainage Control and Stream Protection, and subject to the approval of the OWNER.
- 3.02 Temporary access improvements shall be constructed so as to minimize disturbance to existing vegetation, and to minimize potential erosion.

Section 0230

- 3.03 Where temporary site access crosses perennial or intermittent streams, the CONTRACTOR shall maintain the drainage by providing a temporary crossing in accordance with Section 0280: Drainage Control and Stream Protection, and subject to the OWNER'S approval. Upon completion of the WORK, CONTRACTOR shall restore drainages to approximate original condition, subject to the acceptance and approval of the OWNER.
- 3.04 When no longer required by the CONTRACTOR, temporary access improvements will be reclaimed in the following manner. Existing passable access shall be left in or returned to approximate original condition. Access previously impassable or newly created access shall be restored to blend with surrounding contours and reclaimed for erosion control as shown on the Drawings. The surfaces of such access shall be scarified and revegetated in accordance with Section 0290: Revegetation.

PART 4 - MEASUREMENT AND PAYMENT

4.01 MEASUREMENT

Measurement shall be per mine site as access improvement WORK is completed, accepted and approved by the OWNER. Measurement shall be consistent with the BID PRICE. The OWNER's approval of mine site access development will be authorization for payment of 50 percent of the pay item which will also include consideration for maintenance of temporary access to the site throughout the WORK. The OWNER's acceptance of all WORK completed and approval of the temporary site access reclamation for the site will be authorization for payment of the balance of this pay item.

4.02 PAYMENT

Payment for maintenance of existing paved and gravel-surfaced roads will be consistent with the BID PRICE for this item. Payment of 50 percent of the BID PRICE will be made upon receipt of the invoice submitted by CONTRACTOR. The balance of 50 percent of the BID PRICE may be invoiced and paid after approval of the site WORK and approval of site access reclamation. Payment of this item is subject to withholding of the retainage.

END OF SECTION 0230

0240 Demolition And Clean-Up

PART 1 - GENERAL

1.01 WORK INCLUDED

The WORK consists of the demolition and clean-up of designated structures and areas including, but not limited to, those indicated in Section 0300: Specific Site Requirements. The WORK shall include, but not be limited to, the removal and disposition of concrete slabs and foundations, miscellaneous wood, metal, stone and masonry structures, and debris associated with the abandoned mine operation or generated during construction. Clean-up of miscellaneous debris exposed at the surface and randomly located across any site has not been specifically identified due to the impracticality of such extensive identification. However, it is the intent of these Specifications to require removal and disposal of *all surface debris* associated with the abandoned mine operations. Such removal and disposal shall be included in the CONTRACTOR's scope of WORK.

1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the Bid Proposal* demolition and removal procedures and schedule for approval. This should indicate if blasting is to be used in structure demolition.
- B. CONTRACTOR shall submit *after execution of the CONTRACT and prior to disposal* proof of permission for debris disposal off site at a licensed disposal site.

1.03 RELATED WORK

- A. Section 0300: Specific Site Requirements

1.04 CONDITIONS AND RESTRICTIONS

- A. Demolition shall be conducted to minimize dust generation and public nuisance.
- B. CONTRACTOR shall provide, erect, and maintain temporary barriers and security devices as necessary to ensure safety of CONTRACTOR's personnel, the OWNER's personnel, and the general public.
- C. Debris burial in, mixing with, or covering by fill material is not allowed on site.
- D. Debris placement in mine openings is only allowed with site by site approval from the OWNER.
- E. Materials shall not be burned on site.

PART 2 - PRODUCTS

CONTRACTOR may require materials for demolition and clean-up, such as wrappings or impermeable coverings not otherwise called for in other sections of these Specifications.

PART 3 - EXECUTION

3.01 PREPARATION

CONTRACTOR shall secure any and all required permits for the demolition and clean-up WORK at his or her expense.

Section 0240

3.02 EXECUTION

- A. CONTRACTOR shall demolish only those structures and appurtenances indicated. Demolition shall be performed in an orderly and careful manner. CONTRACTOR shall clean up and dispose of all debris exposed at the surface.
- B. Demolished materials of every nature shall become the property of the CONTRACTOR and shall be disposed of away from the site or at locations indicated in Section 0300: Specific Site Requirements or on the Drawings.
- C. Relics, antiques, artifacts and similar objects as identified by the OWNER remain the property of the OWNER. CONTRACTOR shall notify the OWNER prior to removal and obtain acceptance regarding method of removal. Relics and antiques include, but are not limited to:
 - 1. Cornerstone and contents
 - 2. Commemorative plaques
 - 3. Archaeological relics or finds
 - 4. Historical relics
- D. CONTRACTOR shall remove and promptly dispose of any contaminated, vermin-infested, or dangerous materials encountered. Transformers, oil-filled electrical equipment or other toxic materials shall be called immediately to the attention of the OWNER. Disposal of such items shall be at the direction of the OWNER in accordance with EPA and State Health requirements.
- E. CONTRACTOR shall remove foundation walls and footings to a minimum three feet below finished grade as indicated in the Drawings unless otherwise directed in Section 0300: Specific Site Requirements.
- F. CONTRACTOR shall remove all concrete slabs on grade as indicated in the Drawings unless otherwise directed in Section 0300: Specific Site Requirements.
- G. CONTRACTOR shall provide water and an adequate water supply system for dust suppression for haul roads and demolition WORK where dust will cause a public nuisance or as directed by the OWNER. The cost of water will be paid by the CONTRACTOR.
- H. Depressions resulting from demolition operations shall be filled with materials, approved by the OWNER, from on the site or from designated borrow areas unless located in an area where further excavation is required to yield the reclamation contours shown in the Drawings. The fill material shall be in accordance with Section 0270: Site Grading/Earthwork.
- I. CONTRACTOR shall grade and compact areas affected by demolition to maintain site grades and contours. In no case shall slopes exceed 3h:1v or natural site contours.
- J. CONTRACTOR shall remove demolished materials from site in an orderly fashion. CONTRACTOR shall leave site in clean condition for reclamation grading and earthwork.
- K. CONTRACTOR shall remove from site all debris created during construction.
- L. Final shape and completeness of the WORK shall be subject to approval by the OWNER.

3.03 SALVAGING MATERIALS

All salvaged materials shall become the property of the CONTRACTOR with the exception of relics, antiques or artifacts identified by the OWNER. Salvaged materials from the structures may be stored on-site temporarily, but not beyond the date specified for completion of the CONTRACT. Any value of salvaged materials or costs associated with the removal of equipment, structures, or materials shall be reflected in the bid price amount for Demolition and Clean-up.

PART 4 - MEASUREMENT AND PAYMENT

4.01 MEASUREMENT

- A. Measurement shall be per itemized structure or mine site (as specified on the bid sheet) as demolition and clean-up WORK is completed, accepted, and approved by the OWNER.
- B. The final quantities for major categorizations of materials may vary from the estimated quantities provided. The estimated quantities are based on information gathered and interpreted from surface investigations.

4.02 PAYMENT

Payment for the demolition and clean-up WORK shall be per itemized structure or mine site, at the BID PRICE upon approval of the OWNER for all of the WORK described in this Section.

END OF SECTION 0240

0250 Mine Closures

PART 1 - GENERAL

1.01 WORK INCLUDED

This section describes the various types of mine closures to be used to seal mine openings. The WORK described in this Section also includes preparation, excavation and backfilling of subsidence openings into mine voids. The requirements for furnishing and placing stone and block closures and backfill closures are described here and are indicated on the Drawings. The WORK includes all preparation, labor, materials, furnishing and placing materials, equipment and incidentals necessary to complete the mine closures.

1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the bid proposal* a list of equipment to be used to complete this section of the WORK.
- B. CONTRACTOR shall submit *with the bid proposal* the proposed construction procedures in writing.
- C. CONTRACTOR shall submit *after the award of CONTRACT and before Notice to Proceed* a copy of the certification of the Certified Person (see Part 1.04.E below) for approval by the OWNER.
- D. CONTRACTOR shall furnish the OWNER a set of as-built drawings upon completion of the WORK which shall be required for release of the retainage.

1.03 RELATED WORK

- A. Section 0251: Cast-In-Place Concrete
- B. Section 0252: Concrete Reinforcement
- C. Section 0253: Bat Gate and Shaft Grate Installation
- D. Section 0254: Polyurethane Foam Shaft Closures
- E. Section 0290: Revegetation
- F. Section 0300: Specific Site Requirements

1.04 JOB CONDITIONS

PROTECTION

- A. CONTRACTOR shall exercise precautions appropriate to working near, over, or in areas prone to subsidence. Such known areas should be flagged by the CONTRACTOR prior to the commencement of the WORK. Personnel shall be informed of special safety procedures for equipment usage and general work in these areas.
- B. Personnel shall not enter any mine opening unless under the direction of the Certified Person.
- C. No personnel shall be allowed to work under an unsupported mine roof. Temporary support shall be installed under the direction of a Certified Person qualified to determine roof conditions.
- D. Smoking or any open flame in or within 100 feet of the mine openings is prohibited.
- E. Before any personnel enter any openings a check for explosive and toxic gases shall be made by a Certified Person (a qualified person with current certification to do such WORK under the

Section 0250

General Safety Orders of Utah Coal Mines i.e. Mine Foreman and/or Fire Boss). Continuing checks shall be made throughout the closure operation by the Certified Person.

- F. CONTRACTOR shall inspect openings for old dynamite prior to construction activities.
- G. Personnel shall wear safety harnesses and be properly and securely anchored to a fixed anchor point while working within 15 feet of vertical openings, unless otherwise approved in writing by the OWNER.

PART 2 - PRODUCTS

A. CONCRETE BLOCK

Solid concrete block shall be high strength with a minimum compressive strength of 3,000 pounds per square inch. Hollow block used as shown on the Drawings must be concrete-filled.

B. BACKFILL

Backfill material shall normally consist of mineral soil, subsoil, or a blend of mineral soil and subsoil. Backfill material shall be free from combustible materials. This shall include but not be limited to wood, wood products, trash and vegetation.

C. MORTAR

Mortar shall be either Masonry Cement, 1:3 mix, Type N, or Portland Cement and Lime, 1:1:6 mix, Type N. Precautions must be taken to prepare and protect mortar during cold weather. Mortar will have a 28 day minimum compressive strength for 2-inch cubes of 700 psi.

D. CONCRETE

Concrete shall be in accordance with Section 0251: Cast-in-Place Concrete.

E. REINFORCEMENT

Reinforcement shall be in accordance with Section 0252: Concrete Reinforcement.

F. FILTER CLOTH

Filter cloth shall be a non-woven geotextile fabric having a minimum thickness of 15 mil in accordance with ASTM D-1777 and a minimum permeability of 10^{-2} centimeters per second, such as Fibertex 150 manufactured by Crown Zellerbach, or an approved equivalent.

G. TEMPORARY MINE ROOF SUPPORTS

1. Mine roof supports shall be wooden posts or approved equal that have the following minimum requirements:
 - a. 4½ inch diameter.
 - b. Spruce or pine with a specific gravity between 0.35 and 0.48.
 - c. Moisture content between 10.8 and 14 percent.
 - d. Allowable unit stress of extreme fiber in bending of 750 psi for spruce or 700 psi for pine.
 - e. Maximum diameter of knots on one surface no greater than ½ inch.

2. Caps and wedges shall be used for installation of roof supports.
3. Mine roof jacks may be substituted for wooden posts with the approval of the OWNER.

PART 3 - EXECUTION

3.01 PREPARATION FOR MINE CLOSURES

- A. CONTRACTOR shall clear and grub the face area of mine openings of all vegetation, wood and debris to the extent shown on the Drawings. CONTRACTOR shall inspect, scale and secure the mine openings to a degree which will make the WORK safe to perform. Particular care shall be taken to make WORK conditions safe in instances where, due to the condition of the opening and the probability of loose soil and rock above the opening, there is danger of a rockfall. For openings to be backfilled the CONTRACTOR shall excavate the brow back to a stable condition prior to initiation of closure operations, unless otherwise directed by the OWNER.
- B. The roof and ribs of the mine openings may contain loose rock. Such loose materials shall be scaled by use of tools or equipment extended into the openings before personnel enter the opening for placement of mine roof supports or for any other reason.
- C. Loose, unstable materials typically exist just inside the opening. These materials shall be removed from the working surface inside of the mine openings so a solid working surface exists on which to build the mine closures. The working surface shall be inspected, accepted and approved by the OWNER.
- D. Temporary mine roof supports shall be installed on no more than four foot centers before any personnel enter the opening for construction purposes.
- E. CONTRACTOR shall construct work pad as required.
- F. Bat Exclusion: CONTRACTOR shall Exclude bats from mine workings prior to installation of permanent closures as required in these specifications. The Exclusion process must be conducted during the warm season when bats are flying but before young bats are born (warm season and birthing dates vary depending on geographic location and should be specified by the bat biologist), or in the fall prior to the swarming behavior that leads to hibernation. An attempt to close mines before the warm season may entomb hibernating bats that cannot fly. The preferred method for Exclusion of bats from an adit or shaft is to block the portal or shaft opening with 1-inch diameter chicken wire. The wire permits bats to escape and fly out of the mine, but they will not fly back through the wire into the mine. The wire should be placed over the entrance at least a week in advance and shall be left in place until the date of the closure. The wire should be removed during the day and closure should take place immediately.

3.02 INSTALLATION OF MINE CLOSURES

A. BLOCK WALL CLOSURE

1. CONTRACTOR shall construct walls in the adits as specified in Section 0300: Specific Site Requirements. Variation of the location of the walls will be allowed so that CONTRACTOR can select a suitable location for the walls, with approval of OWNER. Parameters for suitable location of the walls shall be as follows:
 - a. Select an area in which competent rock is found in the back, ribs, and sill (roof, walls, and floor) of the adit.

Section 0250

- b. Utilize irregularities in the ribs and back where possible such that the wall can be "keyed" into the rock to provide more strength and integrity to the wall.
 - c. Locate the wall as far into the adit as is reasonable to reduce visibility of the wall from outside the opening and a maximum of 10 feet with competent brow unless otherwise approved by the OWNER. Allowance for the location of the walls is discussed in Section 0300. Where the remaining portion of the adit left open is unstable or unsafe, backfill shall be placed from the brow to the wall unless otherwise approved by the OWNER.
2. CONTRACTOR shall scale down back and ribs (roof and sides) of the adit, removing any loose rock from the area in which the wall is to be constructed and along access to bulkhead. Any mud, clay, moss or other materials shall be removed where the wall is to be constructed which would be deleterious to the integrity of the wall and would not allow good bonding of the mortar to the rock. CONTRACTOR shall excavate sill (floor) of adit to solid rock where the wall is to be constructed. Drainage shall be provided for any water that tends to accumulate on either side of the bulkhead as described in Part 3.02.A.6 of this Section. Excavated materials shall be cast into the adit behind the bulkhead to minimize surface disturbance in the area.
3. Concrete foundations shall be constructed unless competent foundation rock is encountered which is not friable, subject to deterioration, or otherwise unacceptable and the foundation rock is approved by OWNER. The foundation shall be a minimum of 18 inches in thickness and 30 inches wide to accommodate the 2-foot thick wall. The foundations shall be made of concrete as specified in Section 0251: Cast-In-Place Concrete. Concrete shall be reinforced with No. 4 rebar as shown on the Drawings and as specified in Section 0252: Concrete Reinforcement.
4. CONTRACTOR shall construct walls from foundation or solid rock base if approved by OWNER. Walls shall be constructed of concrete block, native stone, or imported stone. Concrete block walls shall be a minimum of 16 inches thick. Native stone and imported stone walls shall be constructed to a minimum thickness of 2 feet at the base and 18 inches at the top. The wall shall be free of any voids within the wall structure and shall be 100 percent rock and mortar construction. Hollow block bricks, when used, shall be concrete filled. Mortar shall be free of voids and air pockets and shall be firmly packed along ribs and roof of the opening to maintain the integrity of the wall and to make an effective seal.
5. CONTRACTOR shall use the natural shape and irregularities of the mine opening to "key" the wall to the mine opening to provide strength and protection of the wall from damage due to vandalism.
6. Designated openings shall require the installation of a drainage pipe. The drainage pipe shall be located near the base of the stone wall within 15 inches of the intersection of the floor material in the approximate center of the wall or near a low spot along the base. The drain pipe shall extend through the foundation or the base of the wall and a trap shall be formed out-by the wall near the brow as shown on the drawings. The drain pipe shall protrude a minimum of 12 inches on either side of the wall and shall be made from 6-inch nominal diameter, Schedule 80 PVC pipe. The inside end of the pipe shall be firmly supported by block or natural stone. Both the inside and outside ends of the pipes shall be clear of any obstructions which would impair or restrict flow. Both ends of the pipe shall be covered with a protective screen mesh. Gravel shall be installed over the ends of the pipes to protect the pipe from roof falls and plugging. Gravel shall form a drain and cover the top of the pipe with a minimum of 8 inches of material. The gravel drain shall be no less than 18 inches wide and shall extend to and from the end of the pipes a minimum of two feet.

Gravel used in the drain channels shall be selected material ranging from 3/4 to 6 inch in size. CONTRACTOR shall extend a drainage channel away from the bulkhead if it is situated such that water could impound near the base.

7. As further protection, grout shall be used to seal the base of the bulkhead and shall be placed to partially cover the drainpipe. Grout should extend one foot to either side of the base of the wall.
8. The portal areas shall be cleared of all building materials, trash and debris. The site shall be left in a clean and finished appearance.
9. Revegetation of sites shall be completed as specified in Section 0290: Revegetation.
10. Final acceptance of the WORK shall be subject to field inspection by the OWNER.

B. BACKFILL CLOSURE

1. CONTRACTOR shall backfill mine openings as described in Section 0300: Specific Site Requirements or as directed by the OWNER. Backfill shall contain sufficient fines to minimize void space.
2. Drainage lines shall be extended, if required, to the projected limits of the backfill. The drain line shall be placed on a minimum slope of 2 percent and firmly bedded with well-compacted sand and gravel. The end of the pipe shall be protected as described in Part 3.03.A.7.
3. Backfill shall be placed in mine openings to minimum dimensions described and in a manner to eliminate voids. CONTRACTOR shall construct a work pad in front of the opening as required to allow for uniform access to ram the backfill into the opening utilizing a ram or backhoe bucket. Care should be taken not to push the wall out if one has been installed. Materials which require compaction shall be tamped to achieve compaction such that any additional settlement of the fill will not result in reopening of the portal.
4. Final shape of the fill shall be mounded over the opening and blended into surrounding contours as much as practical. Runoff and snowmelt shall be diverted away from and across the fill by use of small channels containing light riprap so that the fill does not erode or impound water.
5. Revegetation of sites shall be completed as specified in Section 0290: Revegetation.
6. The portal areas shall be cleared of all building materials, trash and debris. The site shall be left in a clean and finished appearance.
7. Final acceptance of the WORK shall be subject to field inspection by the OWNER.

C. HAND BACKFILL CLOSURE METHOD

1. Hand Backfill Closure Method shall be used only in places inaccessible to heavy equipment as designated in Section 0300: Specific Site Requirements. The backfill requirements of Section 0250: Mine Closure, Part 3.03.B apply except as provided for equipment or approved by the OWNER.
2. CONTRACTOR shall obtain backfill materials from areas specified in Section 0300: Specific Site Requirements, or as directed by the OWNER.

Section 0250

3. Backfill materials shall be placed in 12 inch thick horizontal lifts in the locations and to the extent shown on the Drawings.

D. WALL AND BACKFILL CLOSURE

Designated mine openings shall be backfilled after the installation of the wall. Bring backfill to the grades shown in the Drawings or as designated in Section 0300: Specific Site Requirements to blend with natural contours. Walls shall be installed per Section 0250, 3.02 A, B, and C.

E. VERTICAL SHAFT BACKFILL CLOSURE METHOD

1. Timber and debris shall be removed from openings to the extent safely possible.
2. CONTRACTOR shall inspect the collar of the opening and determine required precautions for safe completion of WORK. Installation of a short conveyor belt or a ramp may be required.
3. Shaft shall be filled with backfill material to a height above the collar of the shaft to provide drainage away from the opening. The backfill shall be well-graded with a maximum particle size of approximately 2 feet in diameter.
4. Filter cloth shall be installed as shown on the Drawings.
5. CONTRACTOR shall place and compact the backfill starting five feet below the surface. Suitable compaction energy shall be applied in this zone in one-foot lifts by either pressure from the back of the backhoe bucket or other means accepted and approved by the OWNER. The upper five feet of backfill shall not contain any material that may have elevated sulfate concentrations.
6. The backfill shall be mounded a minimum of 24 inches above the adjacent grade, or shall be sloped at 3h:1v and extend a minimum 3 feet horizontal distance beyond the edge of the shaft.

3.03 MINE CLOSURE GRADING

- A. CONTRACTOR shall bring backfill to the grades shown on the Drawings or to blend with natural contours. Backfill shall be free of voids and shall be compacted by mechanized equipment or hand-held mechanical compactors in one foot lifts.
- B. CONTRACTOR shall extend the drainage line (if required) to the projected limits of the backfill. The drain line shall be placed at a minimum slope of 2 percent and firmly bedded with well compacted sand and gravel. The end of the pipe shall be protected as described in Part 3.03.A.7.
- C. The backfilled slopes shall be covered with a minimum of 6 inches of soil/rock fill available on site from areas designated by the OWNER.
- D. Revegetation and mulching of the disturbed areas shall be performed in accordance with Section 0290: Revegetation.
- E. Final shape and completeness of the WORK shall be subject to approval by the OWNER.

3.04 MINE LOCATION MONUMENTS

- A. CONTRACTOR shall install at each mine closure a permanent monument (aluminum survey cap). OWNER will provide and CONTRACTOR will install the survey cap.
- B. At backfill closures, monuments shall be installed on rebar stakes. Stakes shall be #5 (5/8-inch diameter) rebar, normally 3 to 4 feet long. The rebar shall be securely anchored in the ground with the end extending above the final grade 2 to 6 inches. CONTRACTOR may opt to use soil plates, deadmen, bends, or other devices to ensure that the rebar is securely anchored. The exposed end of the rebar shall be squarely cut and free of bends, flaring, mushrooming, or burrs that would prevent proper seating of the survey cap. Seating of the cap onto the rebar shall be done taking precautions not to mar the text. Where site conditions permit and with approval of OWNER, monuments may be set directly into bedrock with epoxy resin as described below.
- C. At structural closures (bulkheads or steel grates), monuments may be set in concrete footers, grade beams, or seams while the concrete is wet or set in bedrock with epoxy resin. Installation in bedrock requires drilling a 1 1/4-inch diameter by 2 inch deep hole to receive the cap.
- D. The placement of the monument will be determined by the OWNER, but typically it will be centered in or adjacent to the mine opening for backfill closures. Monuments should not be placed where it is necessary to climb onto the closures to read them. Monument positioning should consider the potential for vandalism and the potential for siltation that could bury the cap. Monuments may be installed in by grate closures, but not so deep that they cannot be easily read.

PART 4 - MEASUREMENT AND PAYMENT

4.01 BASIS OF PAYMENT

Basis of payment for the WORK will be on the BID PRICE per opening for completion of all the WORK as described in this Section. Breakdown of the WORK into unit prices for individual mine openings shown in the Bid Schedule will be used in determining partial payment or adjustment of the total BID PRICE for this Section as the WORK progresses.

4.02 MEASUREMENT

Measurement for mine closures will be on the BID PRICE per mine opening. Measurement will be based on and compared to the dimensions and quantities identified on the bid sheets, these Specifications and Drawings. The OWNER will request intermediate measurements to determine progress of the WORK.

4.03 PAYMENT

- A. Payment for mine closures will be for each mine site at the BID PRICE. Payment will only be for those closures which are complete, accepted, and approved by the OWNER. No partial payments will be made for individual mine openings.
- B. Payment at the UNIT PRICE for additional quantities will be made for mine closures when final quantities are greater than 15 percent in excess of the estimated quantities shown on the bid sheet for a given mine site. Such unit price payment will require proof of additional quantities provided by the CONTRACTOR and approval of the OWNER, and shall be full compensation for the approved additional masonry or backfilling. Reduction of payment for lesser quantities of masonry or backfill will also be made by the OWNER for quantities greater than 15 percent below the estimated quantity shown on the bid sheet for a given mine. Such UNIT PRICE

Section 0250

adjustment will require approval of the OWNER and will be full compensation for approved additional or reduced mine closure quantities.

END OF SECTION 0250

0251 Cast-In-Place Concrete

PART 1 - GENERAL

1.01 WORK INCLUDED

Cast-in-place concrete shall be used in the WORK for mine closures. This Section provides the material standards, procedures and quality control that shall be required for cast-in-place concrete.

1.02 SUBMITTALS

A. Concrete

1. CONTRACTOR shall submit *with the Bid Proposal* laboratory reports indicating that the supplier's concrete ingredients meet requirements specified.
2. CONTRACTOR shall submit *before use of cast-in-place concrete in WORK* design mixes and laboratory test reports indicating that the concrete ingredients and proportions will result in concrete mixes meeting requirements specified.

B. Batch Tickets

CONTRACTOR shall submit, *with each batch delivered*, delivery tickets from the concrete supplier setting forth the following information:

1. Name of Supplier
2. Name of batching plant and location
3. Date
4. Serial number of ticket
5. Truck number and batch number
6. Contract number and location
7. Volume of concrete (cubic yards)
8. Maximum size of aggregate
9. Type and brand of cement
10. Weight of cement
11. Maximum size of aggregate
12. Weights of fine and coarse aggregates
13. Types and amounts of admixtures
14. Weight of water, or, alternatively, the water:cement ratio

1.03 RELATED WORK

- A. Section 0250: Mine Closure
- B. Section 0252: Concrete Reinforcement

1.04 QUALITY ASSURANCE

Design Criteria:

A. Portland Cement Concrete Mixture

Concrete for closures and structural slabs shall have a minimum compressive strength of 3,000 psi in 28 days. The concrete shall be proportioned in accordance with ACI 211. The type of cement used shall be Portland, Type II (ASTM C150). Air entrainment shall be furnished in all concrete. Air content shall be $5\% \pm 1\%$.

Section 0251

B. Formwork

As outlined in ACI 301, Chapter 4.

C. Reference Standards (Latest Editions)

1. ACI 211 Recommended Practice for Selecting Proportions for Normal Weight Concrete
2. ACI 301 Structural Concrete for Buildings
3. ACI 302 Guide for Concrete Floor and Slab Construction
4. ACI 304 Recommended Practice for Measuring, Mixing, Transporting and Placing Concrete
5. ACI 305 Recommended Practice for Hot Weather Concreting
6. ACI 306 Recommended Practice for Cold Weather Concreting
7. ASTM C 31 Standard Method of Making and Curing Concrete Test Specimens in the Field
8. ASTM C 33 Specification for Concrete Aggregates
9. ASTM C 39 Test for Compressive Strength of Cylindrical Concrete Specimens
10. ASTM C 94 Specification for Ready-Mixed Concrete
11. ASTM C 150 Specification for Portland Cement
12. ASTM C 172 Sampling Fresh Concrete
13. ASTM C 494 Specification for Chemical Admixtures for Concrete

PART 2 - PRODUCTS

MATERIALS

2.01 CEMENT

Cement shall be Type II Portland cement, conforming to ASTM C 150, unless otherwise approved by the OWNER.

2.02 FINE AND COARSE AGGREGATE

Shall conform to ASTM C 33

2.03 WATER

Water shall be potable.

2.04 ADMIXTURES

- A. Chemical Admixtures: ASTM C 494
- B. Calcium Chloride will not be permitted.

2.05 FORMWORK

Form ties, fabricated so that portion remaining in the structure is at least two inches back from concrete surface.

PART 3 - EXECUTION

3.01 FORMWORK

- A. Forms shall be provided for all concrete except where instructed by the OWNER.
- B. Form surfaces which will be in contact with concrete shall be treated with an effective bond-breaking form coating. Such coating shall also effectively prevent the absorption of water from the concrete by plywood forms.

3.02 MIXING

- A. Concrete may be mixed at the job site or delivered as "ready mix" at the CONTRACTOR's option.
- B. If mixed on the site, equipment and mixing procedures shall conform to ACI 301, Chapter 7.
- C. If "ready mixed" concrete is used, it shall be mixed and transported in accordance with ASTM C 94.

3.03 HOT WEATHER CONCRETING

Conform to the requirements of ACI 305

3.04 COLD WEATHER CONCRETING

Conform to the requirements of ACI 306

3.05 PLACING

- A. Concrete shall be placed in accordance with the requirements of ACI 304, Chapter 6.
- B. Concrete shall be placed in forms in horizontal layers of 12 to 18 inches as near as possible to its final location.
- C. Each horizontal layer shall be consolidated by using a mechanical vibrator. The vibrator shall extend into the underlying layer to weld the two layers together. The use of vibrators to move concrete horizontally within the forms shall not be permitted.
- D. Concrete shall not be allowed to free fall more than 6 feet within the confines of the form work. Use tremies, hoses, chutes, or other devices where greater distance is required.

3.06 FIELD QUALITY CONTROL

The OWNER may require random samples for the purpose of quality control. CONTRACTOR shall take sample specimens of the concrete in cylindrical containers in accordance with ASTM C 31 at the point of deposit as follows:

- A. One sampling, consisting of a minimum of three cylinders, shall be made for each batch of ready-mix concrete. At least one sampling shall be made for each 50 cubic yards of concrete or for each day of placing.
- B. The samples shall be taken in accordance with ASTM C 172.
- C. All three sample cylinders will be taken at the same time: one cylinder to be used for a 7-day

Section 0251

test and two for a 28-day test. The average of the 28-day test results will be used for determining acceptance.

D. The 7-day, and 28-day tests shall be performed in accordance with ASTM C 39.

3.07 CURING

Comply with the requirements of ACI 301.

3.08 PATCHING

All damaged and honeycombed areas shall be repaired in accordance with ACI 301, Chapter 9.

3.09 FINISH

A. Formed Surfaces - After removal of forms, patch tie holes and defects. Remove fins from surfaces.

B. Unformed Surfaces - Screed surfaces to indicated dimensions.

3.10 CONSTRUCTION JOINTS

A. Before placement of fresh concrete, CONTRACTORS shall clean reinforcing steel, welded wire fabric and joint surfaces of hardened concrete.

B. Construction joints shall be prepared and bonded as provided in Section 6 of ACI 301 for elevated slabs and ACI 302 for slabs on grade.

PART 4 - MEASUREMENT AND PAYMENT

Measurement and payment for cast-in-place concrete will be per the BID PRICE per mine site in Section 0250: Mine Closure.

END OF SECTION 0251

0252 Concrete Reinforcement

PART 1 - GENERAL

1.01 WORK INCLUDED

Concrete reinforcement is used in various parts of the WORK, described in Part 1 of Section 0251: Cast-in-Place Concrete. This section describes the requirements for concrete reinforcement in concrete structures. Placement of concrete reinforcement shall be as shown on the Drawings.

1.02 RELATED WORK

- A. Section 0250: Mine Closure
- B. Section 0251: Cast-in-Place Concrete

1.03 QUALITY ASSURANCE

Reference Standards (Latest Editions)

- A. ACI 318 Building Code Requirements for Reinforced Concrete
- B. ASTM A 615 Specifications for Deformed and Plain Billet-Steel Bars for Concrete Reinforcement

PART 2 - PRODUCTS

MATERIALS

- 2.01 Reinforcing steel shall be made from plain or deformed new billet stock and shall conform to ASTM A 615, Grade 60.
- 2.02 Reinforcement chairs, hangers, spacers, or other supports shall be non-corrosive.
- 2.03 All reinforcement shall be free from oil, mill scale and excessive rust, or other coatings that will destroy or reduce bond.

PART 3 - EXECUTION

INSTALLATION

- 3.01 Reinforcement shall be accurately formed to the dimensions indicated.
- 3.02 All bars shall be bent cold and shall not be straightened in a manner which will injure the material.
- 3.03 Bars shall be spaced and positioned as shown on the Drawings.
- 3.04 Three (3) inches of concrete cover shall be provided for main reinforcement.
- 3.05 Reinforcement shall be spliced and tied in accordance with the requirements of ACI 318, and as shown in the Drawings.

PART 4 - MEASUREMENT AND PAYMENT

No separate measurement and payment shall be made for concrete reinforcement. OWNER will ascertain that concrete reinforcement meets the requirements of this section and is sized and placed in accordance with the Drawings and these Specifications. OWNER's approval for pay items including concrete reinforcement will require the OWNER's acceptance and approval of the concrete reinforcement.

END OF SECTION 0252

0253 Bat Gate & Shaft Grate Installation

PART 1 - GENERAL

1.01 WORK INCLUDED

- A. CONTRACTOR shall construct steel gates or grates in the portals and shafts as specified in Section 0300: Specific Site Requirements and in accordance with this section. The purpose of the gates and grates is to maintain airflow and wildlife access while preventing human access into the mine.
- B. This work shall consist of fabricating and installing steel bat gate or rebar shaft grate closures within specific mine adits and shafts. Work shall include excavation of loose material and trimming of the mine opening; drilling, placing, and grouting anchors; concrete footers; and fabrication, installation, and welding of steel gates or grates in accordance with these specifications. Refer to the Drawings for construction details.
- C. The dimensions shown on Standard Drawings are generic and based upon a standard design. Actual dimensions will be determined by the mine opening size and site preparation. The CONTRACTOR shall make the necessary measurements and adjustments to ensure that a competent gate or grate is constructed that will prevent human access. Very large or irregularly shaped openings may require custom fitting or modification of the generic design in consultation with the OWNER. Minor variations in the location of the bat gate will be allowed so that the CONTRACTOR may select a stable location for the bat gate, with the approval of the OWNER.

1.02 RELATED WORK

- A. Section 0250: Mine Closure
- B. Section 0251: Cast-in-Place Concrete
- C. Section 0252: Concrete Reinforcement

PART 2 - PRODUCTS

MATERIALS

2.01 BAT GATE COMPONENTS

All steel used for bat gate closure construction shall be 12-14% manganese steel (Manganal® steel or equivalent). Round stock used for horizontal crossbars, perimeter supports, anchor pins, and supplemental vertical bars shall be #8 bars (1 inch diameter). Flat stock used for vertical supports, roof anchor plates, gussets, and lock boxes shall be 4" x ½" plate. Welding rod shall be suitable for use on manganese steel.

2.02 CORRUGATED METAL PIPE (CMP)

Corrugated metal pipe shall be fabricated of 16 gauge (0.064-inch thickness) steel and shall have 2:-inch by 2-inch corrugations. Fabrication shall be riveted (5/16-inch/ single rivet), welded or helical. Continuous lap seam and continuous welded seam shall be considered equivalent in strength to two fasteners per corrugation seam. Fabrication must meet AWS @Structural Welding Codes@ and AASHTO 1977 Standard Specifications for Highway Bridges. CMP galvanization shall meet the requirements of ASTM A386 for assemble products for ASTM A123 for rolled, pressed, and forged steel shapes. Galvanizing repair paint shall meet specification MIL-P-21035. All pipe couplings and hardware shall be compatible with CMP.

Section 0253

2.03 REBAR SHAFT GRATE COMPONENTS

Steel used for shaft grate crossbars and anchor pins shall be mild steel rebar meeting the requirements of ASTM A 615. Bars shall conform to Grade 60. Rebar used for shaft grate crossbars and anchor pins shall be #8 bars (1 inch diameter).

2.04 CONCRETE REINFORCEMENT

Steel used for concrete reinforcement shall be mild steel rebar meeting the requirements of ASTM A 615. Bars other than ties shall conform to Grade 60. Ties shall conform to Grade 40 or Grade 60. Rebar used for concrete reinforcement shall be #4 bars ($\frac{1}{2}$ inch diameter). All reinforcing steel shall be free from rust, scale, or other coating that will destroy or reduce the bond with the cement-grout.

2.05 CEMENT-GROUT

Cement-grout shall consist of a mixture of sand, aggregate, and cement capable of attaining a compressive strength of 3,000 psi in 28 days. Maximum size of coarse aggregate shall be $\frac{3}{4}$ inch.

2.06 EPOXY RESIN GROUT

Epoxy resin grout shall conform to the requirements of ASTM C881, Type IV, grade 3.

2.07 PADLOCKS

Padlocks for locking bat gates shall have a minimum $\frac{3}{8}$ " diameter shackle. Padlocks shall be heavy duty, such as the Master® No. 5D or equivalent. All locks shall be keyed the same.

PART 3 - EXECUTION

3.01 GENERAL

CONTRACTOR shall construct steel gate closures in adits and steel grate closures in shafts as specified below, as shown on the Drawings, and as specified in Section 0300: Specific Site Requirements. The final design, fabrication, and erection of the gate or grate closure shall conform to the guidelines established with these specifications and the drawings. The final design shall be the responsibility of the CONTRACTOR, subject to OWNER's approval.

3.02 BAT GATE INSTALLATION

- A. Location. Variation of the bat gate closure location will be allowed so that the CONTRACTOR can select a suitable location as approved by OWNER. Parameters for suitable location shall be as follows:
 - 1. Select an area in which competent rock is found in the roof, ribs, and floor of the adit.
 - 2. Utilize smooth, non-fractured faces in the ribs and roof, where possible, such that the gate can be "keyed" into the rock to provide more strength and integrity to the closure.
 - 3. Locate the bat gate closure a minimum of three feet into the adit or as approved by the OWNER.
- B. Preparation. The CONTRACTOR shall scale down the roof and ribs of the adit, removing any loose rock from the area in which the bat gate closure is to be constructed and along access to the closure. The portal shall be cleaned and shaped as directed by OWNER. Historic structural

features shall be preserved and maintained.

- C. The concrete footer shall be poured in a trench excavated to the dimensions shown on the Drawings. Concrete shall be reinforced with #4 ($\frac{1}{2}$ -inch) rebar on 12-inch centers with a minimum 2-inch concrete cover on all surfaces. Concrete shall not be poured until the gate steel and rebar have been installed. Concrete shall be mounded as necessary so that the gap between the top of the footer and the bottom crossbar of the gate is no larger than 4 inches. Forms will not be required unless called for by sloping conditions or deep unconsolidated floor material. If used, forms shall be sufficiently braced to prevent movement or dislocation during or after setting the gate steel and rebar in place. Forms shall be removed upon completion of the closure. Concrete construction shall be done in accordance with Section 0251: Cast-In-Place Concrete and Section 0252: Concrete Reinforcement.
- D. Anchor pins shall be doweled into the adit walls a minimum of 12 inches and grouted into place with either cement or epoxy resin. The CONTRACTOR shall determine the means of drilling into the rock and submit the method to the OWNER for approval prior to the start of the drilling operations. Anchor pins shall protrude from the adit ribs to attach the perimeter supports and roof anchor plates. Anchor pins shall be fillet welded to the perimeter bars. Roof anchor plates shall be 4 inches by 8 inches and welded with a continuous bead to the top of the vertical supports and the anchor pins. There shall be at least two anchor pins on each side of the adit and at least one pin for each roof anchor plate. Anchor pins shall be located in competent rock affording the most secure placement. Anchor plate and pin locations and dimensions may be adjusted to fit site conditions with approval of OWNER.
- E. Perimeter bars shall be fillet welded to the anchor pins to provide a continuous steel lining on the adit ribs. Perimeter bars shall be bent or cut into segments to conform closely to irregular surfaces, with a maximum gap of 6 inches between the rib and the bar. If cut into segments, ends of segments shall be butt-welded to each other to form a continuous piece. Perimeter bars shall be installed on the outby side of the gate or as directed by OWNER. However, the perimeter bar at the position of the removable locking bar (crossbars 4 and 5, perimeter bar welded to crossbars 3 and 6) must be on the inby side of the gate.
- F. The vertical supports shall have $1\frac{1}{8}$ inch diameter holes at the required spacing to accept the horizontal crossbars with a minimum of play. Vertical supports shall extend into the concrete footer and shall be positioned as close to the adit ribs as possible, with a maximum gap of 16 inches between the rib and the vertical support. Vertical supports shall be plumbed as directed by OWNER. The tops of the vertical supports shall be welded to the roof anchor plates with a continuous bead.
- G. Horizontal crossbars below a height of 48 inches above the top of the footer shall be spaced on 5-inch centers for a maximum gap between bars of 4 inches. Horizontal crossbars over 48 inches high shall be spaced on $6\frac{1}{2}$ -inch centers for gaps between bars of $5\frac{1}{2}$ inches. With vertical supports and supplemental vertical bars in place, no opening in the bars below 48 inches high shall be larger than 24 inches by 4 inches. There shall be at least one opening in the top tier of bars that is 24 inches by $5\frac{1}{2}$ inches, but no opening in the bars above 48 inches high shall be larger than this. Ends of horizontal crossbars shall be installed to within one inch of the adit rib surface. Except for the removable locking bar, horizontal crossbars shall be fillet welded at each intersection with the perimeter bars and supplemental vertical bars and spot welded at each intersection with the vertical supports.
- H. Supplemental vertical bars shall be installed on the outby side of the horizontal crossbars on $24\frac{1}{2}$ -inch centers as necessary so that no gate opening is greater than 24 inches wide. Supplemental vertical bars shall be fillet welded to horizontal crossbars at each intersection.

Section 0253

Supplemental vertical bars shall extend down to the concrete footer.

- I. The lock box shall be constructed to the shape and dimensions shown on the drawings with fillet welds at all joints. The box shall be welded onto the vertical support at the position of the fourth and fifth horizontal crossbars from the bottom. Tolerances for the lock mechanism construction shall be sufficient to prevent vandals from accessing the padlock with common hand tools. Supplemental shields may required to protect the mechanism.
- J. The fourth and fifth horizontal crossbars shall be welded together with spacers and gussets to form a single removable, lockable unit as shown on the Standard Drawings. Gussets 4 inches square shall be fillet welded to the crossbars and spacers on both sides with a continuous bead. The lockbox ends of the crossbars shall be shaped as shown on the drawings to accept the padlock. The free ends of the crossbars of the removable unit, when installed, shall not extend beyond the vertical support more than 18 inches. Any remaining gap between the ends of the removable crossbars and the adit rib shall be filled with immovable crossbars and vertical bars as required, following the same pattern as the rest of the gate.
- K. Upon completion, soil or rock excavated for the closure preparation and footer trench shall be replaced or scattered to blend with the surroundings. The portal area shall be cleared of all construction materials, formwork, and construction-generated trash and debris. The site shall be left with a clean and finished appearance.
- L. All horizontal crossbars shall be continuous. Joints, if required, shall be butt joints, with bar ends welded to each other to form a continuous piece.
- M. Additional bars or plates may be required to close gaps due to irregularities in the adit rib surface or as supplemental supports, gussets, or lock shields.
- N. All field welds shall be in accordance with the requirements of the American Welding Society (AWS) D.1.1.
- O. Variation in the generic design or custom fitting may be required to accommodate site-specific conditions. Section 0300: Specific Site Requirements may specify alternate materials, dimensions, or design modifications for specific mine openings.

3.03 REBAR SHAFT GRATE INSTALLATION

- A. Location. Variation of the location of the shaft grate will be allowed so that CONTRACTOR can select a suitable location for the shaft grate, with approval of OWNER. Parameters for suitable location of the rebar shaft grate shall be as follows:
 - 1. Select an area in which competent rock is found around the collar of the shaft, if possible.
 - 2. Select an area with minimum irregularities in the collar to avoid excessive site preparation for the construction of the grade beam around the collar.
 - 3. Locate the grade beam at a reasonable distance (typically 3 feet minimum, or as directed by the OWNER) from the shaft collar to reduce the possibility of collapse of the collar of the shaft.
 - 4. Grates at shafts with competent rock collars where grade beams are omitted shall be installed at grade or inside the opening to a maximum depth of 3 feet below grade.
- B. Preparation. CONTRACTOR shall excavate to solid rock where the grade beam is to be constructed where the depth does not exceed two feet to bedrock. Any mud, clay, moss, or

other materials where the grade beam is to be constructed which would be deleterious to the integrity of the grate or grade beam and would not allow good bonding of the concrete to the rock shall be removed. Historic structural features shall be preserved and maintained. Drainage shall be provided for any water that would accumulate on either side of the grade beam. Excavated materials shall be set aside for replacement later.

- C. Where possible, concrete grade beams shall be constructed on competent foundation rock which is not friable, subject to deterioration, or otherwise unacceptable and the foundation rock is approved by OWNER. The grade beam shall be a minimum of 12 inches high and 12 inches wide. Grade beams for grates larger than 15 feet in either dimension (measured from the interior sides of the grade beams) shall be a minimum of 18 inches high and 12 inches wide, or as directed by OWNER. Grade beams shall be pinned to the foundation rock using #8 rebar anchor pins installed a minimum of 18 inches into the rock, grouted, and set 2 inches below the upper surface of the grade beam. Rebar anchor pins shall be located on 8-foot centers maximum.
- D. Forms will be required for all grade beams. Forms shall be sufficiently braced to prevent movement or dislocation during or after setting the grate steel and rebar in place. Concrete shall be reinforced with #6 ($\frac{3}{4}$ -inch) rebar as shown on the Drawings. Concrete shall not be poured until the grate steel and rebar have been installed. Concrete shall be poured in one continuous operation and shall be free of cold joints. The grade beam shall be free of any voids within the beam structure and shall be 100 percent concrete construction. Concrete construction shall be done in accordance with Section 0251: Cast-In-Place Concrete and Section 0252: Concrete Reinforcement.
- E. Grates larger than 15 feet in either dimension (measured from the interior sides of the grade beam) shall be constructed with a supplemental support for the grate. This support shall be a mild steel W8 x 15 I-beam centered in the long-dimension sides, and running across the short dimension of the grate. The I-beam support shall be positioned directly beneath the crossbars and will be embedded in the grade beam 4 inches at each end. The height of the grade beam will be adjusted as needed to accommodate additional height of the I-beam support.
- F. Crossbars shall be installed in the grade beams running each direction on 8-inch centers to form a square grid. Crossbars shall be positioned a minimum of 4 inches below the top surface of the grade beam. Crossbars running the short dimension of the grate shall be placed underneath, except where there is a supplemental I-beam support. Each intersection of the crossbar grid shall be fillet welded on the upper side.
- G. In shafts with competent collars, grade beams may be omitted with approval of the OWNER. Rebar anchor pins shall be installed a minimum of 12 inches into the collar. At least 4 anchor pins shall be installed, with a maximum spacing of 8 feet between pins. Support bars shall be welded to the anchor pins. Grate crossbars shall be installed on the support bars, running each direction on 8-inch centers to form a square grid. Each intersection of the crossbar grid and each contact with the support bars shall be fillet welded on the upper side.
- H. Crossbars shall be continuous. Lap joints, if required, shall be a minimum of 5 inches with continuous fillet welds along both sides of the lap joint.
- I. All field welds shall be in accordance with the requirements of the American Welding Society (AWS) D.1.1.
- J. Upon completion, the collar areas shall be cleared of all construction materials, formwork, and construction-generated trash and debris. Material excavated for the grade beam preparation

Section 0253

shall be backfilled against the beam. Excess material shall be blended into the surrounding area. The site shall be left with a clean and finished appearance.

- K. Variation in the generic design or custom fitting may be required to accommodate site-specific conditions. Section 0300: Specific Site Requirements may specify alternate materials, dimensions, or design modifications for specific mine openings.

3.04 CMP BAT GATE (ADIT GATE) INSTALLATION

- A. Bat gates shall be installed in CMP culverts in unstable locations where gates cannot be anchored directly to competent rock. Culverts may be round or elliptical. Culvert diameters and lengths will be specified in Section 0300: Specific Site Requirements. Culverts will typically be the largest diameter that will fit the opening. Culverts will typically extend in by the brow to competent rock or a minimum distance of twice the adit height. Culverts will typically extend out by the brow 2 feet past the backfill line.
- B. Adit Preparation. The CONTRACTOR shall scale down the roof and ribs of the adit, removing any loose rock from the area in which the CMP bat gate closure is to be constructed and along access to the closure. The portal shall be cleared of obstructions, trimmed, and shaped as directed by OWNER to receive the culvert. Historic structural features shall be preserved and maintained.
- C. Pipe Bed. A pipe bed of sand, crushed rock, fine mine dump material (minus 3 -inch) or equivalent shall be placed a minimum 4 inches thick on the adit floor. The bed shall have a constant grade and shall provide continuous support for the culvert along its entire length. Where the height of the adit is substantially greater than the culvert diameter, unclassified fill may be placed in the adit to raise the culvert to the desired elevation. Pipe bedding will then be placed on the unclassified fill.
- D. Culvert Installation. The culvert shall be slipped into position in the adit onto the pipe bed. The culvert shall be supported by bedding along its entire length when in place. Care shall be taken to avoid buckling or joint separation during handling and subsequent backfilling operations.
- E. Bat Gate Installation. The bat gate may be installed before or after placement of the culvert in the adit. The bat gate shall be installed as described in Part 3.02 above, with the following changes: the vertical supports and horizontal crossbars extend through the culvert a minimum of 6 inches and the perimeter bars are placed on the outside of the culvert. All crossbars shall be spaced on 5-inch centers for a maximum gap between bars of 4 inches. No opening in the bars shall be larger than 24" x 4".
- F. Headwall. A concrete headwall shall be constructed around the culvert and bat gate. The headwall shall be a minimum of 12 inches thick and shall extend out from the culvert a minimum of 12 inches in each direction. The headwall shall be centered on the bat gate. The concrete shall be reinforced with a single mat of #4 (1/2-inch) rebar on 12-inch centers. Concrete shall not be poured until the gate steel and rebar have been installed. Concrete shall be poured in one continuous operation and shall be free of cold joints. The headwall shall be free of any voids and shall be 100 percent concrete construction. Concrete construction shall be done in accordance with Section 0251: Cast-In-Place Concrete and Section 0252: Concrete Reinforcement.
- G. Backfill. The gap between the culvert and the adit walls shall be completely backfilled for the full length and full circumference of the culvert. Polyurethane foam (PUF) shall be used to plug the interior reach of the gap. PUF application shall be in accordance with section 0254: Polyurethane Foam Shaft Closure. PUF can be injected through holes drilled in the culvert every three feet to reach inaccessible areas. Worker area shall be adequately ventilated during

PUF installation. Unclassified fill shall be used to fill the exterior reach of the gap. Earthen backfill shall extend a minimum of 4 feet in by the brow. Backfill shall be placed by hand and tamped. Backfill out by the brow may be placed by machine and shall be placed in 12-inch lifts and compacted until reaching the top of the pipe. The area around the culvert and headwall shall be backfilled to blend with the adjacent slopes. Final grade shall provide positive drainage away from the adit.

- H. Upon Completion, the area shall be cleared of all construction materials, formwork, and construction-generated trash and debris. The site shall be left in a clean and finished appearance.
- I. Variations in the generic design or custom fitting may be required to accommodate site-specific conditions. Section 0300: Specific Site Requirements may specify alternate materials, dimensions, or design modifications for specific mine openings.

PART 4 - MEASUREMENT AND PAYMENT

4.01 BASIS OF PAYMENT

Basis of payment for the WORK will be on the BID PRICE per opening for completion of all the WORK as described in this Section. Breakdown of the WORK into unit prices for individual mine openings shown in the Bid Schedule will be used in determining partial payment or adjustment of the total BID PRICE for this Section as the WORK progresses.

4.02 MEASUREMENT

Measurement for mine closures will be on the BID PRICE per mine opening. The BID PRICE shall include all costs for labor, materials, equipment and all other items necessary for completion of the work as described in this section. Measurement will be based on and compared to the dimensions and quantities identified on the bid sheets, these Specifications and Drawings. The OWNER will request intermediate measurements to determine progress of the WORK.

4.03 PAYMENT

- A. Payment for mine closures will be for each mine site at the BID PRICE. Payment will only be for those closures which are complete, accepted, and approved by the OWNER. No partial payments will be made for individual mine openings.
- B. Payment at the UNIT PRICE for additional quantities will be made for mine closures when final quantities are greater than 15 percent in excess of the estimated quantities shown on the bid sheet for a given mine site. Such unit price payment will require proof of additional quantities provided by the CONTRACTOR and approval of the OWNER, and shall be full compensation for the approved additional grate quantity. Reduction of payment for lesser quantities of installed grate will also be made by the OWNER for quantities greater than 15 percent below the estimated quantity shown on the bid sheet for a given mine. Such UNIT PRICE adjustment will require approval of the OWNER and will be full compensation for approved additional or reduced mine closure quantities.

END OF SECTION 0253

0254 Polyurethane Foam Mine Closures

PART 1 - GENERAL

1.01 DESCRIPTION

The polyurethane foam (PUF) closure of adits consists of installing a bulkhead form, installing PUF to specifications, and backfilling over the PUF with random fill. In shafts, the closure work consists of installing a bottom form, installing PUF to specifications, installing drainage material, topping the PUF with a layer of concrete, and backfilling over the PUF to the specified level with random fill. For shafts, one ventilation/drainage pipe is required. Refer to the drawings for construction details.

1.02 SUBMITTALS

CONTRACTOR shall submit *with the bid proposal* the proposed construction procedures, including a description of the form materials to be used and the foam application equipment or method.

1.03 RELATED WORK

- A. Section 0250: Mine Closures
- B. Section 0251: Cast-In-Place Concrete
- C. Section 0252: Concrete Reinforcement
- D. Section 0300: Specific Site Requirements

PART 2 - PRODUCTS

MATERIALS

A. FORMWORK

1. The forms and cross members may consist of any commonly available building materials capable of sustaining the initial lift of two to four feet of PUF. Examples of acceptable forms and cross members include but are not limited to, the following:

CROSS-MEMBER & BOTTOM FORM

Rebar & Plywood
2x4s & Cardboard or Chicken Wire
Dowels & Paneling
Cardboard Tubes & Carpeting
Blocks of PUF (generated onsite)
Waterbed Mattresses (inflated remotely in the shaft with a hose and air compressor)

2. Any combination of the above noted materials that achieves the required performance will be acceptable. Alternate bottom forms will be acceptable upon approval by the OWNER.
3. Any breach in the bottom form caused by vandals or rock fall is required to be repaired before the arrival of the PUF applicators to the site. The CONTRACTOR is responsible for the integrity of the bottom form, and the loss of any polyurethane should it fail.

B. POLYURETHANE FOAM (PUF)

PUF is required to have a minimum installed density of 1.85 pounds per cubic foot (pcf). PUF characteristics shall conform to the minimum following standards:

PUF CHARACTERISTIC	STANDARD	SPECIFIED IN
Density	1.85 pcf, nominal	
Closed cell content	90%	ASTM D-2856
Compressive strength	25 psi	ASTM D-1621
Water absorption	1% by volume	ASTM D-2127
Exothermic Reaction Rate	Low	
Fire Resistance	Low	ASTM D-1692

Polyurethane foam used may not contain any CFC's (chlorinated fluorocarbons).

C. PROPORTIONING UNIT

1. The proportioning unit shall be capable of attaining a minimum temperature of 125°F. The proportioning unit shall be Gusmer Model H-11 or equivalent. For remote sites, or with approval of the OWNER, smaller capacity proportioners will be acceptable. In this event, the proportioner shall be the Gusmer FF, or equivalent.
2. Minimum heated hose length from proportioner to gun shall be 80 feet. The hose shall maintain or increase component temperature from the proportioner. Longer heated hose lengths may be required depending upon distance from the proportioning unit to the reclamation site.

D. APPLICATION GUN

The application gun shall be capable of mixing plural components in the proper ratio at the minimum acceptable output of four pounds per minute. The gun shall be a Gusmer AR mechanically self-cleaning design, or equivalent.

E. PREPACKAGED, PRE-PROPORTIONED PUF KITS

PUF products consisting of factory prepared kits that are designed to combine and dispense pre-measured quantities of components in the proper ratios may be used in place of an onsite proportioning unit and application gun, with the approval of OWNER. One such product is the foam closure bag manufactured by Foam Concepts Inc. (see Part 2.01.J below). PUF kits shall be used according to the manufacturer's specifications.

F. CEMENT PLUG

Concrete for the cement plug shall have a minimum compressive strength of 3,000 psi in 28 days. The concrete shall be proportioned in accordance with ACI 211. The type of cement used shall be Portland, Type II (ASTM C150). Air entrainment shall be furnished in all concrete. Air content shall be 5%± 1%. Water/cement (W/C) ratio is approximately 0.49 with minimum cement content of 564 lbs/CY. Concrete mixed at the jobsite shall be in accordance with ACI 301, chapter 7. Ready mix concrete shall be in accordance with ASTM C94.

G. FILTER CLOTH

The filter cloth, either woven or non-woven at the CONTRACTOR's option, shall have a minimum thickness of 15 mil in accordance with ASTM D-1777 and a minimum permeability of 10^{-2} cm/sec, such as Fibertex 150® manufactured by Crown Zellerbach or equivalent approved by OWNER. Prior to installation, the CONTRACTOR shall provide the OWNER with documentation that the filter cloth furnished meets the chemical, physical and manufacturing requirements of this Section.

H. VENTILATION/DRAIN PIPE

The ventilation/drain pipe shall consist of 2-inch diameter steel pipe.

I. RANDOM FILL MATERIAL

Random fill material shall consist of native, on-site soils and sandstone rock. The types of miscellaneous fill material to be used shall be approved by the OWNER prior to initiating the work.

J. SUPPLIERS OF PUF

Potential suppliers of polyurethane foam (PUF) are:

Foam Concepts, Inc.
P.O. Box 323
Aurora, Minnesota 55705
(888) 744-7584
(218) 229-3520
E-mail: info@foam-concepts.com
Website: www.foam-concepts.com

Progressive Marketing Group
1906 Highway 71 North
P.O. Box 860
Okoboji, Iowa 51355
(712) 332-9013
(800) 373-2593
(712) 332-9653 FAX
(800) 398-2762 FAX
(800) 806-1171 Dennis Gustafson
E-mail: pmgroup@rconnect.com
Vendor of Equipmentless Foam Sealant™

Section 0254

Utah Foam Products
Ernest Wilson Co.
3609 South 700 West
Salt Lake City, Utah 84119
Contact: Dennis Beckstead
(801) 269-0600 Utah Foam Products
(801) 265-9444 Ernest Wilson Co.
(801) 269-0620 FAX
E-mail: info@utahfoam.com
UFP is a supplier of raw materials. EWC is the contracting arm of the company.

Ron Walker
Azco Construction
2055 West US Highway 50 East
Penrose, Colorado 81240-9575
(719) 372-6872
General contractor with PUF equipment

A Urethane Service and Supply
2200 West 2300 South
West Valley City, Utah 84119
(801) 974-0995
(801) 974-3058 FAX
E-mail: urethane@qwest.net
Roofing contractor

T&W Wilson Spray Urethane
7200 South 2700 West
West Jordan, Utah 84084
Contact: Terry Wilson
(801) 566-1020
(801) 566-6620 FAX
Roofing contractor

Mine Seal, LLC
P.O. Box 231329
Las Vegas, NV 89123
(888) 732-5783
(888) 531-6883 FAX
Mine Closure Consulting Firm
www.mine-seal.com

Most roofing contractors that apply PUF roofing should be capable of providing the appropriate product for mine closure use.

These names are provided for the convenience of bidders. Other vendors may exist. The Utah Abandoned Mine Reclamation Program does not endorse or warrant the reliability or product of any of these vendors.

PART 3 - SAFETY

3.01 MATERIALS

- A. Materials shall be stored per the manufacturer's specifications. All safety precautions outlined by the Polyurethane Division of the Society of Plastics Industries, NFPA, OSHA, EPA and the

manufacturer's Material Safety Data Sheets (MSDS) shall be observed. MSDS and technical data sheets shall be on-site and available at all times.

- B. There shall be no welding, smoking or open flame within 100 feet of PUF application. A minimum 15-pound, class ABC fire extinguisher must be on site at the mine opening where the PUF is being applied during foam application.

C. Oxygen Content of Working Area

1. A flame safety lamp or oxygen meter must be used to test air before and during installation of the bottom forms. The flame safety lamp or oxygen meter will be supplied by the CONTRACTOR and operated only by the Certified Person. Refer to Section 0250, Part 1.04.
2. Oxygen Meter. The oxygen meter shall be a National Mine Service (NMS) OX231 oxygen meter or equivalent. The oxygen meter shall continuously monitor oxygen levels and have an audible warning. If the oxygen content falls below 19%, all personnel must withdraw from the working area in the mine until the oxygen content increases to safe levels.
3. Flame Safety Lamp. The flame safety lamp shall be lowered to the intended level of the bottom form from the surface. If the flame safety lamp is extinguished upon withdrawal then the mine may not be entered until the oxygen level increases. The flame safety lamp shall accompany the bottom form installer during the time in the mine. If the quality and/or intensity of the flame decreases, then the installer must withdraw from the working area until the oxygen content increases.
4. Any remedy for increasing oxygen content of the working area and/or providing ventilation from the surface must be determined in consultation with the OWNER and the Certified Person.

3.02 HANDLING

PUF shall be applied by workers wearing organic respirator masks and safety glasses or goggles. State or Federal regulations requiring additional equipment shall supersede these specifications.

3.03 TRANSPORT

The CONTRACTOR shall follow all applicable State and local regulations for transport and use of PUF and chemicals required for cleanup. The CONTRACTOR shall also obtain any necessary permits for transportation. The CONTRACTOR shall be aware of agencies and jurisdictions requiring notification in the event of a component leak or spill. In the event of a leak or spill, the CONTRACTOR shall notify the appropriate parties.

PART 4 - EXECUTION

4.01 SHAFT CLOSURE INSTALLATION

A. CLEARING DEBRIS

Clear debris other than fixed, attached or permanent structures from the shaft before PUF is installed *as directed by the OWNER*. Historic structural features shall be preserved and maintained. Any historic debris removed shall be placed neatly to the side of the opening.

B. FORMWORK

1. The formwork shall be installed below the surface of the shaft at the bottom of the foam depth level. The depth of foam required to plug a shaft shall be determined by the following formulas, where "a" is the smaller dimension of a rectangular shaft opening and "b" is the larger dimension, with both "a" and "b" measured in feet:
 - a. for shafts where $a = b$, the depth of foam should be: $2a$.
 - b. for shafts where $a < b < 3a$, the depth of foam should be: $2a + \frac{1}{2}(b-a)$
 - c. for shafts where $b > 3a$, the depth of foam should be: $3a$.
2. Cross-member supports may be placed at an angle not more than 20 degrees from horizontal as long as both ends are seated in the shaft. The bottom form shall be set over the cross-members.
3. Bottom forms shall be completed prior to application of any polyurethane foam. The installed depth to bottom form shall be indicated on the as-built drawings for polyurethane foam closures. Any breach in the bottom form caused by vandals or rock fall shall be repaired prior to arrival of PUF applicators at that site. The CONTRACTOR is responsible for the integrity of the bottom form, and the loss of any polyurethane should it fail.

C. VENTILATION/DRAIN PIPE

1. The ventilation/drain pipe shall be placed over a portion of the bottom form unobstructed by cross-members. The ventilation/drain pipe shall be open to the shaft after installation of the foam. The ventilation/drain pipe shall be supported by a tripod or other load-bearing device such that the load is not placed on the bottom form.
2. The 2-inch steel ventilation/drain pipe shall be installed into the approximate center of the PUF installation and shall extend vertically to the lines and grades as shown on the Standard Drawings.
3. The steel ventilation/drain pipe shall extend up through the entire PUF and concrete plug installation to provide ventilation and a watercourse through the entire structure. The 2-inch steel pipe shall be cut off level at the top of the concrete plug.

D. POLYURETHANE FOAM (PUF)

1. PUF shall be applied in lifts with a maximum rise of 1.5 feet. Installed PUF lifts shall pass through the tack free stage before applying the next lift. At no time shall sprayed or poured PUF cut into rising foam. The PUF shall be applied in such a manner that the entire void is filled, and that shadow zones or voids are not created during PUF application, and does not raise the temperature to unsafe levels. At the discretion of the OWNER, thermocouples may be used to monitor exothermic generation. PUF application shall cease if heating or off-ratio foam is observed. The CONTRACTOR shall remedy off-ratio foam and demonstrate proper quality PUF to the OWNER before application resumes. See Part 5 below for characteristics of off-ratio foam.
2. The surface of the void to be filled shall be as free as possible of grease and standing water. PUF shall not be applied to surfaces with running water. Remedial action for such situations shall be specified by the OWNER. Polyurethane foam shall not be applied directly to a debris plug, but must be applied to a bottom form of known physical and chemical

properties. PUF shall not be applied during rain unless the foam is protected from interaction with water by a physical barrier.

3. If off-ratio PUF is observed, the applicator must stop, correct the imbalance and continue application with the proper ratio PUF. Correction and determination of the foam ratio shall be done on a plastic sheet away from the work area. Any lift of off-ratio PUF comprising over two percent (2%) of the intended PUF column height shall be removed. An amount of off-ratio PUF less than two percent (2%) of the specified volume may remain if allowed to cool, and if the outer perimeter of off-ratio foam is removed.
4. The CONTRACTOR shall be responsible for any lost or damaged equipment. In addition, damages or claims arising from PUF overspray shall be the responsibility of the CONTRACTOR. Under no circumstances shall foreign material be placed in the PUF unless specifically authorized by the OWNER. Non-PUF materials must be non-toxic, non-hazardous and not compromise the strength or water saturation characteristics of the PUF.
5. Upon reaching the specified grade as shown on the Standard Drawings, the CONTRACTOR shall clean up PUF operations and wait a minimum of one hour before initiating construction of the concrete plug.

E. CONCRETE PLUG

1. The concrete plug shall be placed directly on top of the polyurethane foam (PUF) as shown on the Standard Drawings and be one foot thick, covering the entire width of the opening. There shall be complete contact along the entire perimeter of the plug with the opening walls.
2. The CONTRACTOR shall determine the means of concrete plug placement and submit it to the OWNER for approval prior to the start of construction.
3. The top of the concrete plug shall be reasonably smooth and completed to provide drainage to the 2-inch steel ventilation/drain pipe.
4. Placement of backfill on top of the concrete plug will not be allowed until the structure has cured for a minimum of 24 hours.

F. FILTER CLOTH

1. The geotextile filter cloth shall be placed in all required structures in a manner acceptable to the OWNER.
2. Fabric shall be rejected at the time of installation if it has defects, rips, holes, flaws, deterioration or damage incurred during manufacture, transportation or storage. Fabric damaged before or during the installation shall be replaced at the CONTRACTOR's expense.
3. The fabric shall be placed without stretching and shall lie smoothly in contact with the concrete plug surface. Each strip shall be continuous in width with no joints. The fabric shall be placed with overlapping seams perpendicular to the long axis of the opening. When end overlapping of strips is necessary, the joints shall be overlapped a minimum of two feet. End overlaps shall be made in the direction of the long axis of the opening. The work shall be scheduled so that not more than one day elapses between the placement of the fabric and the time it is covered with the specified material.

Section 0254

4. The filter cloth shall be installed over the top of the concrete plug and 2-inch PVC ventilation/drain pipe so that free drainage is possible.

G. RANDOM FILL MATERIAL

1. Random fill material shall consist of on-site, native materials as approved by the OWNER. Fill material shall be placed to the thickness shown on the Standard Drawings.
2. Materials for random fill material shall be placed by methods to produce a uniform mass. The first two-foot lift shall be placed by hand or bucket to lower the velocity of impact against the concrete plug. The final surface of the backfilled opening shall be mounded a minimum of one foot above the original ground. Care should be taken not to plug the drain pipe with fill material.

H. SITE CLEAN-UP

All construction-generated trash and debris, such as scrap materials and spilled PUF or concrete, shall be cleaned up and removed. CONTRACTOR shall avoid spraying foam at undesignated targets. Improperly applied PUF and overspray shall be removed.

I. MODIFIED PUF CLOSURE (TYPE B— RECESSED SURFACED)

The standard PUF closure design is modified for shafts designated as historically significant. For these openings, the top surface of the random fill material shall be recessed inside the shaft opening to within three feet of the adjacent ground surface. The minimum thickness of the random fill layer shall be two feet. The positions of the bottom form, PUF, and concrete are lowered accordingly. The intent of the recessed fill is to maintain the original appearance of the opening while still eliminating a serious fall hazard. Shafts designated as historically significant and requiring a recessed closure are listed in Section 0300: Specific Site Requirements and/or the appendices.

4.02 ADIT PUF CLOSURE INSTALLATION

A. CLEARING DEBRIS

Clear debris other than fixed, attached, or permanent structures from the adit before PUF is installed *as directed by the OWNER*. Historic structural features shall be preserved and maintained. Any historic debris removed shall be placed neatly to the side of the opening.

B. FORMWORK

1. The formwork shall be installed in by the brow of the adit to allow for a minimum foam thickness of two feet.
2. Cross-member supports may be placed at an angle not more than 20 degrees from vertical as long as both ends are seated in the adit.
3. Forms shall be completed prior to application of any polyurethane foam. The installed depth to form shall be indicated on the as-built drawing for polyurethane foam closures. Any breach in the form caused by vandals or rock fall shall be repaired prior to arrival of PUF applicators at that site. The CONTRACTOR is responsible for the integrity of the form, and the loss of any polyurethane should it fail.

C. VENTILATION/DRAIN PIPE

Designated openings shall require the installation of a drainage pipe. The drainpipe shall be located near the base of the closure within 15 inches of the intersection of the floor material in the approximate center of the closure or near a low spot along the base. The drainpipe shall extend through the base of the closure. The drainpipe shall protrude a minimum of 12 inches on either side of the seal and shall be made from 6-inch nominal diameter steel pipe. The inside end of the pipe shall be firmly supported by block or natural stone. Both the inside and outside ends of the pipe shall be clear of any obstructions which would impair or restrict flow. Both ends of the pipe shall be covered with a protective screen mesh. Gravel shall be installed over the ends of the pipes to protect the pipe from roof falls and plugging. Gravel shall form a drain and cover the top of the pipe with a minimum of 8 inches of material. The gravel drain shall be no less than 18 inches wide and shall extend to and from the end of the pipes a minimum of two feet. Gravel used in the drain channels shall be selected material ranging from 3/4 to 6 inch in size. CONTRACTOR shall extend a drainage channel away from the bulkhead if it is situated such that water could impound near the base.

D. POLYURETHANE FOAM (PUF)

1. PUF shall be applied in lifts with a maximum rise of 1.5 feet. Installed PUF lifts shall pass through the tack-free stage before applying the next lift. At no time shall sprayed or poured PUF cut into rising foam. The PUF shall be applied in such a manner that the entire void is filled, and that shadow zones or voids are not created during PUF application, and does not raise the temperature to unsafe levels. At the discretion of the OWNER, thermocouples may be used to monitor exothermic generation. PUF application shall cease if heating or off-ratio foam is observed. The CONTRACTOR shall remedy off-ratio foam and demonstrate proper quality PUF to the OWNER before application resumes. See Part 5 below for characteristics of off-ratio foam.
2. The surface of the void to be filled shall be as free as possible of grease and standing water. PUF shall not be applied to surfaces with running water. Remedial action for such situations shall be specified by the OWNER. Polyurethane foam shall not be applied directly to a debris plug, but must be applied to a form of known physical and chemical properties. PUF shall not be applied during rain unless the foam is protected from interaction with water by a physical barrier.
3. If off-ratio PUF is observed, the applicator must stop, correct the imbalance, and continue application with the proper ratio PUF. Correction and determination of the foam ratio shall be done on a plastic sheet away from the work area. Any lift of off-ratio PUF comprising over two percent (2%) of the intended PUF column height shall be removed. An amount of off-ratio PUF less than two percent (2%) of the specified volume may remain if allowed to cool, and if the outer perimeter of off-ratio foam is removed.
4. The CONTRACTOR shall be responsible for any lost or damaged equipment. In addition, damages or claims arising from PUF overspray shall be the responsibility of the CONTRACTOR. Under no circumstances shall foreign material be placed in the PUF unless specifically authorized by the OWNER. Non-PUF materials must be non-toxic, non-hazardous and not compromise the strength or water saturation characteristics of the PUF.
5. Upon reaching the specified grade as shown on the Standard Drawing, the CONTRACTOR shall clean up PUF operations and wait a minimum of one hour before initiating construction of the concrete plug.

E. RANDOM FILL MATERIAL

1. Random fill material shall consist of on-site, native materials as approved by the OWNER. Fill material shall be placed to a minimum thickness of three feet.
2. Materials for random fill material shall be placed by methods to produce a uniform mass. The material may be placed by hand or equipment. The final surface of the backfilled opening shall be graded to blend with the surrounding contour.

F. SITE CLEAN-UP

All construction-generated trash and debris, such as scrap materials and spilled PUF shall be cleaned up and removed. CONTRACTOR shall avoid spraying foam at undesignated targets. Improperly applied PUF and overspray shall be removed.

PART 5 - FIELD QUALITY CONTROL

INSPECTIONS

- A. Periodic checks of the quality of PUF applied shall be made by the OWNER. The main check on quality will be visual. Acceptable PUF shall be tan-white to buff in color with no vesicles and a smooth to coarse orange peel surface. Any one of the following conditions shall cause PUF application to cease, and efforts to correct the off-ratio condition begin.

CONDITION	POSSIBLE CAUSE
Dark PUF Color Smooth and Glassy Friable or Brittle PUF Improper Density	Excess A Component
Light to White in Color Bad Cell Structure Mottled Appearance Blowholes or Pinholes	Excess B Component
Slow rise Poor Cell Structure Frequent Equipment Clogging Slow Curing Bad Physical Properties	Bad Material

- B. At any time during PUF application, the OWNER may call for a density test. The applicator shall fill a container provided by the OWNER for this purpose, and the sample will be tested for density. The density of the sample shall be within eight percent (8%) of the nominal 2 pounds per cubic foot density, with a minimum installed density of 1.85 pounds per cubic foot. Density tests indicating PUF installed is not within the minimum specified density shall cause corrective action resulting in PUF within the acceptable nominal range, less deviation due to barometric pressure changes from STP (Standard Temperature and Pressure).
- C. Density tests of PUF shall be conducted at no cost to the OWNER. At the discretion of the OWNER, density tests showing PUF in the acceptable range may be taken in the center of the cavity to which PUF is being applied. A sampling box constructed of sheet aluminum and lined with polyethylene may be lowered into the cavity to take a representative sample of PUF just above the level of installed polyurethane.

PART 6 - MEASUREMENT AND PAYMENT

6.01 SPECIAL CONSIDERATIONS

- A. The CONTRACTOR's attention is specifically directed to the following.
- B. The final quantities for the major categorizations of materials may vary from the quantities shown on the site-specific summary sheets in Appendix B**. The quantities estimated are based on information gathered and interpreted from surface investigations.
- C. The boundaries of classified materials, along with the volumes are estimates and intended to serve as a guide in outlining the scope of work and evaluating the bids.

6.02 QUANTITY MEASUREMENTS

- A. Polyurethane foam closures will be paid for at the contract Bid Price per each closure completed. Payment at the Bid Price shall be full compensation for furnishing, placing all materials, including all labor, equipment, tool, and incidentals necessary to complete closure installation in accordance with the Standard Drawings and Specifications.
- B. Installation of PUF, fabrication of the concrete plug, placement of filter cloth and ventilation/drain pipes, backfill, revegetation, and cleanup will not be measured for direct payment but will be considered subsidiary to PUF closures.
- C. No payment shall be made for off-ratio PUF.

END OF SECTION 0254

0290 Revegetation

PART 1 - GENERAL

1.01 WORK INCLUDED

The WORK consists of revegetation of the disturbed areas, including areas disturbed by the WORK. Revegetation shall include:

- A. Site preparation
- B. Seedbed preparation
- C. Topsoil placement as required
- D. Seeding
- E. Mulching
- F. Erosion control netting
- G. Seedling and cutting planting

1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the bid proposal* the names of one seed supplier, and alternate, to be used for the seed mixtures required by these specifications.
- B. CONTRACTOR shall submit *with the bid proposal* a written description indicating equipment to be used to perform the work required in this section.
- C. CONTRACTOR shall submit *during construction* empty container labels, tags, and receipts for mulch material and seed for verification of materials being used.
- D. CONTRACTOR shall submit, if mulch is specified, *during construction and prior to applying mulch* the Phytosanitary Certificate required by the Utah Department of Agriculture.

1.03 RELATED WORK

- A. Section 0230: Access Improvement
- B. Section 0250: Mine Closures
- C. Section 0300: Specific Site Requirements

1.04 DELIVERY, STORAGE, AND HANDLING

- A. CONTRACTOR shall deliver seed in original containers showing analysis of seed mixture, percentage of pure live seed (PLS), year of production, net weight, date of packaging and location of packaging. Seed must be stored under dark, cool, and dry conditions. Damaged packages are not acceptable.
- B. Erosion control netting shall be stored out of direct sunlight.

PART 2 - PRODUCTS

2.01 PLANT MATERIALS

- A. A combination of plant materials that may include seed, seedlings, containerized stock, and cuttings shall be used in revegetation. The use of the plant materials shall be in accordance with Section 0300: Specific Site Requirements and as shown on the Drawings.
- B. CONTRACTOR shall make a concerted effort to obtain all components of the plant materials

Section 0290

mixture. Seed and nursery sources may require greater than six weeks notice to obtain specific species. More than one source may be required to furnish all seed or plant varieties. If all sources have been exhausted, or if available seed or stock of a given species is of unacceptable quality, that species may be deleted or another species substituted. Any changes in the seed mixture shall require the written approval of the OWNER prior to execution of the contract.

- C. CONTRACTOR must submit name of company and alternate that will supply seed, see Section 1.02. A.

2.02 SEED

- A. The species composition and planting rates of the seed mixtures to be used are specified in Appendix C. Unless specified otherwise, seeding rates given are for broadcast seeding.
- B. All seed mixes shall be fresh, clean, new crop seed.

2.03 SEEDLINGS

- A. Seedlings include containerized stock, tubelings, and bare root stock obtained from nurseries. The species composition and planting rates of the seedlings to be used are specified in Appendix C.
- B. Seedlings must be healthy and vigorous and not desiccated at time of planting. OWNER reserves the right to refuse payment for decadent plants.
- C. Bare root stock shall have roots that are not withered, dry, or partially dead due to improper transport and/or storage by the CONTRACTOR. All bare root stock shall be stored and delivered with roots in a damp medium.

2.04 DORMANT PLANT MATERIALS

- A. Dormant plant materials will be used for riparian area revegetation. Dormant plant materials include cuttings of live logs, twigs, or whips from wild tree stock.
- B. CONTRACTOR shall obtain dormant materials only from areas identified by the OWNER, and the OWNER shall approve and accept or reject the individual material cut. CONTRACTOR shall cut plant materials just prior to the breaking of dormancy, usually late March to early April. As dormancy is partially a function of temperature, cutting and planting of the materials may be required at a moment's notice (dependent on spring weather) to ensure material is planted while still in a dormant state.
- C. CONTRACTOR shall be responsible for all rooting hormones, sealants, paints, and shock-reducing vitamins.
- D. All dormant vegetative plant materials shall be alive and dormant and not dried or otherwise damaged. Payment will not be made for substandard plant material, as determined by OWNER.
- E. Dormant plant materials shall consist of the following species planted at the indicated spacing, unless otherwise specified in Section 0300: Specific Site Requirements:

<u>Common Name</u>	<u>Scientific Name</u>	<u>Spacing</u>
Cottonwood	<i>Populus fremontii</i> (or) <i>Populus angustifolia</i>	1 every 20 feet

Endemic Willow

Salix spp.

2 rows on 3-foot centers - offset

2.05 MULCH

- A. Mulch, when required, shall consist of native hay or straw free of noxious weeds or any foreign material detrimental to plant life. *Alfalfa will not be permitted.*
- B. Mulch must meet the requirements of the Utah Noxious Weed Act (4-17-3, UCA; Regulation A700-04-09) and the Utah Phytosanitation Act. Mulch must be tested and found clean by an official Utah Department of Agriculture Inspector. CONTRACTOR shall contact the state inspector and arrange testing. Payment will not be made without certificate of inspection from Agricultural Inspector. Untested mulch may be used only with the prior written approval of the OWNER.
- C. Hay used as mulch may be old, but it shall be dry and not moldy.

2.06 EROSION CONTROL BLANKET

- A. Uniform, open weave, erosion control blanket which combines mat of seasoned wood excelsior of consistent thickness with photodegradable plastic mesh (AMXCO Curlex Blankets or equivalent) shall be used on slopes of 2h:1v or greater. The blanket shall be used in combination with straw mulch on sites where slope, soil texture, drainage pattern, or exposure will lead to excessive soil loss from erosion.
- B. Staples for installation of erosion control blanket shall be made of wire (diameter 0.091 inches or greater), U-shaped with 6-inch legs and 1-inch groin. Size and gauge of staples may vary with soil conditions.

2.07 TOPSOIL

- A. Topsoil shall be as defined in Section 0270: Site Grading/Earthwork.

PART 3 - EXECUTION**3.01 GENERAL**

- A. Areas to be revegetated are all those which have been disturbed during reclamation construction. Those areas shall include, but are not limited to, portal closure areas, subsidence areas, grading areas, access routes, staging areas, and other areas disturbed by CONTRACTOR in performing the WORK.
- B. CONTRACTOR shall take necessary precautions to avoid disturbance of surrounding native areas and will not travel on previously undisturbed soil, unless directed by OWNER.
- C. When machinery is specified, all operations will be conducted along the contour. On level sites (area permitting) all equipment operations shall be conducted perpendicular to the prevailing wind direction when wind erosion potential is considered to be high.

3.02 SITE PREPARATION

- A. CONTRACTOR shall remove and bury foreign materials and debris collected during topsoil spreading. Tree stumps and large shrubs may also be removed, buried, or stockpiled for

Section 0290

distribution on the site following top-soiling, as specified in Section 0300 or as directed by OWNER.

- B. Areas that are not fill areas with imported topsoil shall be chiseled or ripped to a depth of 12 inches. This particularly applies to areas that have soils compacted from construction activities and includes haul roads and site access roads. Ripping shall be repeated until the compacted area is loose and friable.
- C. Areas of fill to be covered with imported topsoil shall be chiseled or ripped to a depth of 12 inches. Ripping of fill materials shall be completed by a bulldozer equipped with single or a twin set of ripper shanks. Ripping shall be done on 4-foot centers to a depth of 12 inches and shall follow final grading and precede seedbed material (topsoil) application. Ripping shall be completed at a speed which maximizes ripper shank action and promotes soil material disruption to the specified depth. Ripping shall be repeated until the compacted area is loose and friable.
- D. Topsoil shall be placed on fill areas immediately following ripping to a minimum depth of 24 inches, or other minimum depth as specified in Sections 0270 or 0300, in all areas designated by the OWNER.

3.03 MULCHING

- A. All sites not designated for erosion control blanket shall be mulched unless otherwise specified by the OWNER in Section 0300: Specific Site Requirements.
- B. Mulching shall be performed AFTER topsoil is in place, and PRIOR to seeding. Mulch shall be spread by hand or mechanical blower, in an even manner, at a rate of 2,000 pounds per acre over the site to be mulched. Mulch application shall be initiated at the top of the slope, working downhill, where possible.
- C. Mulch shall be crimped with hand tools where equipment cannot gain access or where soil surface roughness (see Part 3.05 below) is already adequate following topsoil distribution and further equipment activity would level the surface.

3.04 SEEDBED PREPARATION/SURFACE ROUGHENING

- A. AFTER topsoil placement and mulching, and PRIOR to seeding, the ground surface shall be roughened and gouged to create hummocks and depressions with up to 12 inches of relief. This relief will reduce ground surface wind disturbance and create water catchment basins. Roughening can be achieved by gouging with a backhoe or excavator bucket. Surface roughness can also be created during topsoil distribution by leaving intact the mounds and windrows from each dump truck or loader bucket dump. Furrows, basins, and ridges created by the roughening should run predominantly along the contour to minimize runoff. The roughening process should incorporate the mulch into the top of the soil and some will be buried; however, care should be taken to minimize the mulch buried at depth.
- B. Boulders, both large and small, may be left on site after topsoiling and prior to seeding, either singly or in groupings to blend with the natural surroundings, as directed by OWNER. OWNER may require that additional boulders be placed on site prior to seeding to enhance visual variation and provide wildlife habitat.
- C. Seedbed preparation shall be considered to be complete when the soil surface is completely roughened.

- D. Unless the soil is severely compacted, seedbed preparation shall not be required for discontinuous, isolated areas of disturbance less than 0.05 acres (approximately 2500 square feet or 50 feet by 50 feet), such as areas around mine portal closures.

3.05 SEEDING

- A. All seeding shall be broadcasting as directed by OWNER. When broadcast seeding, passes shall be made over the site to be seeded such that even distribution of seed shall be obtained. Broadcast seeding shall take place immediately following the completion of final seedbed preparation. Broadcast seeding shall not be conducted when wind velocities would prohibit even seed distribution. Broadcast seeding shall be followed by hand raking, manual use of a drag chain, or sweeping with sturdy tree or shrub branches to cover seed. This shall be done over the entire site but will not be so extreme as to reduce the extent of soil relief.
- B. Broadcast seeding of large areas shall be done using hand-operated "cyclone-type" mechanical seeders. All seeding equipment used shall be equipped with a metering device and set to the appropriate seeding rate.
- C. Broadcast seeding of small areas of disturbance less than 0.05 acres (approximately 2500 square feet or 50' x 50') may be done by hand scattering. Raking of small areas is not necessary if there is sufficient surface roughness to ensure that seeds will fall into crevices and other micro-topographic depressions so that weather and gravity will cause them to be covered and stay in place.
- D. After completion of the broadcast seeding and seed covering, organic debris such as logs, tree stumps, and grubbed vegetation shall be randomly redistributed across the sites. This shall be done at the OWNER's direction for the purpose of creating visual variation and production of wildlife habitat. Care shall be exhibited to avoid leveling the soil surface.

3.06 SEEDLING PLANTING

- A. Planting of bare-root and/or containerized plant seedling stock, when required, shall occur following ground surface roughening. No seedling planting shall be attempted in frozen seedbed material. Seedling spacing shall be as stated in the Section 0300 revegetation plans. Seedling stock shall be delivered to the planting site as close to the time of planting as possible.
- B. At each individual planting site, a circular area (planting circle) shall be cleared of mulch materials or inhibiting debris. The size of the circle shall be approximately 12 inches in diameter. The receiving hole shall then be dug with the depth of the hole extending 2 to 4 inches deeper than necessary for planting. The hole shall be of sufficient size to allow positioning the seedling and tamping the backfill. After the hole has been formed, it shall be partially backfilled with loose soil to allow planting at the proper depth. The seedling shall then be placed in the hole and the hole $\frac{1}{2}$ backfilled. The hole shall then be filled with water and the remainder of the seedbed material backfilled into the hole as rapidly as possible without displacing water from the hole. The backfill shall be firmly tamped around the seedling. Planting depth shall not exceed the depth at which the seedling was grown in the container.
- C. A basin, which slopes gently from the outside of the planting circle to the seedling stem, shall be formed in the soil to aid in water catchment. The basin shall be mulched with straw (or the mulch replaced when a seedling is planted into a mulched site) and the straw anchored with gravel and seedbed material. Planting holes may be dug by hand or with a power auger. Planting shall be completed randomly over the disturbed area in clumps, as specified in Section 0300.

3.07 WILLOW CUTTINGS

- A. Willow Cuttings shall be planted along the borders of water courses as designated in Section 0300: Specific Site Requirements. Cuttings shall be gathered and planted in the spring (April or May) of the year.
- B. Cuttings shall be collected from locally occurring, dormant plants free from disease. All cuttings shall be of stem material and be approximately two (2) to six (6) feet long. Stem material, 2 to 4 years old at the maximum, shall be considered acceptable for use. The basal cut shall be made at an angle immediately below a node. Cuttings shall be planted immediately after collection, keeping the cuttings moist throughout the process. Should storage be necessary, cuttings shall be placed in a plastic bag with a wet paper towel or cloth wrapped around the bases to prevent desiccation.
- C. To complete the planting procedure, the base end of the cutting shall be pushed into a prepared seedbed such that 1 to 2 feet of cutting remains above the seedbed surface. The base *must* be in contact with the water table. A metal bar may need to be pounded into the soil to develop a pathway for the willow cutting to follow. The base end shall be dipped into a solution of "Rootone F" prior to planting to aid in root formation.

3.08 DORMANT LOG PLANTING

- A. OWNER shall be responsible for locating and securing the necessary permits for obtaining dormant log materials. OWNER shall also identify and tag all materials to be cut, and be on site during the cutting process. CONTRACTOR shall be responsible for cutting, transporting, and handling dormant plant material; site preparation for planting; application of all rooting hormones, transplant shock reducers, paints, and sealers; and placing the plants into the ground at the locations specified in Section 0300.
- B. Dormant logs may be a mix of Narrowleaf Cottonwood, *Populus angustifolia*, and Fremont Cottonwood, *Populus fremontii*. All logs shall be alive and dormant, and not dried or otherwise damaged. All logs shall be between 2 and 6 inches in diameter at the base, and 6 to 18 feet in length. All dormant logs shall be cut at an angle at the base (rooting) end and flat at the top (vegetative) end. The bottom two feet of the log shall be scored with an ax to expose the cambium layer (see drawing). Side limbs will be removed from the logs and all exposed cuts including the top saw cut shall be sealed with an accepted tree paint.
- C. Holes for dormant logs shall be augured to a depth that reaches into the water table. Planting areas adjacent to streams and rivers may be composed entirely of river rock, or closely packed, competent rock. Auguring through this material into the water table may be extremely difficult. An auger with a chisel bit operating off of a power take off (PTO), some other drilling rig, or a backhoe with a narrow bucket may be necessary. Dormant logs shall be planted in holes that barely accommodate the diameter of the logs. If larger holes are necessary because of digging conditions, the excess volume shall be carefully backfilled under the direction of the OWNER. Dormant log spacing shall be as stated in Section 0300. Planting shall occur in the spring (March, April, or May) of the year.
- D. CONTRACTOR shall make every effort to minimize damage to vegetation and environmental disturbance at the tree source area. Unused or excess brush, branch trimmings, logs, etc. shall be disposed of properly. CONTRACTOR shall leave the site neat and in a condition acceptable to OWNER and the landowner.

3.09 EROSION CONTROL BLANKET

- A. The area to be covered shall be properly prepared and seeded prior to application of erosion control blanket. All roads and debris shall be removed prior to seeding and installation.
- B. Seeded slopes shall be covered with excelsior-type erosion control blanket where shown on the Drawings.
- C. CONTRACTOR shall roll blanket down over slopes without stretching or pulling and lay blanket smoothly on soil surface, burying and securing the top end of each section in a narrow (6-inch) trench. CONTRACTOR shall leave 12 inches overlap from top roll over bottom roll and four inches overlap over adjacent section. The blanket shall be placed with the netting on top and the fibers in contact with the soil over the entire area.
- D. The staples shall be installed per erosion control netting manufacturer's recommendations and spaced over the blanket on no less than 6-foot intervals. Outside edges and overlaps shall be at 36-inch intervals.
- E. CONTRACTOR shall lightly dress slopes (manually) with topsoil and cobbles to ensure close contact between blanket and soil.

PART 4 - MEASUREMENT AND PAYMENT

4.01 MEASUREMENT

- A. Measurement will be based on and compared to the quantities identified in the bid sheets, these Specifications and Drawings for each mine site. The OWNER will request intermediate measurements to determine progress of the WORK.
- B. Measurements by CONTRACTOR will be required for a given mine site for acres of revegetation and/or square yards of erosion control blanket. Such measurements will be used by the OWNER for comparison with the estimated quantities shown on the bid sheets.
- C. Should the CONTRACTOR estimate the quantity of materials to be greater than 15% more than the quantities shown in the Bid Schedule, a CHANGE ORDER must be negotiated with the OWNER for ADDITIONAL WORK prior to the CONTRACTOR undertaking ADDITIONAL WORK. Measurement for quantities shall be determined prior to the WORK.
- D. When the actual quantity of Revegetation performed as determined by measurement is greater than 15% less than the estimated quantity on the bid sheet, the OWNER will negotiate a reduction in the BID PRICE by the amount of variance using the UNIT PRICE. This adjustment shall be executed by a CHANGE ORDER.

4.02 PAYMENTS

- A. Payment for Revegetation will be for each mine site at the BID PRICE, as modified by any CHANGE ORDERS. No partial payments will be made.
- B. Payment at the UNIT PRICE for additional quantities of Revegetation will be made for quantities greater than 15 percent in excess of the estimated quantity shown on the bid sheet for a given mine site. Reduction of payment for lesser quantities of Revegetation will also be made by the OWNER for quantities greater than 15% below the estimated quantity shown on the bid sheet for a given mine. Such unit price payment will require approval of the OWNER, and will be full

Section 0290

compensation for additional or reduced revegetation and/or erosion control blanket.

C. Payment will not be made without:

1. Seed: seed testing certification, certification to be submitted with invoice, and
2. Mulch [only if specified]: Phytosanitary Certificate for certification of compliance with the Utah Noxious Weed Act. Certification shall be submitted with invoice.

END OF SECTION 0290

0300 SPECIFIC SITE REQUIREMENTS

PART 1 - GENERAL

1.01 WORK INCLUDED

- A. This section describes the location, the features present, and the WORK to be performed at the Ophir Canyon Project located in Tooele County, Utah. The items of the WORK shall be performed according to the appropriate sections of these specifications.
- B. It is the intent of these Specifications that the site-specific scope of WORK is as described in this Section. The General Technical Specifications, Sections 0200 through 0290, outline WORK broadly applicable to all abandoned mine reclamation situations and that may not be required at each mine site in this project. Where there is a conflict between Section 0300 and the General Technical Specifications (0200's), Section 0300 shall govern.
- C. The access, site description, and specific requirements for each closure method are described in this Section. Details and dimensions are shown on the drawings in Appendix E. CONTRACTOR shall be aware that the dimensions on the Drawings are shown as typical. CONTRACTOR shall also be aware that minimum or maximum dimensions on the Drawings or given in the Specifications are specific and are to be adhered to unless the OWNER approves changes in writing. The quantities presented in the specific site sections should be considered an estimate with a tolerance of plus or minus 15 percent. CONTRACTOR shall visit each site and determine the quantities and amounts required in performing the WORK as intended in these Specifications and on the Drawings.

1.02 LOCATION AND DESCRIPTION

- A. The Ophir Canyon Project is located in the Oquirrh Mountains approximately 19 highway miles south of Tooele, Tooele County, Utah. General reclamation area boundaries of the Ophir Canyon Project are shown on the attached location maps (see Appendix F, Sheet 1) and are described in this section.
- B. The Ophir Canyon Project area consists of approximately 143 identified abandoned mine openings or other mining features. The mine openings consist of adits, inclines, vertical shafts, exposed stopes, prospect pits, trenches, and subsidence holes. The openings occur in a wide range of sizes, configurations, and conditions.
- C. Access: To reach the Ophir Canyon Project area from Tooele (junction of Main and Vine streets). Drive south 11.8 miles on Highway 36 (through Stockton, UT), to the junction of Highway 36 with Highway 73. Turn left (east) on Highway 73 and drive 4.6 miles to a paved road named Ophir Town Site Road. Turn left (east) and proceed toward Ophir Canyon. There are seven (7) site groups with the access to each described from the Ophir Town Site Road turnoff in Parts 1.04 and 1.05.
- D. The formal project boundary takes in the following sections, although mines occur in only a portion of this area:
 - T5S, R3W, Sections: 29, 30, 31, & 32
 - T5S, R4W, Sections: 5, 6, 7, 8, S1/2 15, S1/2 16, 21, 22, 25, 26, 27, 28, & 36
 - T4S, R4W, Sections: S1/2 31, S1/2 32
- E. The Ophir Canyon Project is mapped on the Stockton, Lowe Peak, Ophir, and Mercur USGS 7.5 minute quadrangles.

USGS 7.5 minute quad index:

Stockton	Lowe Peak
Ophir	Mercur

1.03 MINE OPENING LOCATIONS AND DESCRIPTIONS

- A. The Ophir Canyon Project area consists of approximately 143 identified abandoned mine openings or other mining features. The mine openings consist of adits, inclines, vertical shafts, exposed stopes, prospect pits, trenches, and subsidence holes. The openings occur in a wide range of sizes, configurations, and conditions.
- B. Locating Sites: Many of the project sites are very difficult to find, even with maps. There are few good landmarks in the foothills and the pinyon-juniper woodland and oak scrub limit visibility. Natural talus slopes that resemble mine dumps are commonplace. Recreational ATV activity has created a complex and confusing network of unmapped roads and trails that often go nowhere in particular. Flagging tape from dozens of different users is so widespread in the area as to be useless for navigation. For this reason, OWNER recommends that CONTRACTOR have access to Global Positioning Satellite (GPS) equipment to supplement the maps when locating sites. GPS units can use the UTM coordinates in Appendix A to set courses and reduce unproductive time looking for sites. Locations, descriptions, approximate dimensions, UTM coordinates, closure methods, and map references of each mine opening (site) are provided in the table in Appendix A. Detailed locations of the sites are presented on the maps in Appendix F. Note that mine symbols may be plotted on the maps offset slightly from their true locations due to terrain interference with GPS surveys and the way the mapping software treats adit symbols.
- C. Site ID Numbers (Tag Numbers): Each mine opening or feature is identified by a unique site identification number such as 3411308HO002. The ID number consists of seven digits, two letters, and three digits. The first digit indicates the quadrant around the Salt Lake baseline and meridian (or the Uinta special meridian). Townships south and east of the SLBM are coded "4." The second and third digits indicate the township, the fourth and fifth digits indicate the range, and the sixth and seventh digits indicate the section. These numbers are followed by letters indicating the type of mine opening or feature (H = horizontal adit, I = inclined adit, V = vertical shaft, SH = subsidence hole, PR = prospect, TR = trench, PT = open pit,) and, in the case of shafts and adits, letters indicating whether the mine is open (O) or closed (C). These letters are followed by numbers that are sequential numbers assigned as the openings were encountered during the field inventory. Thus, site number 4060318HO003 is the third horizontal opening (HO) inventoried in Township 6 South, Range 3 East, Section 18. The leading zeros in the sequential number part of the ID number are frequently omitted (i.e. HO3 instead of HO003).
- D. Identifying Sites: The mine openings are marked in the field with 1"x 2" wood stakes. Tags were intentionally put in obscure locations to deter vandalism and may not be easy to find. Because of vandalism or weather, many mine ID markers are missing or ineligible. CONTRACTOR will have to rely on the site location maps and the descriptions in Appendix A to identify mine sites. OWNER's Contract Representative will provide assistance in identifying the mine openings.

1.04 PROJECT SITE GROUPINGS

- A. The mine sites in the Ophir Canyon Project have been organized into seven groups based on geographical proximity and access considerations. Map 2 of 6 is the Area Detail Map and will serve as a key on subsequent detail sheets, visually illustrating the position of the current sheet within the entire project area. These groups are the basis for the area detail maps in Appendix F and the site groupings in the Bid Schedule and Closure Schedule, Appendix A. The seven groups are: Foothills, Dry Canyon, Ophir Canyon, South Fork Ophir Canyon/Meadow Canyon, Lion Hill, Silveropolis Hill and Rover Hill. The

descriptions that follow have adequate directions to get to the areas mapped on the area detail maps. The maps can then be used to locate each individual mine site. All of the directions start from the intersection of Highway 73 and the Ophir Town Site Road.

B. Foothills: (Map Sheet 3 of 6, Soldier Creek Canyon) [2 sites]

The Foothills area consists of two sites on the west facing slopes of the project boundary. One shaft in Section 5, T5S, R4W and one shaft in Section 8, T5S, R4W. These sites can be accessed from Soldier Canyon to the north or from the Ophir Town Site Road to the south. From the south, proceed 0.25 miles towards Ophir. Turn left (north) and proceed towards the gravel pit on the dirt road. The road quickly splits again. Take the left fork and there will be one unlocked gate that you will go through. Stay on the power line access road for another 4.17 miles weaving along the power line. The road will then split. Leave the power line road and take the right hand fork (northeast).

C. Dry Canyon Area: (Map Sheet 4 of 6, Ophir Canyon/Possible Staging Areas) [21 sites]

The Dry Canyon Area consists of 21 sites. There are seven adits, seven shafts, and two 2 inclines in Section 21 and five adits in Section 22, T5S, R4W, within the Dry Canyon area. These sites can be accessed by exiting Highway 73 by turning left (east) and driving 0.25 miles up Ophir Canyon. Turn left (north) and proceed towards the gravel pit on the dirt road. The road quickly splits again. Take the right fork and continue to the northeast for 1.6 miles. The road splits into 3 with the main road continuing northeast, one road going southeast and one going due south past Shaft VO001.

D. Ophir Canyon Area: (Map Sheet 4 of 6, Ophir Canyon/Possible Staging Areas) [7 sites]

The Ophir Canyon Area consists of three adits in Section 28, three sites (two shafts, one incline) in Section 26, and one open adit in Section 27, T5S, R4W. These sites can be accessed by exiting east off Highway 73 and driving 1 mile up Ophir Canyon to just past the power substation on the right for the three sites in Section 28, and another 0.1 mile for the site in section 27. Proceed another 1.1 miles up the canyon and stop by a southeast drainage for the foot access to the three sites in Section 26.

E. South Fork Ophir Canyon/Meadow Canyon Area: (Map Sheets 4 and 6 of 6, Ophir Canyon/Possible Staging Areas and Mercur) [3 sites]

The South Fork Ophir/Meadow Canyon Areas consists of two adits in the main South Fork Ophir Canyon (Section 30) and one shaft on the hillside above Meadow Canyon (Section 32) within T5S, R3W. These sites can be accessed by exiting east off Highway 73 and driving 2.5 miles to the edge of the town of Ophir. Continue 1.9 miles northeast through Ophir Township to the end of the pavement. Continue 0.25 miles northeast on the gravel road located in the bottom of Ophir Canyon. The main road continues up the canyon. Turn right (southeast) off the main road and drive 1.35 miles up the bottom of the South Fork Ophir Canyon on a 4-wheel drive trail to an open meadow. Turn right on a small 4-wheel drive trail and continue south up the South Fork Ophir Canyon for another 1.1 miles just past a small stock watering tank in an open area.

F. Lion Hill Area: (Map Sheet 5 of 6, Lion Hill) [70 sites]

The Lion Hill Area consists of seven shafts and 24 adits in section 25, and 18 shafts and 21 adits in section 26, T5S, R4W, on Lion Hill. Exit Highway 73 turning east on to a paved road named Ophir Town Site Road to access these sites. Drive for 2.5 miles to the southwest edge of the town of Ophir. Continue 1.9 miles northeast through Ophir Township to the end of the pavement. Continue 0.25 miles northeast on the gravel road located in the bottom of Ophir Canyon. The main road continues up the canyon. Turn right (southeast) off the main road and drive 1.35 miles up the bottom of the South Fork Ophir Canyon on a 4-wheel drive trail to an open meadow. Turn right on a smaller 4-wheel drive trail and continue south up the South Fork Ophir Canyon 1.25 miles to a topographic saddle. Turn right and drive uphill through the trees to the ridgeline (0.45 miles). Stay on the main 4X4 road on the west side of the ridgeline, continuing northwest 1.3 miles to the Lion Hill Junction. The oak brush is thick along this route and will scratch a normal 4-wheel drive vehicle.

Section 0300

- G. Silveropolis Hill Area: (Map Sheet 4 and 6 of 6, Ophir Canyon/Possible Staging Areas and Mercur) [27 sites]
The Silveropolis Hill Area consists of 27 sites in Sections 24 and 25, T5S, R4W. Exiting east off Highway 73 and driving 4.4 miles on pavement through Ophir Township to the end of the pavement can access these sites. Continue 0.25 miles northeast on the gravel road located in the bottom of Ophir Canyon. The main road continues up the canyon. Turn right (southeast) and leave the main road and drive 1.35 miles up the bottom of the South Fork Ophir Canyon on a 4-wheel drive trail to an open meadow. Turn right on a small 4-wheel drive trail and continue south up the South Fork Ophir Canyon for 1.3 miles to a saddle in an open area. The access to Silveropolis Hill is by turning right and driving 0.41 miles uphill through the trees to the ridgeline. Continue on the main road 0.73 miles northwest to a road juncture leading to the south side of Silveropolis Hill and to Silverado Canyon.
- H. Rover Hill Area: (Map Sheet 6 of 6) [13 sites]
The Rover Hill Area consists of eight sites in Section 36, T5S, R4W, three sites in Section 31, T5S, R3W, and two sites in Section 33 T5S, R3W, around Rover Hill and Porphyry Knob. These sites can be accessed by exiting east off Highway 73 and driving 2.5 miles to the edge of the town of Ophir. Continue 1.9 miles northeast through Ophir Township to the end of the pavement. Continue 0.25 miles northeast on the gravel road located in the bottom of Ophir Canyon. The main road continues up the canyon. Turn right (southeast) and leave the main road and drive 1.35 miles up the bottom of the South Fork Ophir Canyon on a 4-wheel drive trail to an open meadow. Turn right on a small 4-wheel drive trail and continue south up the South Fork Ophir Canyon for another 1.3 miles, past a small stock watering tank to a saddle in an open area. The access to Rover Hill and Silveropolis Hill is by turning right in this saddle and driving uphill through the trees to the ridgeline (0.41 miles). Stay on the main 4x4 dirt road to the west side of the ridgeline, continuing another 0.73 miles northwest to a road junction. The oak brush is thick along this route and will scratch a normal 4-wheel drive vehicle. Turn left (south) and head down the hillside 0.84 miles to the very bottom of Silverado Canyon. At that point, the road continues down Silverado Canyon or climbs up Rover Hill.

1.05 PROJECT AREA ACCESS

- A. The project area is served with a network of old roads, ATV trails, and foot trails. Paved roads are limited to Highway 73 and the main roads in Ophir, Mercur and Soldier Canyons. All other roads and dirt or gravel with varying degrees of passability and upkeep. The dirt roads are quite-rutted or rough and rocky in good weather and turn slick and muddy when wet. High clearance and/or 4-wheel drive vehicles are mandatory for travel in much of the project area. ATV trails lead to many sites often but are too narrow or steep for trucks or crawler equipment to use. Many of the mine sites are accessible only by foot. CONTRACTOR shall select from a pre-determined number of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.
- B. Roads on the maps in Appendix F are symbolized as Highway, Paved, Unimproved, ATV, and Foot. Roads symbolized as Paved are maintained and should be passable to all types of vehicles in all weather. Roads symbolized as Unimproved are wide enough for a standard truck or SUV, but may have ruts, gully crossings, or other obstacles requiring high clearance and/or four-wheel-drive. Roads symbolized as ATV are either too narrow, too steep, or too rocky for full sized vehicles but are suitable for ATV's. Some ATV roads may be also suitable for tracked equipment. Roads symbolized as Foot are too steep, narrow, washed out, or boulder strewn for vehicles, although some may be passable to single-track vehicles (dirt bikes).
- C. Vehicle travel on some roads is subject to restrictions (see Part 2.05 below).

1.06 LAND STATUS

- A. The Ophir Canyon Project area contains land owned or controlled by numerous parties. OWNER is responsible for obtaining the necessary rights of entry to perform the reclamation work. OWNER will have

maps showing boundaries of property tracts available during construction for consultation.

- B. Approximately 56 of the 143 sites occur on public land managed by the Bureau of Land Management (BLM). These include sites on unpatented mining claims and sites on other public land. For more information, contact:

Larry Garahana, Geologist
Salt Lake Office
Bureau of Land Management
2370 South 2300 West
Salt Lake City, Utah 84119
(801) 977-4300

- AA. The remaining 87 sites scheduled for closure are on private land held by a number of different interests.
- D. CONTRACTOR shall not perform WORK on any site until OWNER has obtained landowner consent for that site.
- E. CONTRACTOR shall not perform WORK on sites on BLM administered land until OWNER has obtained authorization from BLM (expected prior to Notice to Proceed).

PART 2 - SPECIAL CONDITIONS AND RESTRICTIONS

2.01 CULTURAL RESOURCE PROTECTION

- A. Portions of the Ophir Canyon Project area have been determined to be eligible for listing on the National Register of Historic Places. *All reclamation activities shall be conducted in a manner sensitive to the historic values and resources found in the area.* CONTRACTOR shall ensure that all construction crewmembers are aware of the cultural sensitivity of the area and the cultural resource protection requirements.
- B. While features such as cabins, head frames, and ore chutes are obviously important, many of the historically important features present in the project area are not readily apparent. For example, ore sorting areas may appear simply as a patch of differently colored rock on a dump. Much of what is significant at Ophir Canyon might typically be dismissed as "trash" somewhere else. Often, the mine opening itself, or cribbing within an opening, is important and needs to be treated appropriately, and protected if possible.
- C. Access improvement, excavation, and other ground disturbing activities shall be limited to the minimum necessary to achieve the goals of the WORK. OWNER shall be present if alteration or removal of structures or structural elements of mine openings, such as props, lagging, cribbing, retaining walls, foundations, doorways and all such work are required. Work shall be limited to the minimum necessary to safely and effectively install the closure. Any such alteration shall be planned in advance in consultation with and executed as directed by the OWNER.
- D. One of the key features of the project area that makes the Ophir mining district historically important is its surviving "historic landscape": the overall appearance of the terrain dotted with mine dumps and workings offering a glimpse of the past. To preserve this historic appearance, mine dumps used as a source of backfill shall be excavated in a way that maintains the shape and grades of the dump. This can be done by uniformly removing material from all surfaces, by removing material from the top down, by slightly "hollowing out" the dump, or by removing one lobe of a multi-lobed dump. The dump's overall appearance should not change except to be reduced in size.
- E. Removal of historic or prehistoric artifacts or rock specimens is prohibited by federal law. This includes, but is not limited to: bottles, bottle fragments, china and glass fragments, tools, tin cans, buckets, pipe, wire,

Section 0300

nails, spikes, bolts, track, machinery, ore cars, vehicles, lumber and other wood, arrowheads and other stone tools, ore samples, petrified wood, and fossils.

- F. CONTRACTOR shall stop work and notify OWNER immediately if human burial remains are discovered.
- G. The mine locations that are historic are listed as such under the "Special Conditions" column in the Mine Closure Schedule in Appendix A, and noted in the site descriptions in Section 0300.
- H. Protection Measures for culturally significant sites are as follows: 1) shafts are to be backfilled flush to the ground so that after settling, small depressions will allow the shaft's location to be recognized; and 2) all features not directly involved in the reclamation activity must not be disturbed in any way. Where walls, loading platforms, roads, machinery mounts, structures, or other features are present, these shall be flagged or barricaded to avoid any disturbance. The OWNER will closely monitor the closure activities.
- I. In all cases, fill will be removed from spoil piles in such a way that the pile's shape is not radically altered or subject to severe erosion. Mine dumps shall be recontoured after reclamation to maintain their appearance as mine dumps. Prying and barring down material from the brow of the mine for fill shall be kept to a minimum.

2.02 BAT CONSERVATION

- A. OWNER has performed surveys to determine which mines are used for bat habitat. Where bats are present in a mine, they will be Excluded from the mine prior to installing airtight closures (see Section 0250, Part 3.01.F). Sites requiring Exclusion prior to closure are indicated in Appendix A (Special Conditions).
- B. The length of the Exclusion period may be reduced from one week to three fair weather days with OWNER's approval. Rainy or cold weather inhibits bat activity and will increase the length of the Exclusion accordingly, up to the one week maximum.
- C. The heavy recreational use of the project area increases the possibility that vandals may damage or remove the chicken wire seals during the Exclusion period. Should this occur, damaged seals shall be replaced and the Exclusion period started over.
- D. The Exclusion process is effective only in warm seasons when bats are active. To prevent entombing hibernating bats, sites indicated in Appendix A as requiring Exclusion prior to closure shall not be closed during the cold season (from October 31 to March 31). Closure of these sites shall be postponed to the following warm season. Cold season closures may be performed following an internal inspection for hibernating bats. Internal inspections shall be performed by the OWNER and are subject to the availability of the OWNER's bat inspection team.
- E. Vertical shafts covered with chicken wire for bat Exclusion shall be flagged with warning tape.

2.03 BIRD CONSERVATION

- A. During spring nesting and fledging (January 15 to August 31) OWNER will perform line-of-sight visual surveys for raptor nests in the vicinity of the mine sites. If nests are found, CONTRACTOR shall reschedule work at those sites until after August 31.
- B. Bald eagles are known to roost and forage in Rush Valley and the Oquirrh Mountains in the winter months. It is expected that any eagles present in the project area will either move or habituate to the construction activity. CONTRACTOR shall avoid disturbing eagles if they are present. Trees used for roosting shall not be disturbed.

2.04 RARE PLANT CONSERVATION

One plant species is listed as threatened under the federal Endangered Species Act. It is:

Ute Ladies'-tresses - T

OWNER will survey work areas for this plant prior to construction. Any plants found shall be flagged by OWNER and avoided by the work crews. It is extremely unlikely that these plants will be present in the project area.

2.05 BLM TRAVEL RESTRICTION

Certain areas in the Ophir Canyon Project area are designated "on-road-only" by the Bureau of Land Management. Vehicles and heavy equipment are restricted to established roads. This designation may affect access to some sites.

2.06 LAND PROTECTION

- A. Trash, containers, wrappings, empty mortar and concrete mix bags, concrete block fragments, rebar cuttings, welding rod scraps, waste PUF, pallets, water jugs, buckets, broken tools, discarded materials, food wrappers, beverage containers, paper towels, and other such litter generated by the reclamation activities shall be kept contained during construction and shall be cleaned up and removed from the site upon completion.
- B. CONTRACTOR shall exercise care with open flames when welding or cutting to avoid starting range fires. CONTRACTOR shall submit a written range fire prevention and fire response plan to OWNER at the start of construction.
- C. CONTRACTOR shall be responsible to reimburse landowners or lease holders for livestock or other property lost, injured, or damaged by CONTRACTOR's operations on access roads.
- D. CONTRACTOR shall not perform WORK on sites on BLM administered land until OWNER has obtained authorization from BLM (expected prior to Notice to Proceed).

2.07 WORKER HEALTH AND SAFETY

- A. Rodents often nest in abandoned mines and leave accumulations of droppings and nest debris. In theory, these nests and droppings could host the potentially lethal Hantavirus, although no mine closure work has ever been linked to a case of Hantavirus. As a precaution, workers should avoid stirring up dust or rodent droppings in mines and use standard hygiene and sanitation practices (washing before eating, etc.). Workers are encouraged to learn to recognize the symptoms of Hantavirus infection and seek proper medical attention if indicated.
- B. The heavy reliance on manual labor for this project and the steep, rugged terrain increase the probability of orthopedic and trauma injuries. Standard safety gear (hard hat, steel-toed shoes) are required for all personnel. Fatigue, heat stress, and dehydration are inherent medical risks of heavy manual labor in desert environments. Frostbite and hypothermia are risks of winter work. Workers should take appropriate precautions for the site conditions.
- C. CONTRACTOR is required to hold regular safety meetings and is encouraged to have a response plan in place in the event of accidents, personal injury, animal bites, or other medical emergency.
- D. All of Tooele County is covered by 911 emergency telephone service, but the project area has no reliable cell phone coverage.

PART 3 - EXECUTION

3.01 WORK REQUIRED AT ALL SITES

The WORK at the Ophir Canyon Project area shall include closure of approximately 143 mine openings and revegetation of areas disturbed by reclamation work. Additional mine closures may be added to the WORK as the project progresses if new mine openings are found or sites are re-evaluated.

- A. Mobilization/Demobilization. Mobilize labor, equipment, and supplies to the site in accordance with section 0200: Mobilization/Demobilization, and as follows:
1. Previously disturbed areas should be selected for staging and activity areas as much as possible. Vegetation grubbing and topsoil stripping and stockpiling shall not be done in the staging areas.
 2. There are minimal services available in the project area. Ophir has a small store that is not open very often. Tooele has all services including motels. Stockton has small market, no fuel. Cell phone service is spotty and poor.
- B. Access Improvement. Improve access to the site along the routes described to the degree required to conduct the WORK. All access improvement shall be performed in accordance with Section 0230, Access Improvement. Where access has been created, the access shall be closed following construction in accordance with Section 0230, Access Improvement. Access grading shall be in accordance with Section 0270, Site Grading/Earthwork.
1. Access to the project area is possible on existing roads and requires little or no additional improvement. The secondary dirt roads inside the project are subject to washouts, ruts, and rock falls. Modest access improvements are anticipated to be needed in some localized areas.
 2. No new access road construction will be allowed. Improve access to the individual mine openings by upgrading the existing dirt roads, ATV trails, and footpaths to the minimum degree required to conduct the WORK. Site access should require minimal or no improvements work in most areas. CONTRACTOR should generally expect to select the mode of transportation to fit the existing ground conditions rather than changing the ground to accommodate a vehicle. Access to many sites will require cross-country traverse. Access routes should be selected to avoid or minimize disturbance to vegetation and cultural resources. Access routes and improvements are subject to approval by OWNER. Except on main roads, work should be organized to minimize the number of repeat trips on a particular route to reduce wear and tear (this applies to foot traffic as well as to vehicle and equipment). Where possible, "one trip in, one trip out" is the goal.
 3. CONTRACTOR shall obliterate footprints, truck and ATV tire tracks, and crawler tracks by raking or similar means as directed by OWNER in areas where access routes deviate from existing established open roads. Severe trail wear or compaction may require mechanical scarification and reseeding.
 4. CONTRACTOR shall remove all access improvements and return roads to their pre-construction condition upon completion of work.
- C. Mine Closure. Close all identified mine openings, subsidence holes, and pits in accordance with the technical specifications in Sections 0250 through 0254, and as follows:
1. Use the closure method as specified for each site in the "Closure Method" column of the table in Appendix A. Estimated closure dimensions and/or construction quantities (cubic yards of backfill;

square feet of masonry wall, bat gate, or rebar grate) for each closure are provided in Appendix A. Use the technical specification section and standard drawing referenced in Appendix A for each closure.

2. Backfill closures specified in Appendix A are noted as either hand work or equipment work. These designations reflect OWNER's expectation for the backfill method, but are not binding. Mine openings scheduled for equipment backfill may be backfilled by hand and mine openings scheduled for hand backfill may be closed by equipment depending on circumstances on the ground. The choice of hand or machine backfill methods shall be determined in consultation with OWNER and is subject to OWNER's approval. Cost adjustments will be negotiated based on the Variation in Quantity Unit Prices in the bid schedule for comparable work.
 3. Two shafts to be backfilled in the Dry Canyon Group have wood cribbing, or other structural elements that shall be protected from damage. These sites are 3050421VO002 and 3050421VO003. CONTRACTOR shall rig a temporary chute or funnel of plywood or sheet metal that will protect the top few feet of the wood structures at these sites from damage from rock impact and abrasion while the shaft is being backfilled.
 4. Wall closures specified in Appendix A are noted as either stone or concrete block. These designations reflect OWNER's expectation for the wall material, but are not binding. The designations are based on assessments of the onsite availability of suitable stone and the difficulty of transporting block to remote locations. Mine openings scheduled for stonewalls may be closed with block walls, or vice versa. The choice of wall material shall be determined in consultation with OWNER and is subject to OWNER's approval. Cost adjustments to the Bid Price will not be made when a wall material is changed.
 5. Concrete block walls shall be treated on the outer surface to blend with the adjacent native rock. Suitable treatments include facing the block wall with a layer of rock or plastering or stuccoing with mortar mixed with local sand or soil. The intent is to camouflage the wall by matching the color and texture of the native rock. Camouflage treatments may be omitted at some sites at OWNER's direction depending on the visibility of the wall.
 6. For sites that are specified to be closed with rebar grates refer to the pinned rebar shaft grate design (see Section 0253, Part 3.03.G) with the grate installed in a angled plane across the opening. Rebar adit grates (mild steel rebar, 8"x8" grid) should not be confused with bat gates (Maganal steel, 6"x24" grid).
 7. Site-specific variations to the generic closure methods are required at some mine openings. Some of these special requirements or customized details are noted in Appendix A. Not all such special requirements are so noted in Appendix A. Sites without notes may still require site-specific variations to be determined during construction.
 8. Where present in a mine, bats will be Excluded from the mine prior to installing the closure (see Section 0250, Part 3.01.F and Section 0300, Part 2.02). Mine sites requiring Exclusion prior to closure are indicated in the "Special Conditions" column in the table in Appendix A.
- C. Revegetation. Revegetate all areas disturbed by reclamation activities in accordance with Section 0290: Revegetation, and as follows:
1. Disturbed areas include staging areas, access routes, backfill portals, shafts, regarded areas, and backfill borrow areas. Areas of bare rock, rock ledges, and rocky out slopes of mine dumps do not need to be revegated.

Section 0300

2. Use the Ophir Canyon seed mixture (Appendix C). A total area estimated at 14 acres will need to be revegetated. The actual revegetation area will vary depending on the CONTRACTOR's diligence in executing the work and limiting disturbance.
3. Revegetation shall be considered incidental to installation of the mine closure. Revegetation costs shall be incorporated into the costs for mine closure. Revegetation is not included as a separate bid or pay item, but is considered subsidiary to the other items of WORK. No separate payment shall be made for revegetation.
4. Mulch and fertilizer shall not be required.

D. Rights of Entry from the Landowners have been obtained on all the sites contained in the WORK.

3.02 CONSTRUCTION SCHEDULING

- A. Notice to proceed with construction is contingent upon OWNER receiving authorizations from the BLM and from the U.S. Office of Surface Mining. OWNER expects both authorizations to be in place by the July 19 bid date. However, if either is lacking, WORK will be postponed accordingly.
- B. Work Priorities: Because the start of construction is mid-summer, it may not be possible to complete all of the WORK before the onset of adverse winter weather. CONTRACTOR shall prioritize the execution of the WORK to complete the higher elevation mine closures first.
- C. Most of the site reclamation for the Ophir Canyon Project is not weather dependent. It is conceivable that the project work will be suspended for the winter because of the late season start date. The CONTRACTOR shall account for this potential shutdown within the mobilization/demobilization cost. The mine closure costs quoted on the bid schedule apply for the duration of the reclamation. The start-up date for resumption of suspended WORK due to adverse weather or other conditions will be determined by OWNER in consultation with CONTRACTOR and will depend upon the nature of the uncompleted WORK.

END OF SECTION 0300

Appendix A

Site Descriptions and Mine Closure Schedule

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

APPENDIX A SITE DESCRIPTIONS

and

MINE CLOSURE SCHEDULE

Note: Refer to Section 0300, Part 1.03.C of the specifications for a description of the site ID numbering (tag number) system.

Use the following specification section and standard design drawing in Appendix E for each closure type referenced in Appendix A:

<u>Closure Type</u>	Specification Section	Standard Mine Closure Design Drawing Appendix E
BACKFILL (ADIT): Hand or Equipment	0250, Part 3.02	E1
BACKFILL (SHAFT): Hand or Equipment	0250, Part 3.02	E2
WALL (BLOCK)	0250, Part 3.02	E3
WALL (STONE)	0250, Part 3.02	E4
BAT GATE	0253, Part 3.02	E6 and E7
REBAR GRATE (GRADE BEAM & I-BEAM)	0253, Part 3.03	E14, E15, and E16
REBAR GRATE (PINNED)	0253, Part 3.03.G	E17

Note: Standard mine closure design drawings for the following closure types are not included in Appendix E because none are specified for this project: Wall & Backfill, CMP Bat Gate

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Refer to Section 0300, Part 1.03.C of the Specifications for a description of the site ID numbering (tag number) system. There are many small prospects for which no work is planned that are tagged or mapped and are simply included in the descriptions of tagged features.

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
SOLDIER CREEK CANYON						
Foot Hills Area (2 sites)						
3050405VO001	4474355	388669	4x10x13d; wood timbers		BFM	20
3050408VO001	4473345	388139	20x14, 8' inside 6x6x+80d		GRATE-B	280
OPHIR CANYON						
Dry Canyon (21 sites)						
3050421HO001	4469033	390490	4.5wx1.5hx13d; no dump	Bat Excl NR Elig	BFH	2
3050421HO002	4469106	390437	3wx1hx?d; Collapsed shed	Bat Excl NR Elig	BFH	1
3050421HO003	4469577	390494	5wx6h VO4 needs to be done first		BG	30
3050421HO004	4470107	390072	5wx2.5h, 5' inside 5wx4hx13d	Bat Excl	BFH	4
3050421HO005	4469981	390174	5wx4.5h55d		BG	20
3050421HO006	4469989	390135	5wx2hx32d	Bat Excl	BFM	3
3050421HO007	4469929	390111	6wx1hx15d		BFH	4
3050421IO001	4470100	390354	12wx4hx+60d; entrance spits to two entries	NR Elig	BG	48
3050421IO002	4469990	390215	6wx4.5hx+60d	Bat Excl	BFM	60
3050421VO001	4469523	390338	19x27, 9' inside 8x10x86d; fence	Bat Excl NR Elig	BFM	320
3050421VO002	4469154	390356	5x14x15d; mine timber across shaft	NR Elig	BFH	40
3050421VO003	4469153	390395	4x7x9d, ladder in shaft, protect ladder	NR Elig	BFH	9
3050421VO004	4469577	390494	5x8x40d; mine timbers		Grate	40
3050421VO005	4470103	390012	5x7x9d, Access improvement		BFM	10
3050421VO006	4470093	390220	5x5.5x29d		BFM	36
3050421VO007	4469989	390135	9x11x+27d; fence		GRATE-P	99
3050422HO001	4469174	390626	6.5wx8hx+100d; wood props, 3" behind wood	NR Elig	BG	52
3050422HO002	4469197	390661	4.5wx1h, 10' inside 5wx3hx14d	NR Elig	BFH	4

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
3050422HO003	4469911	390709	5wx6.5hx115d; mine structures, 5' in just before wood timbers		BG	36
3050422HO004	4470133	390744	4wx6hx+70d; mine rail; concrete steel door frame, 2' inside door frame	NR Elig	BG	24
3050422HO005	4470098	390822	5wx2.5hx40d	Bat Excl NR Elig	Wall-B	15
Ophir Canyon (7 sites)						
3050426VO018	4468273	392422	6x9x16d, foot trail		BFH	14
3050426VO019	4468294	392432	7x9x+40d; mine timbers over opening, foot trail		BFH	62
3050426IO001	4468293	392349	6wx3h; foot trail		BFH	4
3050428HO001	4467846	390237	6wx5hx115d; mine timbers and mine rail	Bat Excl	BFM	32
3050428HO002	4467864	390264	5wx2h, 10' inside 19wx5h	Bat Excl	BFM	40
3050428HO003	4467867	390300	8wx1h, 15' inside 8wx5h; no dump; chicken wire		BFM	6
3050427HO008	4463909	396991	4.5Wx2.5H	Bat Excl	BFH	8
South Fork Ophir/Meadow Canyon (3 sites)						
3050330HO001	4467475	396134	2.5wx1hx179d		BG	3
3050330HO002	4467517	396277	3wx2.5hx+25d		BG	8
3050332VO001	4465707	398241	13x15x18d		BFM	130
Lion Hill (70 sites)						
3050425HO001	4468081	394349	4wx5hx+18d, no dump, scale from brow	Bat Excl NR Elig	BFM	13
3050425HO002	4468000	394297	4wx1hx+12d	NR Elig	BFM	7
3050425HO003	4467909	394013	4wx2h, 10' inside 7wx4hx25d; mine timber 10' inside	NR Elig	BFH	11
3050425HO004	4468190	394154	5wx3hx17d	NR Elig	BFM	10
3050425HO005	4468257	394206	5wx6hx+150d, 8' inside	NR Elig	BG	30
3050425HO006	4468191	394294	2.5wx3hx15d	Bat Excl NR Elig	BFM	7

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
3050425HO007	4468188	394312	3wx.5hx12d; no dump	Bat Excl NR Elig	BFM	7
3050425HO008	4468419	394284	6wxh5hx30d; 35' east of HO9	Bat Excl NR Elig	BFM	20
3050425HO009	4468432	394278	5wx6hx25d; no dump	Bat Excl NR Elig	BFM	8
3050425HO010	4468498	394290	7wx4hx17d	Bat Excl NR Elig	BFM	19
3050425HO011	4468555	394243	4wx1hx35d	Bat Excl NR Elig	BFM	17
3050425HO012	4468578	394245	3wx1hx7d; 30' tall fir tree near portal	NR Elig	BFM	4
3050425HO013	4468579	394234	4wx1hx+6d	NR Elig	BFM	10
3050425HO014	4468579	394227	.5 diax+8d	Bat Excl NR Elig	BFM	10
3050425HO015	4468578	394216	1.5wx.5hx+35d	Bat Excl NR Elig	BFM	10
3050425HO016	4468580	394174	4.5wx6hx+200d; BG 20' inby square set beyond metal door	NR Elig	BG	33
3050425HO017	4468523	394126	4wx1hx+300d; loadout bin; mine rail; mine timbers, dig out little, 2' inby	NR Elig	BG	4
3050425HO018	4468480	394109	3wx1.5h, 20' inside 8wx6.5h x+100d; wood props	Bat Excl NR Elig	BFM	51
3050425HO019	4468484	394069	2wx1h, 10' inside 8wx7hx25d	Bat Excl NR Elig	BFM	51
3050425HO020	4468504	394014	4wx6hx16d	Bat Excl NR Elig	BFM	19
3050425HO021	4468498	393968	4wx1hx+10d	NR Elig	BFM	10
3050425HO022	4468492	393953	2.5wx1.5hx+15d	NR Elig	BFM	10
3050425HO023	4468493	393937	4.5wx2hx16d	Bat Excl NR Elig	BFM	10

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
3050425VO001	4467886	394356	25x25; unconsolidated and sloughing	NR Elig	BFM	104
3050425VO002	4467760	394279	6x11x10d; shaft between two 40' pine trees	NR Elig	BFM	26
3050425VO003	4468212	394181	8x8x19d	NR Elig	BFM	50
3050425VO004	4468217	394161	6x7x33d small dump, adjacent dump material	Bat Excl NR Elig	BFM	55
3050425VO005	4468434	394313	9x10x28d, fill above shaft	Bat Excl NR Elig	BFM	80
3050425VO006	4468469	394166	17x17x13d; sloughing	NR Elig	BFM	60
3050425VO007	4468488	394234	10x10x12d	NR Elig	BFM	16
3050426HO001	4468446	393769	3wx1hx+6d	NR Elig	BFM	11
3050426HO002	4468513	393716	3wx1hx15d	Bat Excl NR Elig	BFH	10
3050426HO003	4468562	393728	4wx1.5hx9d	NR Elig	BFH	6
3050426HO004	4468539	393638	4wx4hx27d; wood props	NR Elig	BFH	19
3050426HO005	4468480	393638	4wx1hx20d; no dump, adjacent side hill	Bat Excl NR Elig	BFM	10
3050426HO006	4468475	393654	2.5wx1hx+25d, small dump, adjacent side hill	Bat Excl NR Elig	BFM	7
3050426HO007	4468438	393417	5.5wx7hx+200d; mine timbers	Bat Excl NR Elig	Wall-S	42
3050426HO008	4468452	393397	3.5wx5hx+30d	Bat Excl NR Elig	BFH	8
3050426HO009	4468396	393489	4.5wx1.5hx+40d	Bat Excl NR Elig	BFH	11
3050426HO010	4468393	393491	5wx6hx60d; barrel, fry pan	Bat Excl NR Elig	Wall-S	30
3050426HO011	4468390	393496	5wx5hx+100d	Bat Excl NR Elig	BFH	12
3050426HO012	4468413	393494	3wx2hx+30d	Bat Excl NR Elig	Wall-S/BFH	6

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
3050426HO013	4468354	393644	4wx4hx40d; wood props	Bat Excl NR Elig	BFH	11
3050426HO014	4468355	393650	3wxh2hx20d	Bat Excl NR Elig	BFH	10
3050426HO015	4468362	393637	1.5wx4hx20d	Bat Excl NR Elig	BFH	4
3050426HO016	4468344	393503	5wx2hx9d	NR Elig	BFH	8
3050426HO017	4468244	393490	4.5wx2.5hx19d	Bat Excl NR Elig	Wall-S/BFH	21
3050426HO018	4468359	393532	6.5wx2h+30d	Bat Excl NR Elig	BFH	19
3050426HO019	4468180	393749	3.5wx1.5h, 5' inside 6wx6hx20	Bat Excl NR Elig	BFM	27
3050426HO020	4468160	393749	3.5wx6hx+100d; access improvement; cabin remains	Bat Excl NR Elig	BFM	22
3050426HO021	4468107	393810	5wx6.5hx41d	Bat Excl NR Elig	BFM	33
3050426VO001	4468474	393664	14x12 tapering to 8x8x26d	Bat Excl NR Elig	BFH	108
3050426VO002	4468468	393552	6x6x34d; mine timbers	Bat Excl NR Elig	BFH	46
3050426VO003	4468474	393549	5.5x5.5x+87d	Bat Excl NR Elig	BFH	100
3050426VO004	4468439	393515	7x9x78d; mine timbers	Bat Excl NR Elig	BFH	190
3050426VO005	4468455	393441	8x8x39d	Bat Excl NR Elig	BFH	98
3050426VO006	4468459	393380	9x5x42d	Bat Excl NR Elig	BFH	75
3050426VO007	4468468	393318	7x6x15d; other crosscuts visible	NR Elig	BFH	30
3050426VO008	4468387	393555	6x7x10.5d; other crosscuts visible, small dump and adjacent material	Bat Excl NR Elig	BFM	27
3050426VO009	4468360	393567	6x6x36d	NR Elig	BFM	51

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
3050426VO010	4468404	393592	6x6x15d, adjacent trench	NR Elig	BFM	22
3050426VO011	4468222	393744	collar 18x14, 10' inside 6x7x80d	Bat Excl NR Elig	BFM	238
3050426VO012	4468184	393708	10x10x14d; crosscuts and other workings visible, use from VO12	Bat Excl NR Elig	BFM	95
3050426VO013	4468186	393706	6x6x+15d; other workings visible	Bat Excl NR Elig	BFM	41
3050426VO014	4468199	393705	10x12x30d; mine timbers	Bat Excl NR Elig	BFM	149
3050426VO015	4468186	393728	5x5x32d; mine timbers; wood props	Bat Excl NR Elig	BFM	54
3050426VO016	4468142	393734	4x6x+35d; mine timbers; wood props	Bat Excl NR Elig	BFM	4
3050426VO017	4468141	393733	3x7x+100d; shaft opens up to 25' high; connects to VO17B	Bat Excl NR Elig	BFM	2000
3050426VO017B	4468125	393729	4x6x22d; crosscuts and other working visible	NR Elig	BFM	500
Silveropolis Hill (27 sites)						
3050424HO001	4468727	394600	5wx2hx+10d; mine timber and structures	NR Elig	BFH	4
3050425HO025	4467545	394206	3wx4hx+100d; caved, hard to find	NR Elig	BFH	6
3050425HO026	4467562	394521	4.5wx4h, 10' inside 6.5wx7hx32d	NR Elig	BG	20
3050425HO027	4467538	394506	7wx6hx+31d	NR Elig	BG	42
3050425HO028	4467524	394377	7wx3.5h, 10' inside 9wx10h x+40d; lumber and scrap iron	NR Elig	BG	90
3050425HO029	4467399	394347	3wx1.5h, 10' inside 3.5wx6hx300	NR Elig	BFH	6
3050425HO030	4467342	394545	8wx4hx+50d	Bat Excl NR Elig	Wall-B	32
3050425HO031	4467309	394562	5wx5hx+50d, equipment access improvement	Bat Excl NR Elig	Wall-B	25
3050425HO032	4467330	394598	5wx2.5h, 10' inside 6wx7hx200d; mine buildings	Bat Excl NR Elig	BFH	9

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
3050425HO033	4467447	394580	1.5wx2hx?d; mine building collapsed; rock wall	Bat Excl NR Elig	BFH	3
3050425HO034	4467598	394617	9wx7hx?d; mine timbers; pipe	NR Elig	BG	63
3050425HO035	4467469	394636	5wx5hx60d; mine rail, adjacent dump	Bat Excl NR Elig	Wall-B	25
3050425HO036	4467482	394610	7wx4hx+45d; tin stove pipe, powder barrel	Bat Excl NR Elig	BFH	6
3050425HO037	4467601	394771	5wx3hx220d	Bat Excl NR Elig	BFH	5
3050425HO038	4467604	394770	6wx3hx22d; mine rail	Bat Excl NR Elig	BFH	6
3050425HO039	4467497	394821	5wx3hx50d; no dump	NR Elig	Wall-B	15
3050425HO040	4467159	394827	4wx3hx50d	Bat Excl	BFM	23
3050425HO041	4468245	394761	6wx6hx+800d; door 100' in closed; mine rail; cabin; box cribbing, 6 square sets in 36'	NR Elig	BG	36
3050425HO042	4468577	394309	2wx1.5h, 10' inside 4wx5hx?d; mine timber and metal parts	Bat Excl NR Elig	BFH	6
3050425HO043	4468550	394278	4wx3hx+50d	Bat Excl NR Elig	BFH	6
3050425HO044	4468280	394427	6wx2hx20d	Bat Excl NR Elig	BFH	8
3050425HO045	4468495	394409	6wx3hx35d; entry shed collapsed	Bat Excl NR Elig	BFH	8
3050425HO046	4467171	0	5wx6hx+59d; mine timber; crank; pipe; screens	NR Elig	BFH	16
3050425VO008	4467562	394521	6x8x8d	NR Elig	BFH	11
3050425VO009	4467524	394479	10x15x9d	NR Elig	BFH	21
3050425VO010	4467533	394384	5x7x+200d; access improvement, connects with HO28	NR Elig	GRATE-P	35
3050425VO011	4467345	394538	4x4.5x27d; mine timbers	NR Elig	GRATE-P	18

APPENDIX A SITE DESCRIPTIONS AND MINE CLOSURE SCHEDULE

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method & Comments	Estimated Quantity cyd/sq'
	Northing	Easting				
MERCUR CANYON						
Rover Hill (13 sites)						
3050331IO001	4466499	395950	4.5wx2.5dx?d; access improvement	Bat Excl	BFM	10
3050331VO001	4465918	395752	12x14x30d; barbed wire fence		BFM	190
3050331VO002	4465469	396001	15x15x?d; fenced		BFM	120
3050433HO004	4466981	390443	4x3.5x20d		BFM	4
3050433VO007	4466897	390448	18x20x12d		BFM	150
3050436HO001	4466862	394978	5wx4hx70d; mine timbers and rail, equipment access from south side	Bat Excl	BFH	8
3050436HO002	4466871	394995	6.5wx8hx?d; mine timbers, equipment access from south side	Bat Excl	BFM	45
3050436HO003	4466639	395006	6wx5h, equipmetn access from south side	Bat Excl	BFM	60
3050436HO004	4466975	394840	3wx1.5hx+25d	Bat Excl	BFH	3
3050436VO001	4466751	395220	12x15x14d	Bat Excl	BFM	120
3050436VO002	4466859	395090	13x16x15d		BFM	47
3050436VO003	4466171	394742	19x19x7d; fence		BFM	105
3050436VO004	4465761	394758	7x8x10d		BFM	16

All Locations and dimensions are approximate and have not been field verified. Construction quantities are estimated and will be confirmed at time of construction. UTM coordinates are all in Zone 12. Refer to Section 0300, Part 1.03.C of the Specifications for a description of the site ID numbering (tag number) system. Dimensions are in feet. h=high/height, w=wide/width, l=long/length, d=deep/depth, diam=diameter, unk=unknown, w/=with, ~approx=approximately. Compass directions=N,NW,E,SE,S, etc. Special conditions: Bat excl=bat Exclsion required, NR Elig=National Register eligibility site, BLM Mon= work to be monitored by BLM archeologist. Closure Methods: TBD= To Be Determined

Appendix B

Sites Listed by Closure Type and Estimated Quantity

APPENDIX B SITES LISTED BY CLOSURE TYPE AND ESTIMATED QUANTITY

APPENDIX B SITES LISTED BY CLOSURE TYPE AND ESTIMATED QUANTITY

APPENDIX B

SITES LISTED BY CLOSURE TYPE AND ESTIMATED QUANTITY

Note: Refer to section 0300, Part 1.03.C of the Specifications for a description of the site ID numbering (tag number) system.

BACKFILL (Hand) Total: 47 sites, 1058 cyd

3050421HO001	2	cyd	3050425HO042	6	cyd	3050426HO016	8	cyd
3050421HO002	1	cyd	3050425HO043	6	cyd	3050426HO018	19	cyd
3050421HO004	4	cyd	3050425HO044	8	cyd	3050426IO001	4	cyd
3050421HO007	4	cyd	3050425HO045	8	cyd	3050426VO001	108	cyd
3050421VO002	40	cyd	3050425HO046	16	cyd	3050426VO002	46	cyd
3050421VO003	9	cyd	3050425VO008	11	cyd	3050426VO003	100	cyd
3050422HO002	4	cyd	3050425VO009	21	cyd	3050426VO004	190	cyd
3050424HO001	4	cyd	3050426HO002	10	cyd	3050426VO005	98	cyd
3050425HO003	11	cyd	3050426HO003	6	cyd	3050426VO006	75	cyd
3050425HO025	6	cyd	3050426HO004	19	cyd	3050426VO007	30	cyd
3050425HO029	6	cyd	3050426HO008	8	cyd	3050426VO018	14	cyd
3050425HO032	9	cyd	3050426HO009	11	cyd	3050426VO019	62	cyd
3050425HO033	3	cyd	3050426HO011	12	cyd	3050427HO008	8	cyd
3050425HO036	6	cyd	3050426HO013	11	cyd	3050436HO001	8	cyd
3050425HO037	5	cyd	3050426HO014	10	cyd	3050436HO004	3	cyd
3050425HO038	6	cyd	3050426HO015	4	cyd			

BACKFILL (Equipment) Total: 66 sites, 5532 cyd

3050331IO001	10	cyd	3050425HO015	10	cyd	3050426VO008	27	cyd
3050331VO001	190	cyd	3050425HO018	51	cyd	3050426VO009	51	cyd
3050331VO002	120	cyd	3050425HO019	51	cyd	3050426VO010	22	cyd
3050332VO001	130	cyd	3050425HO020	19	cyd	3050426VO011	238	cyd
3050405VO001	20	cyd	3050425HO021	10	cyd	3050426VO012	95	cyd
3050421HO006	3	cyd	3050425HO022	10	cyd	3050426VO013	41	cyd
3050421IO002	60	cyd	3050425HO023	10	cyd	3050426VO014	149	cyd
3050421VO001	320	cyd	3050425HO024	10	cyd	3050426VO015	54	cyd
3050421VO005	10	cyd	3050425HO040	23	cyd	3050426VO016	4	cyd
3050421VO006	36	cyd	3050425VO001	104	cyd	3050426VO017	2000	cyd
3050425HO001	13	cyd	3050425VO002	26	cyd	3050426VO017B	500	cyd
3050425HO002	7	cyd	3050425VO003	50	cyd	3050428HO001	32	cyd
3050425HO004	10	cyd	3050425VO004	55	cyd	3050428HO002	40	cyd
3050425HO006	7	cyd	3050425VO005	80	cyd	3050428HO003	6	cyd
3050425HO007	7	cyd	3050425VO006	60	cyd	3050433HO004	4	cyd
3050425HO008	20	cyd	3050425VO007	16	cyd	3050433VO007	150	cyd
3050425HO009	8	cyd	3050426HO001	11	cyd	3050436HO002	45	cyd
3050425HO010	19	cyd	3050426HO005	10	cyd	3050436HO003	60	cyd
3050425HO011	17	cyd	3050426HO006	7	cyd	3050436VO001	120	cyd
3050425HO012	4	cyd	3050426HO019	27	cyd	3050436VO002	47	cyd
3050425HO013	10	cyd	3050426HO020	22	cyd	3050436VO003	105	cyd
3050425HO014	10	cyd	3050426HO021	33	cyd	3050436VO004	16	cyd

APPENDIX B SITES LISTED BY CLOSURE TYPE AND ESTIMATED QUANTITY

WALL (Block) Total: 5 sites, 112 sf

3050422HO005	15	sf
3050425HO030	32	sf
3050425HO031	25	sf
3050425HO035	25	sf
3050425HO039	15	sf

WALL (Stone) Total: 4 sites, 99 sf

3050426HO007	42	sf
3050426HO010	30	sf
3050426HO012	6	sf
3050426HO017	21	sf

BAT GATE Total: 16 sites, 539 sf

3050330HO002	8	sf	3050422HO003	36	sf	3050425HO026	20	sf
3050421HO003	30	sf	3050422HO004	24	sf	3050425HO027	42	sf
3050421HO005	20	sf	3050425HO005	30	sf	3050425HO028	90	sf
3050421HO001	48	sf	3050425HO016	33	sf	3050425HO034	63	sf
3050422HO001	52	sf	3050425HO017	4	sf	3050425HO041	36	sf
3050330HO001	3	sf						

REBAR GRATE Total: 5 sites, 472 sf

3050421VO004	40	sf
3050408VO001	280 *	sf
3050421VO007	99	sf
3050425VO010	35	sf
3050425VO011	18	sf

* concrete grade beam & steel I-beam

Appendix C

Revegetation Seed Mixture

APPENDIX C REVEGETATION SEED MIXTURE

APPENDIX C OPHIR CANYON PROJECT REVEGETATION SEED MIXTURE

	Common Name	Scientific Name	Preferred Variety	Pounds PLS/Acre
A.	<u>Grasses</u>			
	Sheep fescue	Festuca ovina	Covar	2.00
	Alpine bluegrass	Poa alpina		2.00
	Indian ricegrass	Oryzopsis hymenoides	Nezpar	2.00
	Slender wheatgrass	Elymus trachycaulus	Pryor	2.00
	Tufted hairgrass	Deschampsia caespitosa		2.00
	Mountain brome	Bromus marginatus	Bromar	2.00
A.	<u>Forbs</u>			
	Sweet anise	Osmorhiza occidentalis		2.00
	White yarrow	Achillea millefolium		2.00
	Blue mountain penstemon	Penstemon rydbergii		2.00
	Mountain lupine	Lupinus alpestris		2.00
A.	<u>Shrubs</u>			
	Prairie sage	Artemisia ludoviciana		2.00
				====
				22.00

The planting rate indicated (pounds PLS/acre) is for broadcast seeding.

PLS=Pure Live Seed. Because packaged seed contains nonviable seed, chaff, and other inert materials in addition to live seed, the actual application rate of total seed material will be greater than 22 pounds per acre.

A. Seed Mix Quantity Estimate

14 estimated acres @ 22 lbs PLS/acre = 73 pounds PLS mix required

Appendix D

Contractor Report Forms

Daily Construction Progress Report

Contractor Performance Rating

DAILY CONSTRUCTION PROGRESS REPORT

-- CONTRACTOR --

Project: _____ Date: _____ M T W Th F

Crew: _____ Supervisor: _____ Hours: _____ to _____

Equipment: _____

_____ down from _____ to _____ for _____

General description of work performed, equipment/material deliveries, etc:

_____ (Attach as-built drawings as required.)

WORK items approved: _____

Problems/delays and proposed or actual resolution. DOGM action required? Yes No

Visitors & purpose: _____

Temp:	20	30	40	50	60	70	80	90	100	Comments:
Sky:	fair	partly	cloudy	mostly	cloudy	cloudy	overcast	rain	snow	
Ground:	dry	wet	muddy	snow	____"	frozen				

Project is approximately ☐ on schedule

Contract expires:

_____ days behind schedule

____/____/____

_____ days ahead of schedule

Contractor: _____ ____/____/____

Proj Mgr: _____ ____/____/____

AMR Admin: _____ ____/____/____

CONTRACTOR PERFORMANCE RATING

Contractor: _____

Project: _____

Start Date: _____

End Date: _____ Duration: ____ days

Rating: Satisfactory= 1; Unsatisfactory= 0

- _____ 1. Achieved the specified level of project quality and quantity.
- _____ 2. Prompt, diligent, and systematic prosecution of work.
- _____ 3. Adequate personnel (number and skill level).
- _____ 4. Adequate equipment (number, type, and operating condition).
- _____ 5. Effective on-site management and supervision of work.
- _____ 6. Cooperation, responsiveness, and communication with inspector and project manager.
- _____ 7. Cooperation and timely response in negotiation of contract changes.
- _____ 8. Cooperation in negotiation of claims.
- _____ 9. Record of prompt payment for labor, materials, equipment, and subcontract work.
- _____ 10. On-time submission of necessary documents and reports.
- _____ 11. Compliance with all applicable federal, state, and local laws and regulations.
- _____ 12. Minimized the adverse effect of construction activities on the public and the environment.
- _____ 13. Cooperation with landowners and/or utilities.
- _____ = Total = Performance Rating

Attach explanations of all "Unsatisfactory" ratings.

Rated by: _____

Date _____

Reviewed by: _____

Date _____

A contractor with a Performance Rating (or average rating if there is more than one rating) of 9 or less fails to pre-qualify.

CONTRACTOR PERFORMANCE RATING

Page 2

Contractor: _____

Project: _____

Explanations of all "Unsatisfactory" ratings:

Item:


Item:

Appendix E
Standard Mine Closure Design Drawings

APPENDIX E

STANDARD MINE CLOSURE DESIGN DRAWINGS

Sheet E1	Adit Backfill Closure
Sheet E2	Shaft Backfill Closure
Sheet E3	Black Wall Closure
Sheet E4	Native Stone Wall Closure
Sheet E5	Wall and Backfill Closure
Sheet E6	Bat Gate Closure
Sheet E7	Bat Gate Closure Details
Sheet E8	Bat Gate With Door Closure
Sheet E9	Bat Gate With Door Closure Details
Sheet E10	CMP Bat Gate Closure
Sheet E11	CMP Bat Gate Closure Details
Sheet E12	CMP/Rebar Closure
Sheet E13	CMP/Rebar Closure Details
Sheet E14	Rebar Shaft Grate Closure
Sheet E15	Rebar Shaft Grate (With I-Beam)
Sheet E16	Rebar Shaft Grate Grade Beam Details
Sheet E17	Rebar Shaft Grate (Pinned)
Sheet E18	One-way Trap Door Closure Details



UTAH
NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

MINE RECLAMATION PROJECT


ADIT BACKFILL CLOSURE


Scale: as noted

Design: LAA Drafting: JCR

Refer to Spec Section 0253

Sheet E1 of E18






UTAH
NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program


MINE RECLAMATION PROJECT

SHAFT BACKFILL CLOSURE	
Scale: as noted	Design: LAA Drafting: JCR
Refer to Spec Section 0253	Sheet E2 of E18

TYPICAL ELEVATION




TYPICAL SECTION



CONCRETE FOOTER AND REBAR ANCHOR PINS MAY BE OMITTED WITH OWNER'S APPROVAL WHERE THE SILL IS COMPETENT ROCK

PILASTER DETAIL



UTAH
NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

MINE RECLAMATION
PROJECT

BLOCK WALL CLOSURE

Scale: as noted


Design: LAA Drafting: JCR

Refer to Spec Section 0253

Sheet E3 of E18

TYPICAL ELEVATION

TYPICAL SECTION



UTAH
NATURAL RESOURCES
Oil, Gas and Mining
 Abandoned Mine Reclamation Program

MINE RECLAMATION
PROJECT


NATIVE STONE WALL CLOSURE


Scale: as noted

Design: LAA Drafting: JCR

Refer to Spec Section 0253


Sheet E4 of E18




<div><p>UTAH NATURAL RESOURCES Oil, Gas and Mining Abandoned Mine Reclamation Program</p></div>		MINE RECLAMATION PROJECT	
WALL AND BACKFILL CLOSURE		Scale: as noted	Design: LAA Drafting: JCR
		Refer to Spec Section 0253	Sheet E5 of E18



TYPICAL ELEVATION

TYPICAL SECTION





NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)


<div><p>UTAH NATURAL RESOURCES Oil, Gas and Mining Abandoned Mine Reclamation Program</p></div>		MINE RECLAMATION PROJECT	
		BAT GATE CLOSURE	
		Scale: as noted	Design: LAA Drafting: JCR
		Refer to Spec Section 0253	Sheet E6 of E18




LOCK BOX
OBLIQUE VIEW



TYPICAL ELEVATION




TYPICAL SECTION







BARS FILET WELD ALL INTERSECTIONS

FOOTING DETAIL
PLAN VIEW


NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)


<div><p>UTAH NATURAL RESOURCES Oil, Gas and Mining Abandoned Mine Reclamation Program</p></div>		MINE RECLAMATION PROJECT	
		BAT GATE WITH DOOR CLOSURE	
		Scale: as noted	Design: LAA Drafting: DR
		Refer to Spec Section 0253	Sheet E8 of E18




NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)

<div>  <p>UTAH NATURAL RESOURCES Oil, Gas and Mining Abandoned Mine Reclamation Program</p> </div>	MINE RECLAMATION PROJECT	
	BAT GATE WITH DOOR CLOSURE DETAILS	<div> <p>Scale: as noted</p> <p>Design: LAA Drafting: DR</p> </div>
Refer to Spec Section 0253		Sheet E9 of E18




 <p>UTAH NATURAL RESOURCES Oil, Gas and Mining Abandoned Mine Reclamation Program</p>	MINE RECLAMATION PROJECT	
	CMP BAT GATE CLOSURE	
	Scale: as noted	Design: LAA Drafting: JCR
Refer to Spec Section 0253		Sheet E10 of E18


TYPICAL ELEVATION




TYPICAL SECTION



NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)

 UTAH NATURAL RESOURCES Oil, Gas and Mining Abandoned Mine Reclamation Program	MINE RECLAMATION PROJECT	
	CMP BAT GATE CLOSURE DETAILS	
	Scale: as noted	Design: LAA Drafting: JCR
Refer to Spec Section 0253		Sheet E11 of E18



MINE RECLAMATION
PROJECT



CMP/REBAR CLOSURE

Scale: as noted

Design: LAA Drafting: MES


Refer to Spec Section 0253

Sheet E12 of E18




Note: Field dimensions may vary slightly





TYPICAL SECTION



TYPICAL PLAN



Utah Oil Gas and Mining

UTAH
NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

MINE RECLAMATION
PROJECT



REBAR SHAFT GRATE CLOSURE

Scale: as noted


Design: LAA Drafting: JCR

Refer to Spec Section 0253


Sheet E14 of E18



CROSS-SECTION
12" x 12" GRADE BEAM



CROSS-SECTION
12" x 18" GRADE BEAM



Utah Oil Gas and Mining

UTAH
NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

MINE RECLAMATION
PROJECT


REBAR SHAFT GRATE GRADE BEAM DETAILS

Scale: as noted


Design: LAA Drafting: JCR

Refer to Spec Section 0253

Sheet E16 of E18



TYPICAL SECTION



TYPICAL PLAN



Utah Oil Gas and Mining

UTAH
NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

MINE RECLAMATION
PROJECT


REBAR SHAFT GRATE (PINNED)

Scale: as noted

Design: LAA Drafting: JCR

Refer to Spec Section 0253

Sheet E17 of E18



NOTE: STEEL OR PVC PIPE TO EXTENT 12 INCHES
INBY AND OUTBY WALL OR FILL MATERIAL



Utah Oil Gas and Mining

**UTAH
NATURAL RESOURCES**
Oil, Gas and Mining
Abandoned Mine Reclamation Program

**MINE RECLAMATION
PROJECT**

ONE-WAY TRAP DOOR CLOSURE DETAILS

Scale: as noted

Design: LAA Drafting: DR

Refer to Spec Section 0253

Sheet E18 of E18

Appendix F



Project Location Maps

APPENDIX F

PROJECT LOCATION MAPS

INDEX OF MAPS

Sheet 1 of 6	Project Area Location Map	Scale 1:100,000
Sheet 2 of 6	Area Detail Map Boundaries	Scale 1:86,000
Sheet 3 of 6	Soldier Creek Canyon	Scale 1:24,000
Sheet 4 of 6	Ophir Canyon	Scale 1:24,000
Sheet 5 of 6	Lion Hill	Scale 1:4,800
Sheet 6 of 6	Mercur	Scale 1:24,000



**UTAH
NATURAL RESOURCES**
Oil, Gas and Mining
Abandoned Mine Reclamation Program

OPHIR CANYON PROJECT
AMR/045/907

PROJECT AREA LOCATION MAP


1 0.5 0 1 Miles



Drawn by: ANF


Sheet 1 of 6





UTAH NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

OPHIR CANYON PROJECT
AMR/045/907



0 2,000 4,000
Feet

SOLDIER CREEK CANYON


Scale: 1 in = 2000 ft



Drawn by: ANF


Contour Interval: 40 ft

Sheet 3 of 6

Base Topography: Ophir and Lowe Peak
7.5 minute USGS Quad




 <p>UTAH NATURAL RESOURCES Oil, Gas and Mining Abandoned Mine Reclamation Program</p>	<p>OPHIR CANYON PROJECT AMR/045/907</p>		OPHIR CANYON/POSSIBLE STAGING AREAS	
			Scale: 1 in = 2000 ft	Drawn by: ANF
			Contour Interval: 40 ft	Sheet 4 of 6
			Base Topography: Ophir, Lowe Peak, Mercur and Stockton 7.5 minute USGS Quad	



UTAH NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

OPHIR CANYON PROJECT
AMR/045/907



0 400 800
Feet

LION HILL


Scale: 1 in = 400 ft

Drawn by: ANF

Contour Interval: 40 ft


Sheet 5 of 6

Base Topography: Ophir and Mercur 7.5 minute USGS Quad



UTAH NATURAL RESOURCES
Oil, Gas and Mining
Abandoned Mine Reclamation Program

OPHIR CANYON PROJECT
AMR/045/907



0 2,000 4,000
Feet

MERCUR

Scale: 1 in = 2000 ft

Drawn by: ANF

Contour Interval: 40 ft

Sheet 6 of 6

Base Topography: Ophir and Mercur 7.5 minute USGS Quad